

STATION OR BEGINNING DESCRIPTION	STATION OR ENDING DESCRIPTION	OFFSET (LT/RT)	25100630 EROSION CONTROL BLANKET (SY)	28000250 TEMPORARY EROSION CONTROL SEEDING (LB)	28000510 INLET FILTERS (EACH)	X0320139 TEMP CONST'N FENCE	X0323973 SEDIMENT CONTROL SILT FENCE	5421C012 PIPE CULVERTS, CLASS C, TYPE 1, 12" (TEMPORARY)	5421C010 PIPE CULVERTS, CLASS C, TYPE 1, 10" (TEMPORARY)	X0321193 TEMPORARY CATCH BASINS	X0323236 TEMPORARY INLETS	60500080 REMOVING CATCH BASINS TO MAINTAIN FLOW	60500090 REMOVING INLETS TO MAINTAIN FLOW	60500205 FILLING CATCH BASINS	60250200 CATCH BASINS TO BE ADJUSTED	60255500 MANHOLE TO BE ADJUSTED	60265700 VALVE VAULT TO BE ADJUSTED	X0321556 SANITARY MANHOLE TO BE ADJUSTED	Z0018500 DRAINAGE STRUCTURES TO BE CLEANED	55037500 STORM SEWER TO BE CLEANED, 6" (FT)	55037600 STORM SEWER TO BE CLEANED, 8" (FT)	55037700 STORM SEWER TO BE CLEANED, 10" (FT)	55037800 STORM SEWER TO BE CLEANED, 12" (FT)	55037900 STORM SEWER TO BE CLEANED, 15" (FT)	60255700 MANHOLE TO BE ADJUSTED W/ NEW T1F OL	60260400 CATCH BASIN TO BE ADJUSTED W/ NEW T1F OL	60260300 INLETS TO BE ADJUSTED W/ NEW T1F OL		
Pre-Stage																													
IL Route 59																													
3327+30	3337+00	LT	846	175	5	90	668	34		4	1	3		3	1	2	1	1	2	65					49		1		
3337+00	3351+00	LT	690	143	3	485	406	20		2	1	2		2			1		1		12	28		163			4	1	
3351+00	3356+28	LT	231	48	5	165	226	14		2	1		1	2		2			3					134	74	1	2		
US Route 30																													
3764+00	3770+00	LT	242	50	2		434	57		2									1								1		
Stage 1 thru 2																													
IL Route 59																													
3327+30	3337+00	RT			24	452	297	10	10										1										
3337+00	3351+00	RT	920	190	18	802	192	55	9		2			1					3										
3351+00	3356+28	RT	265	56	7	209	209	50			2								2										
US Route 30																													
3764+00	3770+00	RT	216	45	3	239	292	88																					
Stage 3 thru 5																													
IL Route 59																													
3327+30	3337+00	RT			17																								
3337+00	3351+00	RT			20																								
3351+00	3356+28				10																								
US Route 30																													
3764+00	3770+00				9																								
		Totals	3,410	707	123	2,442	2,724	328	19	10	7	5	1	8	2	*4	2	*1	13	*65	*12	*28	*346	*74	2	7	1		

* THIS TOTAL IS FOR EROSION CONTROL SCOPE OF WORK ONLY. SEE REMOVAL ITEMS SCHEDULE OF QUANTITIES FOR TOTAL QUANTITY.