

BEGIN IMPROVEMENT
STA. 3327+30

PIPE CULVERT, CLASS C, TYPE 1
12" (TEMPORARY) - 22' @ 3.0%
(SEE NOTE 6)

MATCH LINE STA. 3337+00


- | | | | |
|------------------------------|------------------------------|------------------------------|------------------------------|
| SEDIMENT CONTROL, SILT FENCE | | TEMPORARY CONSTRUCTION FENCE | |
| 1 | STA. 3327+30 TO STA. 3327+75 | 5 | STA. 3330+45 TO STA. 3330+96 |
| 2 | STA. 3327+83 TO STA. 3329+24 | 6 | STA. 3331+13 TO STA. 3331+65 |
| 3 | STA. 3329+34 TO STA. 3330+35 | 7 | STA. 3331+69 TO STA. 3332+91 |
| | | 8 | STA. 3333+20 |
| | | 9 | STA. 3356+03 TO STA. 3337+00 |

EROSION CONTROL LEGEND

- | | | | |
|--|---|--|--|
| | TEMPORARY EROSION CONTROL SEEDING AND EROSION CONTROL BLANKET | | INLET FILTER |
| | TEMPORARY EROSION CONTROL SEEDING AND EROSION CONTROL BLANKET INSTALLED IN PREVIOUS STAGE | | INLET FILTER INSTALLED IN PREVIOUS STAGE |
| | PERMANENT LANDSCAPING (SEE NOTE 3) | | PERMANENT DRAINAGE STRUCTURE NUMBER (SEE NOTE 5) |
| | TEMPORARY PAVEMENT | | PROPOSED STORM SEWER (SEE NOTE 5) |
| | SEDIMENT CONTROL, SILT FENCE (SEE NOTE 2) | | TEMPORARY PIPE CULVERT |
| | SEDIMENT CONTROL, SILT FENCE INSTALLED IN PREVIOUS STAGE | | TEMPORARY CONSTRUCTION FENCE |
| | DRAINAGE STRUCTURE TO BE CLEANED | | |

NOTES

- THE CONSTRUCTION LIMITS WILL BE STAKED BY THE ENGINEER PRIOR TO COMMENCING CONSTRUCTION. THE CONSTRUCTION LIMITS MAY BE ADJUSTED BY THE ENGINEER TO PRESERVE TREES AND NO ADDITIONAL COMPENSATION WILL BE PAID TO THE CONTRACTOR FOR CHANGED CONSTRUCTION LIMITS.
- SEDIMENT CONTROL, SILT FENCE SHALL BE ERECTED ADJACENT TO R.O.W., EASEMENT, AND CONSTRUCTION LIMITS AND AS DIRECTED BY THE ENGINEER.
- SEE LANDSCAPING PLANS FOR LANDSCAPING REQUIREMENTS.
- SEE PRE-STAGE 1 CROSS SECTIONS FOR GRADING INFORMATION.
- SEE PROPOSED DRAINAGE PLANS FOR STORM SEWER INFORMATION.
- TEMPORARY CONNECTIONS OF TEMPORARY PIPE CULVERT SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCLUDED IN THE UNIT PRICE OF "PIPE CULVERT, CLASS C, TYPE 1 OF THE SIZE SPECIFIED, (TEMPORARY)".



FILE NAME =	USER NAME = #USER#	DESIGNED - PJO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ILLINOIS ROUTE 59 EROSION CONTROL - STAGE 1 THRU 2	F.A. RTE. 338	SECTION 113 N-2	COUNTY WILL	TOTAL SHEETS 260	SHEET NO. 152	
#FILEL#	PLOT SCALE = #SCALE#	CHECKED - JCM	REVISED -			SCALE: AS SHOWN SHEET NO. 1 OF 4 SHEETS STA. 3325+00 TO STA. 3337+00		CONTRACT NO. 60E73			
	PLOT DATE = #DATE#	DATE - JANUARY 16, 2009	REVISED -					FED. ROAD DIST. NO. ILLINOIS		FAP 338 (IL RTE. 59)	