F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-023 PP	KANE	22	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO. 60G22

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: URBAN 100% FED I000-2A					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5					
40600300	AGGREGATE (PRIME COAT)	TON	24	24					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	35	35					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	465	465					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1302	1302					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	11,625	11,625					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10298	10298					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3433	3433					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	250	250					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	56635	56635					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	300	300					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	200	200					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200	200					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1475	1475					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1475	1475					
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	500	500					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	360	360					
Z0076600	TRAINEES	HOUR	500	500					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: I000-2A					

* SPECIALTY ITEM

07080

Rev. 4-9-09

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PLOT DATE: 2/5/2009

2/5/2009
pdmw:wor&PW1001Pm1,GREENDP,60G22100PlusSign.dgn