

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	URETHANE PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 4"	URETHANE PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 6"	URETHANE PAVEMENT MARKING - LINE 12"	TEMPORARY PAVEMENT MARKING - LINE 12"	URETHANE PAVEMENT MARKING - LINE 24"	TEMPORARY PAVEMENT MARKING - LINE 24"	URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	RAISED REFLECTIVE PAVEMENT MARKER
		FEET	FT	SQ FT	FT	FT	FT	FT	FT	FT	FT	SQ FT	SQ FT	EACH
68+76.00 TO 67+21.00	155.0	86.8	7.2	348.8	348.8	-	-	-	-	-	-	-	-	5.8
67+21.00 TO 59+10.00	811.0	583.9	48.7	1824.8	1824.8	-	-	-	-	-	-	-	-	10.1
59+10.00 TO 56+43.00	267.0	296.2	24.7	612.8	612.8	260.0	260.0	-	-	-	-	46.8	46.8	9.8
56+43.00 TO 55+80.00	63.0	35.3	2.9	141.8	141.8	-	-	-	-	14.0	14.0	-	-	0.8
55+80.00 TO 55+40.00	40.0	28.8	2.4	90.0	90.0	-	-	51.0	51.0	-	-	-	-	0.5
55+40.00 TO 46+04.00	936.0	673.9	56.2	2106.0	2106.0	-	-	-	-	-	-	-	-	11.7
46+04.00 TO 44+90.00	114.0	172.5	14.4	256.5	256.5	148.0	148.0	5.0	5.0	-	-	31.2	31.2	4.3
44+90.00 TO 43+58.00	132.0	73.9	6.2	165.0	165.0	-	-	31.0	31.0	-	-	15.6	15.6	4.5
43+58.00 TO 43+10.00	48.0	34.6	2.9	116.0	116.0	-	-	-	-	39.0	39.0	-	-	0.6
43+10.00 TO 30+72.00	1238.0	891.4	74.3	2785.5	2785.5	-	-	-	-	-	-	-	-	15.5
30+72.00 TO 28+70.00	202.0	225.0	18.8	454.5	454.5	199.0	199.0	-	-	65.0	65.0	46.8	46.8	7.5
28+70.00 TO 28+07.00	63.0	35.3	2.9	-	-	-	-	-	-	29.0	29.0	-	-	-
28+07.00 TO 21+50.00	657.0	473.0	39.4	1478.3	1478.3	-	-	-	-	-	-	-	-	8.2
1292+98.00 TO 1294+80.30	182.3	131.3	10.9	410.2	410.2	-	-	-	-	-	-	-	-	2.3
1294+80.30 TO 1296+80.30	200.0	224.0	18.7	450.0	450.0	200.0	200.0	-	-	-	-	46.8	46.8	7.5
1296+80.30 TO 1297+27.80	47.5	26.6	2.2	67.4	67.4	-	-	-	-	-	-	-	-	0.6
1297+27.80 TO 1308+01.50	1073.7	773.1	64.4	2415.8	2415.8	-	-	-	-	-	-	-	-	13.4
1308+01.50 TO 1310+31.50	230.0	165.6	13.8	517.5	517.5	-	-	-	-	-	-	-	-	2.9
1310+31.50 TO 1312+31.50	200.0	224.0	18.7	450.0	450.0	200.0	200.0	-	-	-	-	46.8	46.8	7.5
1312+31.50 TO 1312+90.00	58.5	32.8	2.7	87.5	87.5	-	-	-	-	-	-	-	-	0.7
1312+90.00 TO 1321+62.30	872.3	628.1	52.3	1962.7	1962.7	-	-	-	-	-	-	-	-	10.9
1321+62.30 TO 1323+92.30	230.0	165.6	13.8	517.5	517.5	-	-	-	-	-	-	-	-	2.9
1323+92.30 TO 1325+93.30	201.0	225.1	18.8	452.3	452.3	197.7	197.7	-	-	-	-	46.8	46.8	7.5
1325+93.30 TO 1326+50.00	56.7	31.8	2.6	77.5	77.5	-	-	-	-	-	-	-	-	0.7
1326+50.00 TO 1334+75.50	825.5	594.4	49.5	1857.4	1857.4	-	-	-	-	-	-	-	-	10.3
1334+75.50 TO 1337+05.50	230.0	165.6	13.8	517.5	517.5	-	-	-	-	-	-	-	-	2.9
1337+05.50 TO 1339+05.00	199.5	223.4	18.6	448.9	448.9	195.5	195.5	-	-	-	-	31.2	31.2	7.5
1339+05.00 TO 1339+62.00	57.0	31.9	2.7	83.8	83.8	-	-	-	-	-	-	-	-	0.7
1339+62.00 TO 1349+49.50	987.5	711.0	59.3	2221.9	2221.9	-	-	-	-	-	-	-	-	12.3
1349+49.50 TO 1351+79.50	230.0	165.6	13.8	517.5	517.5	-	-	-	-	-	-	-	-	2.9
1351+79.50 TO 1353+79.50	200.0	224.0	18.7	450.0	450.0	200.0	200.0	-	-	-	-	46.8	46.8	7.5
1353+79.50 TO 1354+42.50	63.0	35.3	2.9	96.8	96.8	-	-	-	-	-	-	-	-	0.8
1354+42.50 TO 1366+01.00	1158.5	834.1	174.2	2606.6	2606.6	-	-	-	-	-	-	-	-	14.5
1366+01.00 TO 1366+98.00	97.0	69.8	70.8	218.3	218.3	-	-	-	-	-	-	-	-	1.2
1366+98.00 TO 1369+78.00	280.0	294.0	211.2	630.0	630.0	231.0	231.0	-	-	-	-	115.5	115.5	9.3
1369+78.00 TO 1370+08.00	30.0	33.6	12.1	59.5	59.5	30.0	30.0	-	-	55.0	55.0	-	-	0.4
1370+08.00 TO 1370+98.00	90.0	15.2	1.3	243.0	243.0	-	-	33.0	33.0	12.0	12.0	26.0	26.0	1.1
1370+98.00 TO 1371+31.00	33.0	57.3	15.1	415.3	415.3	-	-	124.0	124.0	18.0	18.0	15.6	15.6	0.4
1371+31.00 TO 1371+85.00	54.0	30.2	21.2	243.5	243.5	-	-	-	-	-	-	-	-	0.7
1371+85.00 TO 1375+89.00	404.0	290.9	293.9	909.0	909.0	-	-	-	-	-	-	-	-	5.1
1375+89.00 TO 1378+00.00	211.0	151.9	208.0	474.8	474.8	-	-	-	-	-	-	-	-	2.6
1378+00.00 TO 1379+14.00	114.0	127.7	125.0	256.5	256.5	240.0	240.0	-	-	-	-	31.2	31.2	4.3
1379+14.00 TO 1379+59.00	45.0	50.4	49.5	101.3	101.3	126.0	126.0	-	-	-	-	15.6	15.6	1.7
1379+59.00 TO 1380+30.00	71.0	79.5	78.0	159.8	159.8	81.0	81.0	-	-	15.0	15.0	15.6	15.6	2.7
1380+30.00 TO 1380+97.00	67.0	37.5	70.5	83.8	83.8	-	-	-	-	20.0	20.0	-	-	0.8
1380+97.00 TO 1381+20.30	23.3	16.8	25.1	29.1	29.1	-	-	-	-	-	-	-	-	0.3
1381+20.30 TO 1383+92.00	271.7	195.6	103.0	67.9	67.9	-	-	-	-	-	-	-	-	3.4
TOTALS	13820	10674	2158	30480	30480	2308	2308	244	244	267	267	578	578	230

FILE NAME = c:\pwork\p\1001\STEFFENK\dms50699\	USER NAME = staffenk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING SCHEDULE RIGHT SECTION (NB)	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	tsch.74157.dgn	DRAWN -	REVISED -			824	(16-2,19X-2)RS-1,19B,19BR	Coles	49	19	
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 74157					
	PLOT DATE = 2/9/2009	DATE -	REVISED -			SCALE: N/A	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT		