

GENERAL NOTES

ALL ELEVATIONS SHOWN IN THE PLANS ARE BASED ON THE U. S. G. S DATUM.

ALL DISTURBED AREAS WITHIN THE CONSTRUCTION LIMITS SHALL BE FERTILIZED AND SEED. SEEDING SHALL BE CLASS 2 IN ACCORDANCE WITH THE SPECIAL PROVISIONS AND THE APPLICABLE ARTICLES OF SECTION 250 OF THE STANDARD SPECIFICATIONS.

EXISTING TREES, SHRUBS OR BRUSH LOCATED WITHIN THE CONSTRUCTION LIMITS SHALL BE CLEARED. THIS WORK SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.

THE CONSTRUCTION REQUIRED FOR THE CONNECTION OF THE PROPOSED 24" RCCP PIPE CULVERT TO THE EXISTING BOX CULVERT SHALL INCLUDE BUT IS NOT LIMITED TO CONSTRUCTING AN OPENING IN THE EXISTING BOX CULVERT FOR THE PROPOSED PIPE AND SEALING THE CONNECTION. THE CONNECTION TO THE CULVERT SHALL BE SEALED WITH CLASS SI CONCRETE, OR BRICK AND SUITABLE MORTAR, TO THE SATISFACTION OF THE ENGINEER. ALL COSTS ASSOCIATED WITH THE CONNECTION TO THE EXISTING BOX CULVERT SHALL BE INCLUDED IN THE PRICE FOR PIPE CULVERTS, TYPE I RCCP 24".

INDEX OF SHEETS

SHEET NO.	TITLE
1	COVER SHEET
2	GENERAL NOTES, INDEX OF SHEETS, LIST OF HIGHWAY STANDARDS
3	SUMMARY OF QUANTITIES
4-5	SCHEDULES
6	DETAILS
7-14	LOCATION 1: SN 025-0054
15-23	LOCATION 2: SN 025-0055
24-31	LOCATION 3: SN 025-0057
32-39	LOCATION 4: SN 025-0058
40-47	LOCATION 5: SN 025-0059
48-54	LOCATION 6: SN 025-0045
55-63	LOCATION 7: SN 025-0062
64-71	LOCATION 8: SN 025-0064
72-78	LOCATION 9: SN 025-0051
79-85	LOCATION 10: SN 025-0052

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED FOLLOWING THE LAST NUMBERED SHEET OF THE PLANS.

000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
280001-04	TEMPORARY EROSION CONTROL SYSTEMS
542301-02	PRECAST REINFORCED CONCRETE FLARED END SECTION
542526-02	INLET BOX TYPE F 24"
701101-02	OFF-RD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701106-02	OFF-RD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
701400-03	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701406-05	LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY
701901-01	TRAFFIC CONTROL DEVICES

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES & INDEX OF SHEET	F.A.I. RTE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\STEFFENMK\dms5465810	774314.sht:cover.dgn	DRAWN -	REVISED -			70	D-7 Safety 2009-2	Effingham	85	2
PLOT SCALE = 20,0000 1/ IN.	CHECKED -	REVISED -	CONTRACT NO. 74314							
PLOT DATE = 1/30/2009	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.					