

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	3-2, 8X-1, 4-2	SALINE	220	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES US 45 - IL 13 RELOCATION - CONTRACT 6		COUNTY:		SALINE				
		LOCATION:		URBAN				
CONSTRUCTION TYPE CODE:		FUNDING: 100% FED.		1000-2A	X081-2A	X028-2A	Y031-1F	Y007
CODE NUMBER		UNIT	TOTAL QUANTITY	ROAD FOUR LANE	BRIDGE SN 083-0060	BRIDGE SN 083-2020	TRAFFIC SIGNAL	CULVERT SN083-2013
44000100	PAVEMENT REMOVAL	SQ YD	32,316	32,316				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	9,051	9,051				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,091	2,091				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	995	995				
44002805	ISLAND REMOVAL	SQ FT	322	322				
44004250	PAVED SHOULDER REMOVAL	SQ YD	11,448	11,448				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,349	1,349				
48203029	HOT-MIX ASPHALT SHOULDERS, SUPERPAVE 8"	SQ YD	24,586	24,586				
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	3	2	1			
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1				
50105220	PIPE CULVERT REMOVAL	FOOT	776	776				
50200100	STRUCTURE EXCAVATION	CU YD	359		359			
50300100	FLOOR DRAINS	EACH	16		16			
50300225	CONCRETE STRUCTURES	CU YD	695.0		695.0			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	809.5		809.5			
50300260	BRIDGE DECK GROOVING	SQ YD	2,078		2,078			
50300280	CONCRETE ENCASMENT	CU YD	51.2		51.2			
50300300	PROTECTIVE COAT	SQ YD	2,556		2,556			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1			
50500505	STUD SHEAR CONNECTORS	EACH	4,464		4,464			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	316,230		255,890			60,340
50800515	BAR SPLICERS	EACH	242		242			
51201800	FURNISHING STEEL PILES HP 14x73	FOOT	6,356		6,356			
51202305	DRIVING PILES	FOOT	6,356		6,356			
51203800	TEST PILE STEEL HP 14x73	EACH	2		2			
51500100	NAME PLATES	EACH	3	1				1
52000110	PREFORMED JOIN STRIP SEAL	FOOT	242		242			
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12		12			
52100520	ANCHOR BOLTS 1"	EACH	24		24			
52100530	ANCHOR BOLTS 1 1/4"	EACH	48		48			
52100540	ANCHOR BOLTS 1 1/2"	EACH	24		24			
54001000	BOX CULVERT END SECTION	EACH	6					
54002020	EXPANSION BOLTS 3/4 INCH	EACH	174					114
54011103	PRECAST CONCRETE BOX CULVERT 11'X3'	FOOT	384			384		
54003000	CONCRETE BOX CULVERTS	CU YD	260					260
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	6	6				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	6	6				
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	8	8				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	15	15				
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	2	2				
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	2	2				

Rev. 4-16-09

Rev.

CHECKED BY: BWM PLOT DATE: 2/4/2009
DRAWN BY: DMS PLOT SCALE: 1/4"=30'

M:\PROJECTS\PROJ 526\ROADWAY\COMMON\ACTIVE FILES\SUM02-3526-05.dgn