



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 14, 2026

SUBJECT FAP ROUTE 362(BARRINGTON RD)
PROJECT NHPP-6C4R(185)
SECTION 2019-161-W
COOK COUNTY
CONTRACT NO. 62K33
Item No. 001, April 24th, 2026, Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices.
2. Revised the Table of Contents to the Special Provisions.
3. Revised pages 34, 114, and 115 of the Special Provisions.
4. Added page 239-249 to the Special Provisions.
5. Revised sheets 2, 4-5, 7-8, 13, 25-26, 309-310, 312, 320, 325, 328, 332-333, 336-337, 343, and 348-351 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS (D1).....	1
STATUS OF UTILITIES (D1).....	2
CONSTRUCTION LAYOUT SPECIAL FOR RESURFACING WITH ADA AND STAND ALONE ADA (D1).....	7
PUBLIC CONVENIENCE AND SAFETY (D1)	8
COMPLETION DATE PLUS WORKING DAYS (D1)	9
TEMPORARY PAVEMENT (D1).....	9
AGGREGATE SURFACE COURSE FOR TEMPORARY ACCESS (D1).....	10
HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D1)	11
WINTERIZED TEMPORARY ACCESS (D1)	18
CLEANING EXISTING DRAINAGE STRUCTURES (D1).....	19
ADJUSTMENTS AND RECONSTRUCTIONS (D1).....	19
DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (D1).....	20
ENGINEER'S FIELD OFFICE TYPE A (D1)	21
TRAFFIC CONTROL AND PROTECTION (ARTERIALS) (D1)	22
RELOCATE EXISTNG PTZ CAMERA.....	22
TRAFFIC CONTROL PLAN (D1)	23
FRICTION AGGREGATE (D1)	24
SLIPFORM PAVING (D1).....	27
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (D1).....	27
WORK ZONE TRAFFIC CONTROL (D-1 MAINTENANCE)	28
TEMPORARY INFORMATION SIGNING	29
TRAFFIC CONTROL FOR WORK ZONE AREAS.....	30
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (WITH 15 MIN FULL STOPS)	30
VIDEO VEHICLE DETECTION SYSTEM.....	31
FIBER OPTIC INTERCONNECT CENTER, 24 PORT OR 48 PORT	32
FULL-ACTUATED CONTROLLER IN EXISTING CABINET	32
FENCE REMOVAL.....	33
TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	34
PIPE UNDERDRAIN REMOVAL	34
MAST ARM SIGN PANELS	34
TRAFFIC SIGNAL GENERAL REQUIREMENTS.....	35

COILABLE NON-METALLIC CONDUIT	51
UNDERGROUND RACEWAYS	51
ROD AND CLEAN EXISTING CONDUIT	52
HANDHOLES	53
FIBER OPTIC TRACER CABLE	54
REMOVE AND REPLACE BATTERIES FOR UNINTERRUPTABLE POWER SUPPLY	55
FIBER OPTIC CABLE.....	55
SPLICE FIBER IN CABINET	56
TERMINATE FIBER IN CABINET	57
ELECTRIC CABLE	58
EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C.....	58
TRAFFIC SIGNAL POST	58
MAST ARM ASSEMBLY AND POLE	60
CONCRETE FOUNDATIONS	60
LED SIGNAL HEAD AND OPTICALLY PROGRAMMED LED SIGNAL HEAD	61
TRAFFIC SIGNAL BACKPLATE	66
DETECTOR LOOP	66
RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	68
RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	68
OUTDOOR RATED NETWORK CABLE	69
ACCESSIBLE PEDESTRIAN SIGNALS.....	69
LAYER II DATALINK SWITCH.....	78
LAYER III NETWORK SWITCH	81
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	83
EMBANKMENT I (D1).....	84
BOX CULVERT REMOVAL	85
FLY ASH RESTRICTION	85
EROSION CONTROL BLANKET (SPECIAL).....	86
MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE.....	87
PRECAST CONCRETE CAPS	88
COFFERDAM (TYPE 1) (IN-STREAM/WETLAND WORK) (D1).....	88
COFFERDAM (TYPE 2) (IN-STREAM/WETLAND WORK).....	89
PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE.....	90
PROSECUTION OF WORK.....	90
RELOCATE EXISTING TRAFFIC SIGNAL EQUIPMENT	90

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	91
PROTECTION OF EXISTING TREES	96
MULCH PLACEMENT FOR EXISTING WOODY PLANTS	101
PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE	102
REQUIRED INSPECTION OF WOODY PLANT MATERIAL	103
FAILURE TO COMPLETE PLANT CARE AND ESTABLISHMENT WORK ON TIME	103
PLANTING WOODY PLANTS.....	104
PLANTING PERENNIAL PLANTS	110
SUPPLEMENTAL WATERING	113
BIAXIAL GEOGRID.....	114
POROUS GRANULAR EMBANKMENT (SPECIAL).....	115
BAR SPLICERS, HEADED REINFORCEMENT	116
AGGREGATE SUBGRADE IMPROVEMENT (BDE).....	117
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE)	119
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES, CONCRETE, AND MORTAR (BDE)	120
COMPENSABLE DELAY COSTS (BDE).....	135
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE).....	138
EROSION CONTROL BLANKET (BDE).....	140
FUEL COST ADJUSTMENT (BDE).....	142
GUARDRAIL (BDE)	145
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE).....	145
INLET FILTERS	146
LONGITUDINAL TINING (BDE)	148
MECHANICALLY STABILIZED EARTH RETAINING WALLS (BDE)	149
PAVEMENT MARKING (BDE).....	150
PAVEMENT PATCHING (BDE)	150
PERFORMANCE GRADED ASPHALT BINDER (BDE).....	151
PREFORMED PLASTIC PAVEMENT MARKING (BDE)	156
RAISED REFLECTIVE PAVEMENT MARKERS (BDE).....	157
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE).....	157
SEEDING (BDE).....	159
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	164
SIGN PANELS AND APPURTENANCES (BDE)	167
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE).....	168
STEEL COST ADJUSTMENT (BDE).....	170

SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	171
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	172
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	172
SUBMISSION OF PAYROLL RECORDS – FEDERAL AID CONTRACT (BDE)	173
SURFACE TESTING OF PAVEMENTS – IRI (BDE)	174
SURVEYING SERVICES (BDE)	180
TEMPORARY CONCRETE BARRIER (BDE)	180
TRAINING SPECIAL PROVISIONS (BDE)	181
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION .	183
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	185
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	186
PROJECT LABOR AGREEMENT	189
STORM WATER POLLUTION PREVENTION PLAN	207
IL EPA PERMIT	223
IDNR PERMIT	228
CHAIN LINK FENCE, 4' ATTACHED TO STRUCTURE	239
404 PERMIT	240

TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)

Description. This work consists of furnishing equipment, labor, and materials to install maintaining, and removing temporary traffic barrier terminal, type 1, special (tangent) end sections for a temporary traffic stage as detailed in the plans and according to the manufacturer's specifications. All work shall be according to Section 631 and 705 of the Standard Specifications and/or as directed by the Engineer.

The terminal shall be delineated with a terminal marker-direct applied. No other guardrail delineation shall be attached to the terminal section.

Basis of Payment. This work will be paid for at the contract unit price per EACH for TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT).

PIPE UNDERDRAIN REMOVAL

Description. This work shall consist of the removal of existing underdrain pipe, fittings, and cleanouts as shown on the plans.

Basis of Payment. This work will be paid for at the contract unit price per FOOT for PIPE UNDERDRAIN REMOVAL, regardless of diameter or material, which shall include removal and disposal of all pipe, fittings, and cleanouts, all labor, materials and equipment necessary to complete the work as specified.

MAST ARM SIGN PANELS

Effective: May 22, 2002

Revised: July 1, 2015

Add the following to Article 720.02 of the Standard Specifications:

Sign stiffening channel systems shall be aluminum and meet the requirements of ASTM 6261-T5. Sign mounting banding, buckles, and buckle straps shall be manufactured from AISI 201 stainless steel.

Revised 4/14/2026

Method of Application: A spray nozzle that does not damage small plants must be used when watering all vegetation. Water shall be applied at the base of the plant to keep as much water as possible off plant leaves. An open hose may be used to water trees, shrubs, and seedlings if mulch and soil are not displaced by watering. The water shall be applied to individual plants in such a manner that the plant hole shall be saturated without allowing the water to overflow beyond the earthen saucer. Watering plants in beds shall be applied in such a manner that all plant holes are uniformly saturated without allowing the water flow beyond the periphery of the bed. Water shall slowly infiltrate into soil and completely soak the root zone. The Contractor must supply metering equipment as needed to assure the specified application rate of water.

Method of Measurement: Supplemental watering will be measured in units of 1000 gallons of water applied as directed.

Basis of Payment: This work will be paid for at the contract unit price per UNIT of SUPPLEMENTAL WATERING, measured as specified. Payment will include the cost of all water, equipment and labor needed to complete the work specified herein and to the satisfaction of the Engineer.

BIAXIAL GEOGRID

This work shall consist of furnishing and installing geogrid and shall be completed in accordance with applicable portions of Section 210 of the Standard Specifications.

Materials shall meet the requirements as shown below. Shop drawings shall be submitted to the Engineer for approval prior to construction.

- Resistance to Long Term Degradation: 100%
- Junction Efficiency: 93%
- Flexural Stiffness: 2,000,000 (mg-cm)
- Resistance to UV Degradation: 100%

The allowable tensile strength of the biaxial geogrid after all reductions shall meet or exceed the Required Tensile Strength (Trp) shown on the plans. The tensile strength of the biaxial geogrid at 5% strain shall meet or exceed 1,500 lb/ft.

The aperture dimensions and the required tensile strength will be as specified in the plans. It shall be the Contractor's responsibility to inspect the geogrid to ensure it is free from any flaws or damage that may have occurred during shipping and handling. Prior to installation, the undercut surface shall be compacted, cleared of debris and shall be graded smooth. Before unrolling, the Contractor shall anchor the beginning of the roll at the center and the corners to the underlying surface using pins or anchors. The geogrid shall be manually unrolled over the prepared surface. As it is unrolled, the geogrid shall be aligned, and pulled taut with hand tension to remove wrinkles and laydown slack. Adjacent rolls shall have 3-foot overlap. The geogrid shall be manually cut where necessary. All material placed over the grid shall be done so in a manner to prevent tearing.

Revised 4/14/2026

Any geogrid damaged during installation shall be replaced by the Contractor with no additional compensation for labor or materials.

Method of Measurement. This work will be measured and paid for at the contract unit price per square yard for BIAxIAL GEOGRID.

Basis of Payment. This work shall be paid for at the contract unit price per SQUARE YARD for BIAxIAL GEOGRID, which price shall include all labor, materials, and equipment necessary to complete the work as specified herein. Any overlap of geogrid will not be measured for payment.

POROUS GRANULAR EMBANKMENT (SPECIAL)

This work will be performed in accordance with Section 207 of the Standard Specifications. This work shall consist of the furnishing, transporting, and placing of porous granular embankment at locations shown on the plans and as directed by the Engineer.

The material used for embankment shall be class B quality stone meeting the CA-8 or CA-18 gradation requirements.

Method of Measurement. This work will be measured for payment in cubic yards compacted in place, and the volume computed by the method of average end areas.

Basis of Payment. This work will be paid for at the contract unit price per CUBIC YARD for POROUS GRANULAR EMBANKMENT (SPECIAL).

Revised 4/14/2026

CHAIN LINK FENCE, 4' ATTACHED TO STRUCTURE

This work shall consist of all labor, materials and equipment necessary for the mounting of a chain link fence on retaining walls, in accordance with the details and locations shown on the plans and the requirements of Section 664 of the Standard Specifications.

All posts shall be vertical when erected; the base plate must be welded to the post at the proper angle to account for any slope along the top of the wall. The fence fabric shall be Type I, Class D and shall be in accordance with Article 1006.27 of the Standard Specifications.

The steel base plate shall meet the requirements of AASHTO M183.

Method of Measurement. Measurement shall be made along the top of the fence center to center of the end post, in feet, completed in place.

Basis of Payment. The work under this item will be paid at the contract unit price per foot for CHAIN LINK FENCE, 4' ATTACHED TO STRUCTURE.

404 PERMIT

USACE SECTION 404 PERMIT



DEPARTMENT OF THE ARMY
U.S. ARMY CORPS OF ENGINEERS, CHICAGO DISTRICT
231 SOUTH LA SALLE STREET, SUITE 1500
CHICAGO IL 60604-1437

April 8, 2026

Regulatory Branch (LRC-2024-00496)

SUBJECT: Signed Permit for the Barrington Road from Central Road to IL-62 Roadway Improvements, South Barrington, Cook County, Illinois (Latitude 42.0923°N, Longitude - 88.1412°W)

IDOT Contract 62K33

Jose Rios
Illinois Department of Transportation
201 West Center Court
Schaumburg, Illinois 60196

Dear Mr. Rios:

The U.S. Army Corps of Engineers has authorized the above-referenced project under Section 404 of the Clean Water Act, as described in your notification and as shown on "Proposed Highway Plans Route FAP 362 (Barrington Road) Central Road to IL-62", dated August 26, 2024, prepared by Ardmore Roderick. Enclosed is your copy of the executed permit which becomes effective on the date of this letter.

This determination covers only your project as described above. If the design, location, or purpose of the project is changed, you should contact this office to determine the need for further authorization. If it is anticipated that the activity as described cannot be completed within the time limits of the authorization, you must submit a request for a time extension to this office at least thirty (30) calendar days prior to the expiration date of your permit. Failure to do so will result in the District's re-evaluation of your project, which may include the issuance of a public notice.

This office is in receipt of a ledger indicating use of advance purchase credits 2.13 acres of wetland from the Grey Willows mitigation bank and 66 linear feet of stream credits from the Muirhead Springs mitigation bank.

Once you have completed your project, please sign and return the enclosed compliance certificate. If you have any questions, please contact Patrick VerHalen by telephone at (312) 846-5545, or email at Patrick.J.VerHalen@usace.army.mil.

Sincerely,
Teralyn
Pompeii
Teralyn Pompeii, Chief
Regulatory Division

Digitally signed by Teralyn
Pompeii
Date: 2025.04.08 09:45:29
-05'00'

Added 4/14/2026

Enclosure

cc:

U.S. Environmental Protection Agency (Dana Rzezniak) **Add only if interested, EPA Wetlands Section**
U.S. Environmental Protection Agency (Dean Maraldo) **Add only if interested, EPA Enforcement Maraldo.Dean@epa.gov **
U.S. Fish and Wildlife Service (Shawn Cirton) **Add only when coordinating Section7**
U.S. Coast Guard, Marine Safety Unit Chicago (LT Kyle Goetz) *Add only if interested**
Illinois Department of Natural Resources/OWR (Bill Boyd) **Add only if interested for Lake, McHenry, Cook, DuPage, Kane, or Will Counties**
Illinois Department of Natural Resources/OWR (Bill Milner) ** Add only if interested for Kendall, Grundy, Kankakee, and Iroquois Counties**
Illinois Environmental Protection Agency (Darren Gove) **Add only if individual 401 WQC required**
Illinois Department of Natural Resources (Brad Hayes) **Add only if interested**
Illinois Department of Natural Resources/OWR (Russ Flinchum/Eric Otto) **Add when within CZM for Lake Michigan**

Cook County Building and Zoning (Michael Fazio)
Metropolitan Water Reclamation District of Greater Chicago (Maureen Durkin) **include on all Cook County with wetland impacts**
DuPage County Stormwater Management (Jenna Fahey)
Kane County Division of Environmental Management (Jodie Wollnik)
Lake County Stormwater Management Commission (Brian Frank) **always include in Lake County**
Lake County Planning, Building and Development Department (Eric Steffen) **always include in Lake County**
McHenry County Department of Planning and Development (Stoyan Kolev)
Will County Land Use Department (Nicole Roedl/Alex Brumley) **include both**
Kane/DuPage SWCD (Tommy Purdom) **only if requesting SESC oversight**
McHenry-Lake County SWCD (Aidan Woltman) **only if requesting SESC oversight**
McHenry-Lake County NRCS (Spring Duffey) **only if requesting SESC oversight**
North Cook County SWCD (Rick McAndless) **only if requesting SESC oversight**
Will-South Cook SWCD (Robert Jankowski) **only if requesting SESC oversight**

City

Agent



**PERMIT COMPLIANCE
CERTIFICATION**

Permit Number: LRC-2024-00496
Permittee: Jose Rios
Illinois Department of Transportation
Date of Issuance: April 8, 2026

I hereby certify that the work authorized by the above-referenced permit has been completed in accordance with the terms and conditions of said permit and if applicable, compensatory wetland mitigation was completed in accordance with the approved mitigation plan.¹

PERMITTEE

DATE

Upon completion of the activity authorized by this permit and any mitigation required by the permit, this certification must be signed and returned to the following address:

Email to: ChicagoRequests@usace.army.mil
Subject: Compliance Certification, LRC-2024-00496

Please note that your permitted activity is subject to compliance inspections by Corps of Engineers representatives. If you fail to comply with this permit, you may be subject to permit suspension, modification, or revocation.

¹ If compensatory mitigation was required as part of your authorization, you are certifying that the mitigation area has been graded and planted in accordance with the approved plan. You are acknowledging that the maintenance and monitoring period will begin after a site inspection by a Corps of Engineers representative or after thirty days of the Corps' receipt of this certification. You agree to comply with all permit terms and conditions, including additional reporting requirements, for the duration of the maintenance and monitoring period.



DEPARTMENT OF THE ARMY

PERMIT

PERMITTEE: Jose Rios
Illinois Department of Transportation

APPLICATION: LRC-2024-00496
Barrington Road from Central Rad to IL-62 (Contract 62K33)

ISSUING OFFICE: U.S. Army Corps of Engineers, Chicago District

You are hereby authorized to perform work in accordance with the terms and conditions specified below.

Note: The term "you" and its derivatives, as used in this authorization, means the permittee or any future transferee. The term "this office" refers to the U.S. Army Corps of Engineers, Chicago District.

PROJECT DESCRIPTION: Roadway Improvements, as described in your notification and as shown on the plans titled, "Proposed Highway Plans Route FAP 362 (Barrington Road) Central Road to IL-62", dated August 26, 2024, prepared by Ardmore Roderick.

To offset project impacts, 2.13 acres of wetland credits have been deducted from those which were purchased in advance from the Grey Willows mitigation bank and 66 linear feet of stream credits deducted from those which were purchased in advanced from the Muirhead Springs mitigation bank as indicated in the mitigation credit ledger provided by IDOT on March 19, 2026.

PROJECT LOCATION: Barrington Road (FAP 362) from Central Road to Illinois Route 62 (Algonquin Road), Cook County, IL, Section 26, Township 42 N, Range 9 E (Latitude 42.0923, Longitude -88.1412).

GENERAL CONDITIONS:

1. The time limit for completing the authorized work ends five (5) years from when the Federal official, designated to act for the Secretary of the Army, has signed below. If you find that you need more time to complete the authorized activity(s), submit your request for a time extension to this office for consideration at least 60 days before the above date is reached.

- 2 -

2. You must maintain the activity authorized by this permit in good condition and in conformance with the terms and conditions of this permit. You are not relieved of this requirement if you abandon the permitted activity, although you may make a good faith transfer to a third party in compliance with General Condition 4 below. Should you wish to cease to maintain the authorized activity or should you desire to abandon it without a good faith transfer, you must obtain a modification of this permit from this office, which may require restoration of the area.
3. Please note that this site is within the aboriginal homelands of several American Indian Tribes. If any cultural, archaeological or historical resources are unearthed during activities authorized by this permit, work in that area must be stopped immediately and the Corps, State Historic Preservation Office and/or Tribal Historic Preservation Office must be contacted for further instruction. The Corps will initiate the coordination required to determine if the remains warrant a recovery effort or if the site is eligible for listing on the National Register of Historic Places.
4. If you sell the property associated with this permit, you must obtain the signature of the new owner in the space provided and forward a copy of the permit to this office to validate the transfer of this authorization.
5. You shall comply with the water quality certification issued under Section 401 of the Clean Water Act by the Illinois Environmental Protection Agency for the project. Conditions of the certification are conditions of this authorization. For your convenience, a copy of the certification is attached if it contains such conditions.
6. You must allow representatives from this office to inspect the authorized activity at any time deemed necessary to ensure that it is being accomplished in accordance with the terms and conditions of your permit.

SPECIAL CONDITIONS

Special Condition 1: This authorization is contingent upon implementing and maintaining soil erosion and sediment controls in a serviceable condition throughout the duration of the project. You shall comply with the project's soil erosion and sediment control (SESC) plans and the installation and maintenance requirements of the SESC practices on-site. You shall notify this office any changes or modifications to the approved plan set. Please be aware that field conditions during project construction may require the implementation of additional SESC measures for further protection of aquatic resources. If you fail to implement corrective measures, this office may require more frequent site inspections to ensure the installed SESC measures are acceptable. Please be aware that work authorized herein may not commence until you receive written notification from this office that your plans meet technical standards.

- 3 -

As part of the soil erosion and sediment control (SESC) process, you are required to retain a qualified Independent SESC Inspector (ISI) to review the project's SESC plans and provide a detailed narrative that explains the measures to be implemented at the project site. The ISI is also required to perform site inspections of the implemented SESC measures to ensure proper installation and regular maintenance of the approved methods.

You are required to retain a qualified Independent SESC Inspector (ISI). The following requirements apply:

- a. You shall contact this office and the ISI at least 10 calendar days prior to the preconstruction meeting so that a representative of this office may attend. The meeting agenda will include a discussion of the SESC plan and the installation and maintenance requirements of the SESC practices on the site;
- b. Prior to commencement of any in-stream work, you shall submit construction plans and a detailed narrative to this office that disclose the contractor's preferred method of cofferdam and dewatering method;
- c. The ISI will perform weekly inspections of the implemented SESC measures to ensure proper installation and regular maintenance of the approved methods. The ISI contact information form shall be submitted to this office via e-mail and/or hard copy prior to commencement of the permitted work;
- d. The ISI shall submit to the Corps an inspection report with digital photographs of the SESC measures on a weekly basis during the active and non-active phases of construction. An inspection report shall also be submitted at the completion of the project once the SESC measures have been removed and final stabilization has been completed; and
- e. Field conditions during project construction may require the implementation of additional SESC measures not included in the SESC plans for further protection of aquatic resources. You shall contact this office immediately in the event of any changes or modifications to the approved plan set or non-compliance of an existing SESC method. Upon direction of the Corps, corrective measure shall be instituted at the site to resolve the problem along with a plan to protect and/or restore the impacted jurisdictional area(s). If you fail to implement corrective measures, this office may require more frequent site inspections to ensure the installed SESC measures are acceptable.

Special Condition 2: Upon completion of "For Construction" plans and construction documents and upon completion of As-Built Plans, the Applicant will provide a copy of the documents to ensure the proposed impacts have not changed from the documents reviewed for this authorization.

Special Condition 3: You are responsible for all work authorized herein and for ensuring that all contractors are aware of the terms and conditions of this authorization.

Special Condition 4: A copy of this authorization must be present at the project site during all phases of construction.

Added 4/14/2026

- 4 -

Special Condition 5: You shall notify this office of any proposed modifications to the project, including revisions to any of the plans or documents cited in this authorization. You must receive approval from this office before work affected by the proposed modification is performed.

Special Condition 6: You shall notify this office prior to the transfer of this authorization and liabilities associated with compliance with its terms and conditions. The transferee must sign the authorization in the space provided and forward a copy of the authorization to this office.

Special Condition 7: Work in the waterway should be timed to take place during low or no-flow conditions. Low flow conditions are flow at or below the normal water elevation.

Special Condition 8: The plan will be designed to allow for the conveyance of the 2-year peak flow past the work area without overtopping the cofferdam. The Corps has the discretion to reduce this requirement if documented by the applicant to be infeasible or unnecessary.

Special Condition 9: Water shall be isolated from the in-stream work area using a cofferdam constructed of non-erodible materials (steel sheets, aqua barriers, rip rap and geotextile liner, etc.). Earthen cofferdams are not permissible.

Special Condition 10: The cofferdam must be constructed from the upland area and no equipment may enter flowing water at any time. If the installation of the cofferdam cannot be completed from shore and access is needed to reach the area to be coffered, other measures, such as the construction of a causeway, will be necessary to ensure that equipment does not enter the water. Once the cofferdam is in place and the isolated area is dewatered, equipment may enter the coffered area to perform the required work.

Special Condition 11: If bypass pumping is necessary, the intake hose shall be placed on a stable surface or floated to prevent sediment from entering the hose. The bypass discharge shall be placed on a non-erodible, energy dissipating surface prior to rejoining the stream flow and shall not cause erosion. Filtering of bypass water is not necessary unless the bypass water has become sediment-laden as a result of the current construction activities.

Special Condition 12: During dewatering of the coffered work area, all sediment-laden water must be filtered to remove sediment. Possible options for sediment removal include baffle systems, anionic polymers systems, dewatering bags, or other appropriate methods. Water shall have sediment removed prior to being re-introduced to the downstream waterway. A stabilized conveyance from the dewatering device to the waterway must be identified in the plan. Discharge water is considered clean if it does not result in a visually identifiable degradation of water clarity.

- 5 -

Special Condition 13: The portion of the side slope that is above the observed water elevation shall be stabilized as specified in the plans prior to accepting flows. The substrate and toe of slope that has been disturbed due to construction activities shall be restored to proposed or pre-construction conditions and fully stabilized prior to accepting flows.

Further Information:

1. Congressional Authorities. You have been authorized to undertake the activity described above pursuant to:

() Section 10 of the Rivers and Harbors Act of 1899 (33 U.S.C. 403).

(x) Section 404 of the Clean Water Act (33 U.S.C. 1344).

() Section 103 of the Marine Protection, Research and Sanctuaries Act of 1972 (33 U.S.C. 1413).

2. Limits of this Authorization.

a. This permit does not obviate the need to obtain other federal, state, or local authorizations required by law.

b. This permit does not grant any property rights or exclusive privileges.

c. This permit does not authorize any injury to the property or rights of others.

d. This permit does not authorize interference with any existing or proposed Federal project.

3. Limits of Federal Liability. The Federal Government does not assume any liability for the following:

a. Damages to the permitted project or uses thereof as a result of other permitted or unpermitted activities or from natural causes.

b. Damages to the permitted project or uses thereof as a result of current or future activities undertaken by or on the behalf of the United States in the public interest.

c. Damages to persons, property, or to other permitted or unpermitted activities or structures caused by the activity authorized by this permit.

d. Design or construction deficiencies associated with the permitted work.

e. Damage claims associated with any future modifications, suspension, or revocation of this permit.

Added 4/14/2026

- 6 -

4. Reliance on Applicant's Data: The determination of this office that issuance of this permit is not contrary to the public interest was made in the reliance on the information you provided.

5. Reevaluation of Permit Decision. The office may reevaluate its decision on this permit at any time the circumstances warrant. Circumstances that could require a reevaluation include, but are not limited to, the following:


- a. You fail to comply with the terms and conditions of this permit.
- b. The information provided by you in support of your permit application proves to have been false, incomplete, or inaccurate (see 4 above).
- c. Significant new information surfaces which this office did not consider in reaching the original public interest decision.

Such a reevaluation may result in a determination that it is appropriate to use the suspension, modification, and revocation procedures contained in 33 CFR 325.7 or enforcement procedures such as those contained in 33 CFR 326.4 and 326.5. The referenced enforcement procedures provide for the issuance of an administrative order requiring you to comply with the terms and conditions of your permit and for the initiation of legal action where appropriate. You will be required to pay for any corrective measures ordered by this office, and if you fail to comply with such directive, this office may in certain situations (such as those specified in 33 CFR 209.170) accomplish the corrective measures by contract or otherwise and bill you for the cost.

6. Extensions. General Condition 1 established a time limit for the completion of the activity authorized by this permit. Unless there are circumstances requiring either a prompt completion of the authorized activity or a reevaluation of the public interest decision, the Corps will normally give favorable consideration to a request for an extension of this time limit.

- 7 -

Your signature below, as permittee, indicates that you accept and agree to comply with the terms and conditions of this authorization.


PERMITTEE _____ DATE 4/1/2026
Jose Rios
Illinois Department of Transportation

LRC-2024-00496
Corps Authorization Number

This authorization becomes effective when the Federal official, designated to act for the Secretary of the Army, has signed below.

Teralyn Pompeii Digitally signed by Teralyn Pompeii
Date: 2026.04.08 09:53:48 -05'00'
For and on behalf of _____ DATE 8 April 2026
Colonel Kenneth P. Rockwell
Commander, Chicago District

If the structures or work authorized by this authorization are still in existence at the time the property is transferred, the terms and conditions of this authorization will continue to be binding on the new owner(s) of the property. To validate the transfer of this authorization and the associated liabilities associated with compliance with its terms and conditions, have the transferee sign and date below. The document shall be attached to a copy of the permit and submitted to the Corps.

LRC-2024-00496
CORPS PROJECT NUMBER

TRANSFEEEE DATE _____

ADDRESS

TELEPHONE