



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 13, 2026

SUBJECT FAP Route 333 (ILL 120/Elm St.)
Project NHPP-AU8W(267)
Section 2025-1094-RS
McHenry County
Contract No. 80B20

Item No. 019, April 24th, 2026, Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices.
2. Revised page ii of the Table of Contents of the Special Provisions.
3. Added pages 104-107 to the Special Provisions.
4. Revised sheet 3 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

UP'S RIGHT OF ENTRY INSTRUCTIONS TO THE CONTRACTOR	48
UP RR ROE APPLICATION	49
TRAFFIC CONTROL AT AT-GRADE RR CROSSINGS	50
DRILLED SHAFTS	50
CONSTRUCTION REQUIREMENTS	53
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES, CONCRETE, AND MORTAR (BDE)	61
COMPENSABLE DELAY COSTS (BDE)	78
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	81
PAVEMENT MARKING (BDE)	83
PAVEMENT PATCHING (BDE)	84
PREFORMED PLASTIC PAVEMENT MARKING (BDE)	84
RAISED REFLECTIVE PAVEMENT MARKERS (BDE)	85
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	86
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE)	87
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	91
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	92
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	93
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	93
SUBMISSION OF PAYROLL RECORDS – FEDERAL AID CONTRACT (BDE)	94
SURVEYING SERVICES (BDE)	96
TRAINING SPECIAL PROVISIONS (BDE)	96
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION	99
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	101
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	101

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	104
---	-----



REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less. △

Soil Disposal Analysis. When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

Intersection of IL 120 (Elm Street) and Park Lane Avenue, McHenry, McHenry County

- All excavation planned at the northwest quadrant and northeast quadrant at the intersection of IL 120 (Elm Street) and Park Lane Avenue. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 120 (Elm Street) and N. Scully Drive, McHenry, McHenry County

- All excavation planned at the southwest quadrant and southeast quadrant at the intersection of IL 120 (Elm Street) and N. Scully Drive. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 120 (Elm Street) and Beach Road (north leg), McHenry, McHenry County

- All excavation planned at the northwest quadrant and northeast quadrant at the intersection of IL 120 (Elm Street) and Beach Road (north leg). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 120 (Elm Street) and Beach Road (south leg), McHenry, McHenry County

- All excavation planned at the southwest quadrant and southeast quadrant at the intersection of IL 120 (Elm Street) and Beach Road (south leg). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 120 (Elm Street) and Highway Avenue, McHenry, McHenry County

- All excavation planned at the northwest quadrant and northeast quadrant at the intersection of IL 120 (Elm Street) and Highway Avenue. The Engineer has determined this material meets

the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 120 (Elm Street) and Meadow Lane, McHenry, McHenry County

- All excavation planned at the northwest quadrant and southeast quadrant at the intersection of IL 120 (Elm Street) and Meadow Lane. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.
- All excavation planned at the northeast quadrant and southwest quadrant at the intersection of IL 120 (Elm Street) and Meadow Lane. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 120 (Elm Street) and N. Ramble Road, McHenry, McHenry County

- All excavation planned at the northwest quadrant and northeast quadrant at the intersection of IL 120 (Elm Street) and N. Ramble Road. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

IL 120 (Elm Street) and East Entrance of McDonald's (stop controlled), McHenry, McHenry County

- All excavation planned at the southwest quadrant and southeast quadrant at IL 120 (Elm Street) and the east entrance of McDonald's (stop controlled). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

IL 120 (Elm Street) and West Entrance of McHenry Shopping Center Plaza (stop controlled), McHenry, McHenry County

- All excavation planned at the northwest quadrant and northeast quadrant at IL 120 (Elm Street) and the west entrance of McHenry Shopping Center Plaza (stop controlled). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 120 (Elm Street) and Oak Drive, McHenry, McHenry County

- All excavation planned at the northwest quadrant, northeast quadrant, southwest quadrant, and southeast quadrant at the intersection of IL 120 (Elm Street) and Oak Drive. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

IL 120 (Elm Street) and East Entrance of Jewel-Osco (stop controlled), McHenry, McHenry County

- All excavation planned at the northwest quadrant and northeast quadrant at IL 120 (Elm Street) and the east entrance of Jewel-Osco (stop controlled). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 120 (Elm Street) and Front Royal Drive, McHenry, McHenry County

1

- All excavation planned at the southwest quadrant and southeast quadrant at the intersection of IL 120 (Elm Street) and Front Royal Drive. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 120 (Elm Street) and W. Crystal Lake Road, McHenry, McHenry County

- All excavation planned at the northwest quadrant, northeast quadrant, southwest quadrant, and southeast quadrant at the intersection of IL 120 (Elm Street) and W. Crystal Lake Road. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 120 (Elm Street) and Union Pacific railroad crossing, McHenry, McHenry County

- All excavation planned at the northwest quadrant, northeast quadrant, southwest quadrant, and southeast quadrant at the intersection of IL 120 (Elm Street) and the Union Pacific railroad crossing. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 120 (Elm Street) and Freund Avenue, McHenry, McHenry County

- All excavation planned at the northwest quadrant and northeast quadrant at the intersection of IL 120 (Elm Street) and Freund Avenue. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

IL 120 (Elm Street) and Driveway Entrance of McHenry Municipal Parking, McHenry, McHenry County

- All excavation planned at the southwest quadrant and southeast quadrant at IL 120 (Elm Street) and the driveway entrance of McHenry Municipal Parking. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 120 (Elm Street) and Richmond Road, McHenry, McHenry County

- All excavation planned at the northeast quadrant and southeast quadrant at the intersection of IL 120 (Elm Street) and Richmond Road. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 120 (Elm Street) and Green Street, McHenry, McHenry County

- All excavation planned at the northwest quadrant, northeast quadrant, southwest quadrant, and southeast quadrant at the intersection of IL 120 (Elm Street) and Green Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank



(LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites:

None

