SUMMARY OF QUANTITIES

Code No.	Item	Unit	Total Quantity	TYPE CODE: IL-120 MCHENRY ROADWAY 80% FED 20% STATE 0005	IL-120 MCHENRY ROADWAY 100% STATE 0005	IL-120 MCHENRY TRAFFIC SIGNALS 80% FED 20% STATE 0021	URBAN	URBAN	URBAN
20200100	EARTH EXCAVATION	CU YD	~~106~~ 110	~~106~~ 110					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	513.9	513.9					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5.1	5.1					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	5.1	5.1					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5.1	5.1					
25200110	SODDING, SALT TOLERANT	SQ YD	513.9	513.9					
25200200	SUPPLEMENTAL WATERING	UNIT	4.1	4.1					
42001300	PROTECTIVE COAT	SQ YD	878.3	878.3					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	6233	6233					
42400800	DETECTABLE WARNINGS	SQ FT	717	717					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2.7	2.7					
44000600	SIDEWALK REMOVAL	SQ FT	6233	6233					
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	1188	1188					
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	964	964					
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	~~700~~ 892	~~700~~ 892					
44201299	DOWEL BARS 1 1/2"	EACH	~~4585~~ 4664	~~4585~~ 4664					
44213200	SAW CUTS	FOOT	~~11888~~ 12170	~~11888~~ 12170					
44213202	TIE BARS 1"	EACH	~~400~~	~~400~~					
44213204	TIE BARS 3/4"	EACH	440	440					
45200100	JOINT OR CRACK ROUTING (PC CONCRETE PAVEMENT AND SHOULDER)	FOOT	~~82056~~ 79688	~~82056~~ 79688					
45200300	JOINT OR CRACK FILLING	POUND	~~28672~~ 22767	~~28672~~ 22767					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1					

REVISE ITEM 1

SUMMARY OF QUANTITIES

	Code No.	Item	Unit	Total Quantity	TYPE CODE: IL-120 MCHENRY ROADWAY 80% FED 20% STATE 0005	IL-120 MCHENRY ROADWAY 100% STATE 0005	IL-120 MCHENRY TRAFFIC SIGNALS 80% FED 20% STATE 0021	URBAN	URBAN	URBAN
	60255500	MANHOLES TO BE ADJUSTED	EACH	5	5					
	60260100	INLETS TO BE ADJUSTED	EACH	5	5					
	60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	10	10					
	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5					
	60404950	FRAMES AND GRATES, TYPE 24	EACH	5	5					
	60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5					
	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5					
	60920012	PIPE CULVERTS TO BE CLEANED 12"	FOOT	200		200				
	60920015	PIPE CULVERTS TO BE CLEANED 15"	FOOT	200		200				
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	~~106~~ 110	~~106~~ 110					
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	~~1~~ 2	~~1~~ 2					
*	66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	1					
*	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1					
*	66901006	REGULATED SUBSTANCES MONITORING	CAL DA	5	5					
	67100100	MOBILIZATION	L SUM	1	1					
	70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	LSUM	1	1					
	70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1					
	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
	70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1					
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
	70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1					
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	70	70					
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
	70107025	CHANGEABLE MESSAGE SIGN	CAL DA	246	246					

REVISE ITEM 1

REVISE ITEM

*** = SPECIALTY ITEM**

MODEL: SOQ-1 [Sheet]
FILE NAME: c:\pw_work\pwidot\syed.a.rizvi@illinois.gov\d1153888\D17325-sht-SOQ.dgn

USER NAME = syed.rizvi	DESIGNED -	REVISED - SR 2/23/26	
	DRAWN -	REVISED - 1 SR 4/10/26	
	CHECKED -	REVISED -	
PLOT DATE = 2/2/2026	DATE -	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL. ROUTE 120 (ELM ST.) (WEST OF MARTIN RD. TO GREEN ST.)

SCALE: | SHEET 1 OF 3 SHEETS | STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
333	2025-1094-RS	MCHENRY	43	3

CONTRACT NO. 80B20

ILLINOIS | FED. AID PROJECT