



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 15, 2026

SUBJECT FAI Route 94 (I-90/I-94)
Project BR-TP37(636)
Section (0404.2-1B) BD,BJR 25
Cook County
Contract No. 80B62

Item No. 030, April 24th, 2026, Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices.
2. Revised pages i-ii of the Table of Contents of the Special Provisions.
3. Added page 105 to the Special Provisions.
4. Revised sheet 7 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF IMPROVEMENT	1
DESCRIPTION OF IMPROVEMENT	1
MAINTENANCE OF ROADWAYS (D1)	2
STATUS OF UTILITIES (D1)	2
PUBLIC CONVENIENCE AND SAFETY (D1)	4
HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D1)	5
DETECTABLE WARNINGS (SPECIAL)	12
ADJUSTMENTS AND RECONSTRUCTIONS (D1)	13
CURB OR COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT (D1)	14
ENGINEER'S FIELD OFFICE TYPE A (D1)	15
TRAFFIC CONTROL AND PROTECTION (ARTERIALS) (D1)	15
TRAFFIC CONTROL PLAN (D1)	16
FRICTION AGGREGATE (D1)	17
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (D1)	19
KEEPING THE EXPRESSWAY OPEN TO TRAFFIC	21
FAILURE TO OPEN TRAFFIC LANES TO TRAFFIC	23
TEMPORARY INFORMATION SIGNING	23
APPROACH SLAB REPAIR	24
BRIDGE SIDEWALK REPAIR	25
HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	28
PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	28
METHYL METHACRYLATE PAVEMENT COLORIZATION, VARIOUS COLORS	28
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	30
TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	31
DIAMOND GRINDING AND SURFACE TESTING BRIDGE SECTIONS	35
BRIDGE DECK GROOVING (LONGITUDINAL)	40
BRIDGE DECK CONCRETE OVERLAYS	41
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES, CONCRETE, AND MORTAR (BDE)	49
COMPENSABLE DELAY COSTS (BDE)	64
CONCRETE SEALER (BDE)	67
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	67
DECK SLAB REPAIR	69
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE)	73
INLET FILTERS	74
PAVEMENT MARKING (BDE)	76

PERFORMANCE GRADED ASPHALT BINDER (BDE)	77
PREFORMED PLASTIC PAVEMENT MARKING (BDE)	82
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE).....	83
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	84
SIGN PANELS AND APPURTENANCES (BDE)	88
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	89
STEEL COST ADJUSTMENT (BDE)	90
STRUCTURAL REPAIR OF CONCRETE (BDE).....	92
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	98
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	99
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	99
SUBMISSION OF PAYROLL RECORDS – FEDERAL AID CONTRACT (BDE)	100
SURVEYING SERVICES (BDE)	101
TEMPORARY CONCRETE BARRIER (BDE)	102
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....	102
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	102
WORKING DAYS (BDE)	104
DELINEATORS (SPECIAL)	105
DELINEATOR REMOVAL	105

DELINEATORS (SPECIAL)

Description. Work under this item shall be performed according to Section 635 of the Standard Specifications for Road and Bridge Construction, except as herein modified. Work under this item shall consist of all labor, equipment, and materials necessary to install a longitudinal surface mounted flexible delineator system at the locations determined by the Engineer.

General Requirements. The Contractor shall install the flexible delineator system using the salvaged delineator components and any additional fastening hardware and/or anchor bolts necessary to complete the work.

The system shall be MASH 2016 crash tested and test results accepted by FHWA.

Wherever base units are to be secured onto concrete bridge deck, the base units shall be installed without the need to drill holes into the deck. The method of attachment shall be per the manufacturer's recommendations for this type of installation. Adhesives shall meet the requirements of Section 1027 of the Standard Specification and shall be approved by the Engineer prior to the start of the installation.

Where interconnected base separator units are used, combined segments shall have a maximum length of 40', and a 2' gap shall be provided between combined segments to provide for drainage.

Method of Measurement. Delineator (Special) will be measured for payment per each vertical delineator bollard. The base units will not be measured separately for payment.

Basis of Payment. This work will be paid for at the contract unit price per EACH for DELINEATORS (SPECIAL).

DELINEATOR REMOVAL

Description. This work shall consist of the removal and salvage of the surface mounted flexible delineator system at the locations determined by the Engineer. Removal shall include both the vertical delineator bollards and base units. The Contractor shall then salvage the delineator components throughout the duration of grinding and overlay operations until the delineators are to be reinstalled.

Method of Measurement. This work will be measured for payment per each vertical delineator bollard removed. The removal of base units will not be measured separately for payment.

Basis of Payment. This work shall be paid for at the contract unit price per EACH for DELINEATOR REMOVAL.

