

MODEL: SOQ_1 [Sheet]
FILE NAME: c:\pw_work\pwwd\qarum\1056841\11326-sh-SOQ.dgn

SUMMARY OF QUANTITIES					TYPE CODE					
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
					DESIGNED OVERLAY	TS IMPROV.	DESIGNED OVERLAY			
					80% FED 20% STATE	80% FED 20% STATE	100% STATE			
	0005	0021	0005							
	CODE NO.	ITEM	UNIT	TOTAL QUANTITY						
*	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	161	161					
*	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	69	69					
*	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	5	5					
	20200100	EARTH EXCAVATION	CU YD	4325	4325					
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	255	255					
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	775	775					
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	290	290					
	21400100	GRADING AND SHAPING DITCHES	FOOT	250	250					
	25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25					
	25003115	INTERSEEDING, CLASS 1B	ACRE	0.50	0.50					
	25003312	INTERSEEDING, CLASS 4A	ACRE	5.90	5.90					
	25100630	EROSION CONTROL BLANKET	SQ YD	150	150					
	25200110	SODDING, SALT TOLERANT	SQ YD	290	290					
	28000400	PERIMETER EROSION BARRIER	FOOT	450	450					
	30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	255	255					
	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	7710	7710					
	40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	17350	17350					
	40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	42700	42700					
	40600370	LONGITUDINAL JOINT SEALANT	FOOT	30550	30550					
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	95	95					
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	405	405					

MODEL: SOQ 2 [Sheet]
FILE NAME: c:\pw_work\pwid\qanum\1056841D\11326-sh-SOQ.dgn

SUMMARY OF QUANTITIES					TYPE CODE					
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
					DESIGNED OVERLAY	TS IMPROV.	DESIGNED OVERLAY			
					80% FED 20% STATE	80% FED 20% STATE	100% STATE			
	0005	0021	0005							
CODE NO.	ITEM	UNIT	TOTAL QUANTITY							
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	19	19						
63200310	GUARDRAIL REMOVAL	FOOT	2475	2475						
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	125	125						
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	4325	4325						
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	10	10						
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	1						
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1						
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	30	30						
67100100	MOBILIZATION	L SUM	1	1						
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1						
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1						
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1						
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1						
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1						
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1						
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10						
70300100	SHORT TERM PAVEMENT MARKING	FOOT	261680	261680						
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	21810	21810						
70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	SQ FT	2850	2850						
70300221	TEMPORARY PAVEMENT MARKING - LINE 4"- PAINT	FOOT	196260	196260						
70300241	TEMPORARY PAVEMENT MARKING - LINE 6"- PAINT	FOOT	18240	18240						

MODEL: SOQ_3 [Sheet]
FILE NAME: c:\p_w\work\p\td\qarum\1056841\11326-sh-SOQ.dgn

SUMMARY OF QUANTITIES					TYPE CODE					
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
					DESIGNED OVERLAY	TS IMPROV.	DESIGNED OVERLAY			
					80% FED 20% STATE	80% FED 20% STATE	100% STATE			
	0005	0021	0005							
CODE NO.	ITEM	UNIT	TOTAL QUANTITY							
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4		4					
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	205		205					
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	70		70					
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1469		1469					
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	55		55					
* 87900200	DRILL EXISTING HANDHOLE	EACH	10		10					
* 88600100	DETECTOR LOOP, TYPE I	FOOT	2857		2857					
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1720		1720					
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4		4					
* 89502380	REMOVE EXISTING HANDHOLE	EACH	9		9					
* K0026700	TREE CARE	EACH	23	23						
* K0029624	WEED CONTROL, TEASEL	GALLON	0.50	0.50						
* K0036120	MULCH PLACEMENT 4"	SQ YD	250	250						
* X0320050	CONSTRUCTION LAYOUT (SPECIAL)	L SUM	1	1						
* X0325222	WEED CONTROL, BASAL TREATMENT	GALLON	12	12						
* X0327120	WEED CONTROL, NATIVE LANDSCAPE ENHANCEMENT	ACRE	5.90	5.90						
* X1400367	PEDESTRIAN SIGNAL POST, 10 FT.	EACH	1		1					
* X2010350	TREE REMOVAL, ACRES (SPECIAL)	ACRE	5.36	5.36						
* X2010516	SELECTIVE CLEARING	UNIT	19.7	19.7						
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	120	120						
* X2100002	PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE	UNIT	4	4						