



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 7, 2026

SUBJECT: FAU 3512 (US 14)
Section 21-00174-00-BR (Mount Prospect)
Cook County
Contract No. 61M15
Item 044
April 24, 2026 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices**
- 2. Revised Plan Sheets 11, 25, 31, 105-108, 121, 123, 124, 126, & 134**
- 3. Revised Special Provision Index**
- 4. Added page 110A to the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

INDEX OF SPECIAL PROVISIONS

AVAILABLE REPORTS (D1 LR)..... 110
PRECAST ORNAMENTAL PIER CAP.....110A
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION111
LR107-4 FORM.....113
LR1030-2 FORM.....114
LPC 663 FORM.....116

PRECAST ORNAMENTAL PIER CAP

Description.

This work shall consist of fabricating, furnishing, transporting, and installing the precast ornamental pier caps as specified herein, as shown on the plans, and as directed by the Engineer. The work shall include shop drawings, grouting, anchoring, and cleanup necessary to match the project's architectural renderings. The ornamental pier caps shall be concrete, as specified herein.

All precast concrete items shall be supplied by qualified producers. The Department will maintain a list of qualified producers.

Materials.

Precast ornamental pier cap concrete shall be Class PC according to Section 1020 of the Standard Specifications and shall have a minimum compressive strength of 4,500 PSI at 28 days with 6% to 8% air entrainment and finish as indicated in the plans. Color to be approved by the Engineer prior to fabrication. Dimensions to be as shown on the plans.

Provide high strength nonshrink grout suitable for exterior precast architectural concrete work and according to Article 1024.02 of the Standard Specifications. The grout color shall be approved by the Engineer prior to use.

Dowels shall be ½" in diameter and ASTM Type 304 Stainless Steel. Epoxy bonding shall be according to Article 1025.01 of the Standard Specifications.

Method of Measurement.

This work shall be measured for payment per EACH.

Basis of Payment.

This work will be paid for at the contract unit price per EACH for PRECAST ORNAMENTAL PIER CAP.