



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 10, 2026

SUBJECT: FAU 3506 (Sheridan Road)
Section 19-00137-00-BT (Highland Park)
Lake County
Contract No. 61M41
Item 051
April 24, 2026 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices**
- 2. Revised Plan Sheets 2 & 6**
- 3. Revised Special Provision Index**
- 4. Added pages 55A & 55B to the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

INDEX OF SPECIAL PROVISIONS

SANITARY MANHOLES TO BE ADJUSTED OR RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID.....	43
DOMESTIC WATER METER VAULT TO BE ADJUSTED (SPECIAL)	44
FAILURE TO COMPLETE PLANT CARE AND ESTABLISHMENT WORK ON TIME	46
PROTECTION OF EXISTING TREES.....	47
PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE.....	51
SUPPLEMENTAL WATERING	52
WASHOUT BASIN	54
GEOTEXTILE FABRIC	55
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	55A
TEMPORARY INFORMATION SIGNING	56
TRAFFIC CONTROL AND PROTECTION (ARTERIALS) (D1)	57
DETOUR	58
BRICK FACADE.....	59
FRICTION AGGREGATE (D1)	61
HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D1)	64
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (D1).....	72
MINERALIZED CARBON DIOXIDE CONCRETE (D-1)	74
AVAILABLE REPORTS (D1 LR).....	76
LOCAL ROAD SPECIAL PROVISION FOR INSURANCE LR107-4.....	77
LOCAL ROAD SPECIAL PROVISION FOR LOCAL QUALITY ASSURANCE/QUALITY MANAGEMENT QC/QA (LR1030-2)	78

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either "uncontaminated soil", hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Soil Disposal Analysis. When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

Site 3839V-8: Residences, 767, 777, 803 & 819 Sheridan Road and 99 Roger Williams Avenue, Highland Park, Lake County

- Station 114+40 to Station 121+57 (CL Sheridan Road), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Site 3839V-6: Residence, 855 Sheridan Road, Highland Park, Lake County

- Station 121+57 to Station 124+95 (CL Sheridan Road), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Site 3839V-5: Rosewood Park and Rosewood Beach, Highland Park, Lake County

- Station 124+95 to Station 126+55 (CL Sheridan Road), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Site 3839V-3: Residences, 999 Dean Avenue and 950, 960, 970, 990, 1000, 1002, 1004, 1008, 1010, 1014, 1016 & 1024 Sheridan Road and 89 & 111 Cary Avenue, Highland Park, Lake County

- Station 123+00 to Station 143+75 (CL Sheridan Road), 0 to 35 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Site 3839V-2: Residences, 909, 919, 933, 943, 959, 975, 985, 999 & 1011 Sheridan Road and 25, 54, 80, 94, 104 & 120 Oakmont Road, Highland Park, Lake County

- Station 126+55 to Station 143+55 (CL Sheridan Road), 0 to 80 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Site 3839V-1: Residence, 1044 Sheridan Road and 166 Cedar Avenue, Highland Park, Lake County

- Station 143+80 to Station 144+30 (CL Sheridan Road), 0 to 45 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites:

None