

DATE PLOTTED = 4/8/2026 2:17:25 PM
PEN TABLE = 0021133.16.tbl
PLOT CONFIG = CG-PDF.plt
MODEL SHOWN NAMES
FILE NAME: I:\PROJ\0021133.16\CADD\Sheet\Phase II\MainSheet\0021133.16-Std-Index.dgn

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS AND STANDARDS
3 - 7	SUMMARY OF QUANTITIES
8 - 9	TYPICAL SECTIONS
10	SCHEDULE OF QUANTITIES
11	PROPOSED WATER/SEWER STRUCTURE SCHEDULE
12 - 13	ALIGNMENT, TIES AND BENCHMARKS
14 - 16	EXISTING CONDITIONS AND REMOVAL PLAN
17 - 22	PROPOSED PLAN AND PROFILE
23 - 25	MAINTENANCE OF TRAFFIC
26 - 32	EROSION CONTROL AND LANDSCAPING PLAN
33 - 36	PLAT OF HIGHWAYS
37 - 38	BLOCK WALL DETAILS
39 - 42	ADA RAMP DETAILS
43	MISCELLANEOUS DETAILS
44 - 64	STRUCTURAL PLAN
65 - 66	HIGHLAND PARK STANDARD DETAILS
67 - 70	IDOT DISTRICT 1 STANDARD DETAILS
71 - 100	CROSS SECTIONS

HIGHWAY STANDARDS

STANDARD NO.	LIST OF DESCRIPTION
000001-09	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
280001-07	TEMPORARY EROSION CONTROL SYSTEMS
424001-12	PERPENDICULAR CURB RAMPS FOR SIDEWALKS
424006-06	DIAGONAL CURB RAMPS FOR SIDEWALKS
424011-05	CORNER PARALLEL CURB RAMPS FOR SIDEWALKS
424016-06	MID-BLOCK CURB RAMPS FOR SIDEWALKS
542306-03	PRECAST REINFORCED CONCRETE ELLIPTICAL FLARED END SECTION
601001-05	PIPE UNDERDRAINS
602001-02	CATCH BASIN TYPE A
602301-04	INLET TYPE A
602402-03	PRECAST MANHOLE TYPE A 5' DIAMETER
602406-11	PRECAST MANHOLE TYPE A 6' DIAMETER
602601-06	PRECAST REINFORCED CONCRETE FLAT SLAB TOP
602701-02	MANHOLE STEPS
604001-05	FRAME AND LIDS TYPE 1
604011-05	FRAME AND GRATE TYPE 3V
604036-03	GRATE TYPE 8
606001-09	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
630116	BACKSIDE PROTECTION OF GUARDRAIL
664001-02	CHAIN LINK FENCE
701006-05	OFF-RD OPERATIONS, 2L, 2W, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701311-03	LANE CLOSURE, 2L, 2W, MOVING OPERATIONS- DAY ONLY
701501-06	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701801-06	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901-11	TRAFFIC CONTROL DEVICES
704001-08	TEMPORARY CONCRETE BARRIER
720001-01	SIGN PANEL MOUNTING DETAILS
720006-04	SIGN PANEL ERECTION DETAILS
780001-05	TYPICAL PAVEMENT MARKINGS
782006-01	GUARDRAIL AND BARRIER WALL REFLECTOR MOUNTING DETAILS

IDOT DISTRICT 1 DETAILS

STANDARD NO.	LIST OF DESCRIPTION
BD-51	BENCHING DETAIL FOR EMBANKMENT WIDENING
TC-10	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
TC-13	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
TC-21	DETOUR SIGNING FOR CLOSING STATE HIGHWAYS
TC-22	ARTERIAL ROAD INFORMATION SIGN

GENERAL NOTES

- ANY REFERENCE TO THE STANDARD SPECIFICATIONS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE ILLINOIS DEPARTMENT OF TRANSPORTATION (IDOT) STANDARD SPECIFICATIONS, ADOPTED JANUARY 1, 2022 AND THE JANUARY 1, 2026 SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS.
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE.
- THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL DRIVEWAYS WITHIN THE CONSTRUCTION LIMITS AT ALL TIMES, EXCEPT DURING CONCRETE PLACEMENT AND CURING OF CURB AND SIDEWALK. WHEN DRIVEWAY ACCESS MUST BE TEMPORARILY RESTRICTED, THE CONTRACTOR SHALL PROVIDE WRITTEN NOTICE TO THE CITY AND PROPERTY OWNER AT LEAST 72 HOURS IN ADVANCE.
- HMA AND PCC DRIVEWAYS SHALL BE CONSTRUCTED WITH FLARES ACCORDING TO THE HIGHLAND PARK TYPICAL DRIVEWAY AND SIDEWALK DETAIL. BRICK PAVER DRIVES SHALL BE CONSTRUCTED TO MATCH EXISTING LAYOUT.
- THE CONTRACTOR SHALL CONTACT KALPANA KANNAN-HOSADURGA THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT KALPANA.KANNAN-HOSADURGA@ILLINOIS.GOV A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.
- DRAINAGE STRUCTURE ELEVATIONS: GRADES OF SEWER LINES WERE DETERMINED FROM AVAILABLE PLANS AND SURVEYS. ACCORDINGLY, AS DIRECTED BY THE ENGINEER, THE INVERTS OF THE PROPOSED DRAINAGE WILL BE REVISED TO MEET EXISTING FIELD CONDITIONS.
- THE TOP OF ALL STRUCTURES SHALL BE FLUSH WITH THE ADJACENT SURFACE OR AT THE INDICATED ELEVATIONS SHOWN ON THE PLANS.
- FRAME ELEVATIONS ARE GIVEN ONLY TO ASSIST IN DETERMINING THE APPROXIMATE OVERALL HEIGHT OF THE STRUCTURE. FRAMES ON ALL NEW STRUCTURES WILL BE ADJUSTED TO THE FINAL ELEVATION OF THE AREA IN WHICH THEY ARE LOCATED.
- THE APPROXIMATE LOCATION OF KNOWN UTILITIES ARE SHOWN ON THE PLANS, HOWEVER, THE CITY DOES NOT GUARANTEE ITS ACCURACY. PRIOR TO COMMENCING OPERATIONS ON THE PROJECT WHICH MAY IN ANY WAY CREATE THE POSSIBILITY OF INVOLVEMENT WITH EXISTING UTILITIES, THE CONTRACTOR SHALL CONTACT THE UTILITY INVOLVED. ADJUSTMENT OF ALL PUBLIC UTILITIES WITHIN THE LIMITS OF IMPROVEMENT WILL BE DONE BY THE RESPECTIVE OWNERS.
- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123. FOR FIELD LOCATIONS OF BURIED UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.
- ANY AGGREGATE SUBGRADE CONTAMINATED AND/OR DAMAGED BY THE CONTRACTOR'S VEHICLES AND/OR EQUIPMENT IS TO BE REMOVED AND REPLACED AS DIRECTED BY THE ENGINEER AT THE CONTRACTOR'S EXPENSE.
- BACKFILLING STORM SEWER CONSTRUCTED UNDER THE ROADWAY SPECIFIED UNDER ART. 550.07(b,c) OF THE SSRBC WILL NOT BE ALLOWED.
- THE RESIDENT ENGINEER SHALL CONTACT BRANDY KENNEDY, AREA TRAFFIC FIELD ENGINEER, AT BRANDY.KENNEDY@ILLINOIS.GOV, A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

COMMITMENTS

- SUBMIT THE ADA/PROWAG INSPECTION SUMMARY FORM (D1 PD0039) TO THE D1 ADA COORDINATOR IN PDF TO DOT.D1.ADA@ILLINOIS.GOV.
- ENSURE ALL OPERATORS, EMPLOYEES, AND CONTRACTORS WORKING IN AREAS OF INDIANA BAT, NLEB, OR TCB SUITABLE HABITAT ARE AWARE OF ALL TRANSPORTATION AGENCY ENVIRONMENTAL COMMITMENTS, INCLUDING ALL APPLICABLE AVOIDANCE AND MINIMIZATION MEASURES (AMMs)
- SHOULD THE PROJECT REQUIRE NEW/ADDITIONAL TEMPORARY OR PERMANENT LIGHTING, OR REPLACING EXISTING PERMANENT LIGHTS, ALL LIGHTING SHALL BE INSTALLED IN ACCORDANCE WITH IDOT BDE MANUAL - CHAPTER 56 AND WITH THE USFWS PBO FOR IBAT, NLEB AND TRICOLORED BAT. THIS INCLUDES THE FOLLOWING:
 - DIRECT TEMPORARY LIGHTING AWAY FROM SUITABLE HABITAT DURING THE ACTIVE SEASON.
 - WHEN INSTALLING NEW/ADDITIONAL PERMANENT LIGHTING OR REPLACING EXISTING PERMANENT LIGHTS, USE DOWNWARD-FACING, FULL CUT-OFF LENS LIGHTS (WITH SAME INTENSITY OR LESS FOR REPLACEMENT LIGHTING); OR FOR THOSE TRANSPORTATION AGENCIES USING THE BACKLIGHT UPLIGHT AND GLARE (BUG) SYSTEM DEVELOPED BY THE ILLUMINATING ENGINEERING SOCIETY,4 THE PROJECT SHOULD BE AS CLOSE TO 0 FOR ALL THREE RATINGS WITH A PRIORITY OF "UPLIGHT" OF 0 AND "BACKLIGHT" AS LOW AS PRACTICABLE.
- MODIFY ALL PHASES/ASPECTS OF THE PROJECT (E.G., TEMPORARY WORK AREAS, ALIGNMENTS) TO THE EXTENT PRACTICABLE TO AVOID TREE REMOVAL/TRIMMING IN EXCESS OF WHAT IS REQUIRED TO IMPLEMENT THE PROJECT SAFELY.
- ENSURE TREE REMOVAL/TRIMMING IS LIMITED TO THAT SPECIFIED IN PROJECT PLANS AND ENSURE THAT CONTRACTORS UNDERSTAND CLEARING LIMITS AND HOW THEY ARE MARKED IN THE FIELD (E.G., INSTALL BRIGHT COLORED FLAGGING/FENCING PRIOR TO ANY TREE REMOVAL/TRIMMING TO ENSURE CONTRACTORS STAY WITHIN CLEARING LIMITS).
- ENSURE TREE REMOVAL/TRIMMING IS LIMITED TO THE INACTIVE SEASON, OCCURS WITHIN 100 FT OF THE ROAD/RAIL SURFACE, AND IS OUTSIDE OF DOCUMENTED HABITAT FOR THE INDIANA BAT, NLEB, AND TCB.
- TREES THREE (3) INCHES IN DIAMETER OR GREATER AT BREAST HEIGHT SHALL NOT BE CLEARED FROM APRIL 1ST THROUGH SEPTEMBER 30TH OF ANY GIVEN YEAR.



8725 W. Higgins Rd, Ste 600, Chicago, IL 60631
P 773.775.4009 | www.ciorba.com

USER NAME = Roadway	DESIGNED - VZ	REVISED - 4/8/2026
	DRAWN - VZ	REVISED -
PLOT SCALE = 2.0000 ' / in.	CHECKED - EPS	REVISED -
PLOT DATE = 4/8/2026	DATE - 3/26/2026	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SHERIDAN ROAD SIDEWALK INDEX OF SHEETS AND STANDARDS				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
				3506	19-00137-00-BT	LAKE	100	2
								CONTRACT NO. 61M41
SCALE: N.T.S.	SHEET 1	OF 1 SHEETS	STA.	TO STA.				
				ILLINOIS FED. AID PROJECT				

DATE PLOTTED = 4/8/2026 2:18:38 PM
PEN TABLE = 0021133.16.tb
PLOT CONFIG = CDP-PDF.plt
FILE NAME = N:\PROJECTS\133.16\CD\DD\Sheet\Phase 1\Misc\Sheet0021133.16-sh-500.dgn



USER NAME = Roadway	DESIGNED - VZ	REVISED - 4/8/2026
	DRAWN - VZ	REVISED -
PLOT SCALE = 2.0000 ' / in.	CHECKED - EPS	REVISED -
PLOT DATE = 4/8/2026	DATE - 3/26/2026	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SHERIDAN ROAD SIDEWALK
SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 4 OF 5 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3506	19-00137-00-BT	LAKE	100	6
CONTRACT NO.				61M41
ILLINOIS		FED. AID PROJECT		

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL	80% STATE 20% CITY ITEP 0028	100% CITY ITEP 0028
*	63000035	BACK SIDE PROTECTION OF GUARDRAIL	FOOT	84	84	
*	66400305	CHAIN LINK FENCE, 6'	FOOT	134	134	
⚠	*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1,260	1,260
	67100100	MOBILIZATION	L SUM	1	1	
⚠	*	66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2
	70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28	28	
⚠	*	66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	1
	70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	290	290	
⚠	*	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1
	70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	FOOT	868	868	
⚠	*	66901006	REGULATED SUBSTANCES MONITORING	CAL DA	10	10
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	650	650	
	70600255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	3	3	
*	72000100	SIGN PANEL - TYPE 1	SQ FT	102	102	
	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	6	6	
	72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	2	2	

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL	80% STATE 20% CITY ITEP 0028	100% CITY ITEP 0028
*	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	192	192	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,891	2,891	
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	324	324	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	24	24	
*	K1004595	PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE	L SUM	1	1	
	X0326806	WASHOUT BASIN	L SUM	1	1	
	X0327611	REMOVE AND REINSTALL BRICK PAVER	SQ FT	2,306	2,306	
	X0540000	BRICK PAVERS	SQ FT	4,165	4,165	
*	X1400326	RECTANGULAR RAPID FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	2	2	
	X5091300	DECORATIVE STEEL RAILING	FOOT	461	461	
*	X5620124	WATER SERVICE LINE REMOVAL	FOOT	31	31	