



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 10, 2026

SUBJECT: FAP Route 693 (IL 9)
Project STP-97C2(491)
Section 21BR-2
McLean County
Contract No. 70574
Item No. 115, April 24, 2026 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Added page 55 to the Special Provisions.
4. Revised sheets 4, 5, 22, and 25 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

SIGN PANELS AND APPURTENANCES (BDE).....	44
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	45
STEEL COST ADJUSTMENT (BDE)	46
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	48
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	49
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	49
SUBMISSION OF PAYROLL RECORDS – FEDERAL AID CONTRACT (BDE)	49
SURVEYING SERVICES (BDE)	51
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....	51
WATERPROOFING MEMBRANE SYSTEM (BDE)	52
WOOD SIGN SUPPORT (BDE).....	52
WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....	52
ROCK FILL – FOUNDATION	55

Revised April 10, 2026

ROCK FILL – FOUNDATION

Revised: November 24, 2025

This work consists of constructing a layer of rock fill below culverts or shallow foundations having unstable or unsuitable soil conditions. When shown on the plans, the rock fill limits and thickness shall be confirmed by the Engineer prior to excavating below the theoretical top of rock fill line. Materials shall meet the requirements of the following Articles of the Standard Specifications:

CA-6 and CA-7	1004.04
Rock fill	1005.01

All rock fill shall be well graded. The gradation of rock fill shall be selected based on layer thickness as shown below:

Less than or equal to 1 ft	Stone Riprap RR 1
Greater than 1 ft	Stone Riprap RR 1
Greater than 3 ft	Primary Crusher Run or Shot Rock (18" max size)

The method of rock fill placement shall be approved by the Engineer. Rock fill shall be capped according to application as shown below:

Shallow Foundations	4 to 6 inches CA-6
Cast-In-Place Box Culverts	6 inches CA+6
Pre-Cast Box Culverts	Porous Granular Bedding Materials (Article 540.06)
Pre-Cast Pipe Culverts	4 to 6 inches Fine Aggregate (Article 542.04(c))

In shallow foundation applications, the CA-6 cap shall be compacted to the satisfaction of the Engineer. No compaction of rock fill is required for culvert applications.

This work will be measured and paid for at the contract unit price per ton for ROCK FILL – FOUNDATION. The contract price for ROCK FILL – FOUNDATION shall include aggregate materials and aggregate material placement.

Excavation for the rock fill will be performed in accordance with Section 502 of the Standard Specifications and measured according to Article 502.12 (b). Unless otherwise specified in the plans, the excavation will be paid for at the contract unit price per cubic yard for REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS FOR STRUCTURES.

Added April 10, 2026