

MODEL: SQQ-1 [Sheet]
FILE NAME: c:\pw_work\pwid\project\sd037082\0570E14.sht-SQQ.dgn

LOCATION OF WORK:					FAI 74 (I-74)
					URBAN (BLOOMINGTON NORMAL)
					INTERSTATE
					STA. 737+00.00 TO STA. 1111+00.00
COUNTY:					MCLEAN
FUNDING BREAKOUT:					FEDERAL 80% / STATE 20%
CONSTRUCTION TYPE CODE:					0005
	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY
	40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	258,586.00	258,586.00
	40600370	LONGITUDINAL JOINT SEALANT	FOOT	221,572.00	221,572.00
	40600405	MATERIAL TRANSFER DEVICE	TON	42,508.00	42,508.00
	40600990	TEMPORARY RAMP	SQ YD	6,052.00	6,052.00
	40603218	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-9.5FG, N70	TON	1,220.00	1,220.00
	40604050	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N50	TON	16,732.00	16,732.00
	40604162	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	2,215.00	2,215.00
	40605034	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, 12.5, MIX "E", N80	TON	22,341.00	22,341.00
	40800029	BITUMINOUS MATERIALS (TACK COAT)	POUND	1,080.00	1,080.00
	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	156.00	156.00
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	36,123.00	36,123.00
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	332,447.00	332,447.00
	44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	14,520.00	14,520.00
	44200050	WELDED WIRE REINFORCEMENT	SQ YD	312.00	312.00
	44213000	PATCHING REINFORCEMENT	SQ YD	312.00	312.00
	* SPECIALTY ITEM				

	USER NAME = Bridgette.Pierson	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					74	57-20(1),21,22)RS-4	MCLEAN	78	4
		CHECKED -	REVISED -		CONTRACT NO. 70E14							
	PLOT DATE = 1/29/2026	DATE -	REVISED -		SCALE:	SHEET 1	OF 5 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		

CLASS A PATCHES, TYPE II, III, 14" (SPECIAL)

				X4420621	X4420624	44213200	44213204	44213000	
STATION	DIRECTION	SIZE (FOOT)		TY II	TY III	SAW CUTS	TIE BARS (TRANS)	PATCHING REINFORCEMENT	
		LENGTH	WIDTH						
FAI 74									
1096+06	WB	6	x 12	8.0		36.0	22.0	8.0	
1096+06	WB	6	x 12	8.0		36.0	22.0	8.0	
1083+64	WB	4	x 12	5.3		32.0	22.0	5.3	
885+94	WB	4	x 12	5.3	16.0	32.0	22.0	5.3	
837+98	WB	12	x 12			48.0	22.0	16.0	
779+29	WB	4	x 12	5.3		32.0	22.0	5.3	
779+17	WB	6	x 12	8.0		36.0	22.0	8.0	
771+90	WB	4	x 12	5.3		32.0	22.0	5.3	
771+90	WB	4	x 12	5.3		32.0	22.0	5.3	
770+03	WB	4	x 12	5.3		32.0	22.0	5.3	
770+03	WB	4	x 12	5.3		32.0	22.0	5.3	
769+00	WB	4	x 12	5.3		32.0	22.0	5.3	
769+00	WB	4	x 12	5.3		32.0	22.0	5.3	
765+63	WB	4	x 12	5.3		32.0	22.0	5.3	
765+63	WB	4	x 12	5.3		32.0	22.0	5.3	
763+64	WB	4	x 12	5.3		32.0	22.0	5.3	
762+04	WB	4	x 12	5.3		32.0	22.0	5.3	
762+04	WB	4	x 12	5.3		32.0	22.0	5.3	
760+02	WB	4	x 12	5.3		32.0	22.0	5.3	
760+02	WB	4	x 12	5.3		32.0	22.0	5.3	
757+04	WB	4	x 12	5.3		32.0	22.0	5.3	
757+04	WB	4	x 12	5.3		32.0	22.0	5.3	
750+05	WB	4	x 12	5.3		32.0	22.0	5.3	
742+61	WB	4	x 12	5.3		32.0	22.0	5.3	
742+61	WB	4	x 12	5.3		32.0	22.0	5.3	
742+00	WB	4	x 12	5.3		32.0	22.0	5.3	
737+83	WB	10	x 12	13.3		44.0	22.0	13.3	
743+71	EB	4	x 12	5.3		32.0	22.0	5.3	
744+43	EB	4	x 12	5.3		32.0	22.0	5.3	
745+48	EB	4	x 12	5.3		32.0	22.0	5.3	
749+73	EB	4	x 12	5.3		32.0	22.0	5.3	
753+36	EB	4	x 12	5.3		32.0	22.0	5.3	
754+44	EB	4	x 12	5.3		32.0	22.0	5.3	
779+19	EB	4	x 12	5.3		32.0	22.0	5.3	
779+19	EB	4	x 12	5.3		32.0	22.0	5.3	
781+62	EB	5	x 12	6.7		34.0	22.0	6.7	
781+62	EB	5	x 12	6.7		34.0	22.0	6.7	
782+24	EB	5	x 12	6.7		34.0	22.0	6.7	
788+33	CL	4	x 15	6.7		38.0	28.0	6.7	
903+42	EB	4	x 12	5.3		32.0	22.0	5.3	
903+42	EB	4	x 12	5.3		32.0	22.0	5.3	
917+35	EB	4	x 12	5.3		32.0	22.0	5.3	
948+84	EB	6	x 12	8.0		36.0	22.0	8.0	
949+02	EB	4	x 12	5.3		32.0	22.0	5.3	
976+52	EB	4	x 12	5.3		32.0	22.0	5.3	
1007+91	EB	8	x 6	5.3		28.0	10.0	5.3	
1009+37	EB	8	x 6	5.3		28.0	10.0	5.3	
1037+89	EB	8	x 12	10.7		40.0	22.0	10.7	
1040+11	EB	6	x 12	8.0		36.0	22.0	8.0	
1040+17	EB	6	x 12	8.0		36.0	22.0	8.0	
* DENOTES CENTERLINE				TOTAL:	296.0	16.0	1,664.0	1,082.0	311.9
				USE:	296	16	1,664	1,082	312
				SQ YD	SQ YD	FT	EACH	SQ YD	

CLASS D PATCHES, TYPE II, IV, 10"

					44201765	44201771
STATION	DIRECTION	SIZE (FOOT)			TY II	TY IV
		LENGTH		WIDTH		
	CR 700					
16+92.44	NB	4	x	12	5.3	
16+92.44	SB	4	x	12	5.3	
	NB	4	x	12	5.3	
	SB	4	x	12	5.3	
	NB	5	x	12	6.7	
	SB	5	x	12	6.7	
	NB	4	x	12	5.3	
	SB	4	x	12	5.3	
	SB	3	x	12	4.0	
	NB	4	x	12	5.3	
	SB	4	x	12	5.3	
	NB	4	x	12	5.3	
	SB	4	x	12	5.3	
	NB	4	x	12	5.3	
	SB	4	x	12	5.3	
25+65	NB	4	x	12	5.3	
25+65	SB	4	x	12	5.3	
	NB	5	x	12	6.7	
	SB	5	x	12	6.7	
	NB	5	x	12	6.7	
	SB	5	x	12	6.7	
31+03	NB	4	x	12	5.3	
31+03	SB	4	x	12	5.3	
32+60	NB	5	x	12	6.7	
32+60	SB	10	x	12	13.3	
33+05	NB	5	x	12	6.7	
33+05	SB	5	x	12	6.7	
33+50	SB	4	x	12	5.3	
34+00	SB	4	x	12	5.3	
35+00	SB	5	x	12	6.7	
36+00	SB	6	x	12	8.0	
37+00	SB	8	x	12	10.7	
38+50	SB	8	x	12	10.7	
39+00	SB	5	x	12	6.7	
39+00	SB	5	x	12	6.7	
39+50	SB	5	x	12	6.7	

CLASS D PATCHES, TYPE II, IV, 10"

					44201765	44201771	
STATION	DIRECTION	SIZE (FOOT)			TY II	TY IV	
		LENGTH		WIDTH			
	CR 700						
40+10	NB	5	x	12	6.7		
40+10	SB	5	x	12	6.7		
41+00	SB	6	x	15	10.0		
42+00	SB	5	x	12	6.7		
42+25	SB	6	x	12	8.0		
42+64	SB	5	x	12	6.7		
45+00	NB	10	x	12	13.3	26.7	
45+20	SB	10	x	24	0.0		
46+00	SB	5	x	24	13.3		
51+60	NB	4	x	12	5.3		
51+60	SB	4	x	12	5.3		
53+00	NB	4	x	15	6.7		
53+40	SB	6	x	12	8.0		
55+20	NB	4	x	12	5.3		
55+40	NB	4	x	12	5.3		
58+00	NB	10	x	12	13.3		
60+00	SB	5	x	12	6.7		
66+00	NB	5	x	12	6.7		
67+75	NB	4	x	12	5.3		
RAMP E	WB	4	x	12	5.3		
RAMP E	WB	4	x	12	5.3		
RAMP C	WB	4	x	15	6.7		
RAMP B	EB	4	x	12	5.3		
RAMP B	EB	6	x	12	8.0		
RAMP B	EB	6	x	12	8.0		
RAMP B	EB	4	x	12	5.3		
RAMP B	EB	4	x	12	5.3		
RAMP B	EB	4	x	12	5.3		
RAMP D	EB	4	x	12	5.3		
RAMP D	EB	4	x	12	5.3		
RAMP D	EB	4	x	12	5.3		
RAMP D	EB	4	x	12	5.3		
* DENOTES CENTERLINE					TOTAL:	444.7	26.7
					USE:	445	27
						SQ YD	SQ YD

MODEL: Schedules-2 [Sheet]
FILE NAME: c:\pw_work\wtd\proj\csd037082\0570E14.sht-Schedules.dgn

PLOT DATE = 1/29/2026	USER NAME = Bridgette.Pierson	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					74	57-20(1),21,22)RS-4	MCLEAN	78	25
		CHECKED -	REVISED -					CONTRACT NO. 70E14				
		DATE -	REVISED -		SCALE:	SHEET 2	OF 5 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		