

COMMITMENTS

THERE ARE NO COMMITMENTS FOR THIS PROJECT.

LIST OF HIGHWAY STANDARDS

STANDARD NO.	DESCRIPTION
0000001-09	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006-00	DECIMAL OF AN INCH AND OF A FOOT
420001-11	PAVEMENT JOINTS
442101-09	CLASS B PATCHES
426701-09	PAVEMENT WELDED WIRE REINFORCEMENT
606301-04	PC CONCRETE ISLANDS AND MEDIANS
701456-05	PARTIAL EXIT RAMP CLOSURE, FREEWAY/EXPRESSWAY
701901-11	TRAFFIC CONTROL DEVICES
D5 60621900	CONCRETE MEDIAN, TYPE SM (SPECIAL)
D5 60623711	SIGN POST BLOCKOUTS
D5 7800BBBB	PAVEMENT MARKING (INTERSTATE & MULTILANE APPLICATIONS)

GENERAL NOTES

G.N.-100A
ELECTRONIC FILES AND/OR ELECTRONIC SURVEY INFORMATION INCLUDING CADD FILES WILL NOT BE AVAILABLE TO THE CONTRACTOR.

G.N.-406S
PROJECT POSTED SPEED LIMITS

THE FOLLOWING TABLE IS A LISTING OF POSTED SPEED LIMITS WITHIN THE PROJECT LIMITS. THE ENGINEER SHALL FIELD VERIFY THESE LIMITS:

STATION	TO	STATION	POSTED SPEED LIMIT (MPH)
RAMP		RAMP	45

G.N.-440B
THE EXISTING TIE BARS BETWEEN THE EXISTING PAVEMENT AND EXISTING MEDIANS, GUTTERS AND/OR COMBINATION CURB AND GUTTERS THAT ARE FOUND SUITABLE FOR REUSE SHALL BE CLEANED, STRAIGHTENED AND INCORPORATED INTO THE NEW CONSTRUCTION. ANY EXISTING TIE BARS THAT ARE FOUND UNSUITABLE TO BE INCORPORATED INTO THE PROPOSED CONSTRUCTION DUE TO EXCESSIVE RUSTING OR DISTRESS SHALL BE REMOVED FLUSH WITH THE FACE OF THE EXISTING CONCRETE AND DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT-OF-WAY IN ACCORDANCE WITH ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS.

THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE VARIOUS REMOVAL PAY ITEMS AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

G.N.-703A
SHORT TERM PAVEMENT MARKING SHALL BE APPLIED TO THE PAVEMENT AFTER ANY OF THE FOLLOWING: COLD MILLING AND/OR PLACING BITUMINOUS MATERIALS (TACK COAT), LEVELING BINDER (MACHINE METHOD), BINDER AND SURFACE COURSES. SHORT TERM PAVEMENT MARKING PLACED ON THE SURFACE SHALL COINCIDE WITH THE FINAL PAVEMENT STRIPING. SHORT TERM PAVEMENT MARKING PLACED PRIOR TO THE SURFACE SHALL COINCIDE WITH THE EXISTING PAVEMENT MARKINGS. USE 4 FEET PER 40 FEET (OR 10% PER STATION).

G.N.-781
THE FINAL PAVEMENT MARKINGS SHALL BE IN PLACE PRIOR TO PLACING THE RAISED REFLECTIVE PAVEMENT MARKERS.

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS
2	HIGHWAY STANDARDS
2	GENERAL NOTES
2	COMMITMENTS
3 - 4	SUMMARY OF QUANTITIES
5	TYPICAL CROSS SECTION
6	SCHEDULE OF QUANTITIES
7-8	PATCHING PLAN SHEET

MODEL: General Notes-1 [Sheet]
FILE NAME: c:\pwworking\illinois.goble\1125243\0570182.sht-GenNotes.dgn

USER NAME	= jason.goble	DESIGNED	- JRG	REVISED	-
		DRAWN	- JRG	REVISED	-
		CHECKED	-	REVISED	-
PLOT DATE	= 12/4/2025	DATE	-	REVISED	--

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS, GENERAL NOTES,
LIST OF HIGHWAY STANDARDS, COMMITMENTS

SCALE: SHEET 1 OF 1 SHEETS STA. T.O STA.

F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	CM PATCHING 2026-1	MCLEAN	8	2
CONTRACT NO. 70H82				
ILLINOIS FEDERAL PROJECT				

LOCATION OF WORK:FAI 39 (I-39)

RURAL

INTERSTATE

HUDSON INTERCHANGE RAMPS

COUNTY:MCLEAN

FUNDING BREAKOUT:STATE 100%

CONSTRUCTION TYPE CODE:0006

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY
	44201299	DOWEL BARS 1 1/2	EACH	1,072.0
	44004250	PAVED SHOULDER REMOVAL	SQ YD	722.0
	44213000	PATCHING REINFORCEMENT	SQ YD	1,144.6
	44213200	SAW CUTS	FOOT	1,446.0
	44213210	TIE BARS 1 3/8"	EACH	220.0
	48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	32.0
	48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	721.8
	67100100	MOBILIZATION	LUMP SUM	1.0
	70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	LUMP SUM	1.0
	70103815	TRAFFIC CONTROL SURVEILANCE	CAL DAY	8.0
	70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28.0
	70307120	TEMPORARY PAVEMENT MARKING - LINE - 4" - TYPE IV TAPE	FOOT	640.0
*	78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	640.0
*	78008350	POLYUREA PAVEMENT MARKING TYPE II - LINE 12"	FOOT	48.0
*	78011025	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	640.0
*	78011065	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	48.0
* SPECIALTY ITEM				



MODEL: Summary of Quantities-1 [Sheet]
FILE NAME: c:\pwworking\jason.goble@illinois.gov\1125243\0570H82.sht-SOQ.dgn

	USER NAME = jason.goble	DESIGNED - JRG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JRG	REVISED -						39	CM PATCHING 2026-1	MCLEAN	8	3
		CHECKED -	REVISED -						CONTRACT NO. 70H82				
	PLOT DATE = 12/9/2025	DATE -	REVISED -		SCALE:	SHEET 1	OF 2	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		