



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 8, 2026

SUBJECT: FAU 9380 (North County Road)
Section 24-00031-00-SW (Macoutah)
St. Clair County
Contract No. 97887
Item 190
April 24, 2026 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices**
- 2. Revised Plan Sheets 3, 6, & 17**
- 3. Revised page 16 of the Special Provisions**
- 4. Added page 16A to the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

POST MOUNTED FLASHING BEACON INSTALLATION (SPECIAL)

This work shall consist of the installation of Rectangular Rapid Flashing Beacons (RRFBs) at the locations shown on the plans, in accordance with Section 4L of the "Manual of Uniform Traffic Control Devices for Streets and Highways" (MUTCD).

Solar system: 55W high-efficiency panel conforming to IP-67. NEMA 4 rated cabinet with lockable clasps.

Storage/backup battery: Sealed gel battery, functional for 30 days without charge requiring no periodic watering. Sealed construction. Battery lifespan 3 years.

Control Circuit: IP-67 NEMA rated enclosure, dustproof and waterproof. Wireless communication system between units on each side of the street, 900 MHz frequency, programmable.

Light Emitting Source: Flashing beacon, LED array viewable from all directions, SAE J595 certified. Irregular flash pattern. Flash frequency must be MUTCD compliant. Powder coated aluminum finish.

Pole: 4.5" diameter aluminum conforming to Section 1077.01 of the "Standard Specifications for Road and Bridge Construction", the applicable IDOT Highway Standards, and the construction details on the plans.

Concrete Foundation: Shall conform to Section 1077.01 of the "Standard Specifications for Road and Bridge Construction" and the construction details on the plans.

Activation: ADA pushbutton activation.

Sign Panel: Shall meet all requirements for Section 720, substrate shall be 0.080 Highway Grade Aluminum. Each post shall include one R10-25 background color shall be white and legend shall be black, two S1-1, one W16-7P(R), and one W16-7P(L), background color shall be fluorescent yellow and legend shall be black. S1-1 and W16-7P Signs shall be mounted on both sides of pole as shown in the Construction Details.

Warranty: 1 year (min.) on entire assembly

This work shall be paid for at the contract unit price per EACH for POST MOUNTED FLASHING BEACON INSTALLATION (SPECIAL), which price shall include the beacon installation, concrete foundations, control circuits, signs, and all other work, equipment, and materials necessary to provide a complete and functional assembly.

POP-UP ROOF DRAINS

This work shall consist of the addition of a pop-up drain, and adjusting existing sump pump drains to match proposed conditions according to Section 601 of the "Standard Specifications for Road and Bridge Construction" and as directed by the Engineer. Underground sump pump drains have been located from available surveys and records

and are shown on the plans. It is possible there may be others, the existence of which is not presently known or shown.

The Engineer will evaluate each roof drain separately and will determine the appropriate method of adjustment. Ideally, sump pump drains shall discharge at the proposed pop up drain located in the plans. Existing materials may be reused, if possible. However, this work may involve the removal of existing materials and the installation of similar, new materials. Appropriate fittings to connect the proposed materials to the existing materials will also be required. This work is anticipated to be confined to the proposed right-of-way limits.

This work shall be paid for at the contract unit price per EACH for POP-UP ROOF DRAINS, which price shall include all excavation, pipe removal and replacement, curb modifications, pop up drain, backfill and all other work necessary to adjust the sump pump drain.