

ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES			
LOCATION OF WORK			80% FEDERAL 20% STATE RURAL CONSTRUCTION TYPE CODE X028-2A
CODE NO.	ITEM	UNIT	
20200100	EARTH EXCAVATION	CU YD	6325
20201000	GRADING AND SHAPING ROADWAY	UNIT	6
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	64
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	150
25000210	SEEDING, CLASS 2A	ACRE	1.25
25000310	SEEDING, CLASS 4	ACRE	1
25000750	MOWING	ACRE	1.25
25100115	MULCH, METHOD 2	ACRE	2.25
25100630	EROSION CONTROL BLANKET	SQ YD	928
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	430
28000300	TEMPORARY DITCH CHECKS	EACH	21
28000400	PERIMETER EROSION BARRIER	FOOT	145
28000500	INLET AND PIPE PROTECTION	EACH	2
28100107	STONE RIPRAP, CLASS A4	SQ YD	252
28200200	FILTER FABRIC	SQ YD	252
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	151
44004250	PAVED SHOULDER REMOVAL	SQ YD	481
44200988	CLASS B PATCHES, TYPE IV, 11 INCH	SQ YD	539
44213100	PAVEMENT FABRIC	SQ YD	539
44213200	SAW CUTS	FOOT	480
48101200	AGGREGATE SHOULDERS, TYPE B	TON	734
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	130
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	838
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	279
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	10250
50901760	PIPE HANDRAIL	FOOT	17
51500100	NAME PLATES	EACH	2
54003000	CONCRETE BOX CULVERTS	CU YD	66.4
54011004	PRECAST CONCRETE BOX CULVERT 10' x 4'	FOOT	192
54201279	PIPE CULVERTS, TYPE 2 RCCP 24"	FOOT	69
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1
61100605	MISCELLANEOUS CONCRETE	CU YD	1.2

● NON-PARTICIPATING 100% STATE

ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES			
LOCATION OF WORK			80% FEDERAL 20% STATE RURAL CONSTRUCTION TYPE CODE X028-2A
CODE NO.	ITEM	UNIT	
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	1
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	2
61140100	STORM SEWERS (SPECIAL) 10"	FOOT	85
61140200	STORM SEWERS (SPECIAL) 12"	FOOT	128
63200310	GUARDRAIL REMOVAL	FOOT	906
63500105	DELINEATORS	EACH	12
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	17
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	28
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	10
78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	123
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	36544
78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	72
X0323660	DROP BOX NO. 1	EACH	1
X0325911	HOT-MIX ASPHALT SURFACE COURSE, SPECIAL	TON	118
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0017202	DOWEL BARS 1 1/2"	EACH	400
Z0075300	TIE BARS	EACH	202
Z0049800	RELOCATE EXISTING SURVEY MARKERS	EACH	1

● INDICATES SPECIALTY ITEM

FILE NAME = ...\\07\07075\vb-rs\z11306ovr3.dgn	USER NAME = CFC-rs	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 1:8000 / IN.	CHECKED -	REVISED -
	PLOT DATE = 01/21/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.

COOMBE-BLOXDORF P.C.
Engineers / Land Surveyors
Springfield, Illinois
Design Firm License No. 184-002703

F.A.S RTE. 1087	SECTION 107T-1	COUNTY STEPHENSON	TOTAL SHEETS 47	SHEET NO. 3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 64C64				