## EROSION CONTROL SCHEDULE

| LOCATION (STATION RANGE) | 25100630 EROSION CONTROL BLANKET | 28000250 TEMPORARY EROSION CONTROL SEEDING | 28000300 TEMPORARY DITCH CHECKS | 28000400 PERIMETER EROSION BARRIER | 28000500 INLET AND PIPE PROTECTION | 28100107 STONE RIPRAP CLASS A4 | 28200200 FILTER FABRIC |
|---|---|---|---|---|---|---|---|
| | SY | LB | EA | FT | EA | SY | SY |
| RT STA 599+94 TO STA 612+50 | | 265 | | | | | |
| RT STA 599+94 TO STA 600+27 | | | | 35 | | | |
| RT STA 600+10 TO STA 600+65 | 112.0 | | | | | | |
| RT STA 600+30 | | | 1 | | | | |
| RT STA 600+50 | | | 1 | | | | |
| LT STA 600+50 TO STA 613+00 | | 165 | | | | | |
| LT STA 600+69.5 | | | | | 1 | | |
| RT STA 600+69.5 | | | | | | 13.3 | 13.3 |
| RT STA 602+30 | | | 1 | | | | |
| LT STA 602+75 | | | 1 | | | | |
| RT STA 604+10 | | | 1 | | | | |
| RT STA 605+90 | | | 1 | | | | |
| LT STA 606+20 | | | 1 | | | | |
| RT STA 607+70 | | | 1 | | | | |
| RT STA 608+25 TO STA 612+50 | 295.1 | | | | | | |
| RT STA 609+39.56 | | | | | | 216.0 | 216.0 |
| RT ST A 609+40 | | | 1 | | | | |
| LT STA 609+50 TO STA 613+00 | 521.3 | | | | | | |
| LT STA 609+65 TO STA 610+98 | | | | 110 | | | |
| RT STA 609+80 | | | 1 | | | | |
| RT STA 610+20 | | | 1 | | | | |
| LT STA 610+25.56 | | | | | 1 | 22.2 | 22.2 |
| RT STA 610+60 | | | 1 | | | | |
| RT STA 611+00 | | | 1 | | | | |
| LT STA 611+15 | | | 1 | | | | |
| RT STA 611+40 | | | 1 | | | | |
| LT STA 611+45 | | | 1 | | | | |
| LT STA 611+75 | | | 1 | | | | |
| RT STA 611+80 | | | 1 | | | | |
| LT STA 612+05 | | | 1 | | | | |
| LT STA 612+35 | | | 1 | | | | |
| LT STA 612+65 | | | 1 | | | | |
| TOTALS | 928 | 430 | 21 | 145 | 2 | 252 | 252 |

## SEEDING SCHEDULE

| LOCATION | 25000210 SEEDING CLASS 2A | 25000310 SEEDING CLASS 4 | 25100115 MULCH METHOD 2 | 25000750 MOWING |
|---|---|---|---|---|
| | AC | AC | AC | AC |
| LT STA 600+51.71 TO LT STA 613+00.00 | 0.50 | 0.50 | 1.00 | 0.50 |
| * RT STA 599+93.67 TO RT STA 612+50.00 | 0.75 | 0.50 | 1.25 | 0.75 |
| TOTAL | 1.25 | 1.00 | 2.25 | 1.25 |

* INCLUDES AREA EAST ALONG GODDARD ROAD

## GOOD NEIGHBOR POLICY SCHEDULE

| LOCATION | PAVEMENT LENGTH | PAVEMENT WIDTH AVE | SURFACE TYPE | X0325911 HMA SURFACE COURSE, SPECIAL 1 1/2" | 48102100 AGGREGATE WEDGE SHOULDERS, TYPE B | 20201000 GRADING AND SHAPING ROADWAY | 78001110 PAINT PAVEMENT MARKING - LINE 4" |
|---|---|---|---|---|---|---|---|
| | FEET | FEET | | TON | TON | UNIT | FOOT |
| WEST GALENA ROAD - US 20 TO IL 73 | 7680 / 2320 | 22.1 / 35.5 | HMA | 118 | 11 | - | 26560 |
| WEST HOWARDSVILLE ROAD (TOWNLINE ROAD) - FIVE CORNERS ROAD TO WEST GALENA ROAD | 4440 / 1400 / 4090 | 19.1 / 36.6 / 23.3 | AGG / O&C / O&C | - | 73 | 2.2 | - |
| FIVE CORNERS ROAD - WEST HOWARDSVILLE ROAD TO WEST GODDARD ROAD | 2500 | 16.5 | AGG | - | 13 | 1.2 | - |
| WEST GODDARD ROAD - FIVE CORNERS ROAD TO IL 73 | 5200 | 20.2 | AGG | - | 33 | 2.6 | - |
| | | | TOTAL | 118 | 130 | 6 | 26560 |

## GUARDRAIL REMOVAL AND PAVED SHOULDER REMOVAL SCHEDULE

| LOCATION | 63200310 GUARDRAIL REMOVAL | 44004250 PAVED SHOULDER REMOVAL |
|---|---|---|
| | FT | SY |
| RT STA 600+17.90 TO RT STA 604+62.86 | 463.1 | 235.0 |
| LT STA 603+57.29 TO LT STA 604+73.39 | 116.1 | 64.4 |
| RT STA 607+15.57 TO RT STA 608+16.48 | 101.0 | 56.1 |
| LT STA 607+58.38 TO LT STA 609+83.99 | 225.7 | 125.6 |
| TOTAL | 906 | 481 |

## ROCK EXCAVATION SCHEDULE

| LOCATION | 50200400 ROCK EXCAVATION FOR STRUCTURES |
|---|---|
| | CY |
| STA 600+69.49 | 22 |
| STA 609+82.56 | 257 |
| TOTAL | 279 |

## FIELD TILE SCHEDULE

| LOCATION | 61100605 MISCELLANEOUS CONCRETE | 61133100 FIELD TILE JUNCTION VAULT, 2' DIA. | 61133200 FIELD TILE JUNCTION VAULT, 3' DIA. | 61140100 STORM SEWERS (SPECIAL) 10" | 61140200 STORM SEWERS (SPECIAL) 12" | 21301052 EXPLORATION TRENCH 52" |
|---|---|---|---|---|---|---|
| | (CU YD) | (EACH) | (EACH) | (FOOT) | (FOOT) | (FOOT) |
| 34' LT STA 608+21 EX END | 0.406 | | 1 | | 65 | 50 |
| 48' LT STA 608+58 EX END | 0.415 | 1 | | 85 | | 50 |
| 47' LT STA 609+05 EX END | 0.350 | | 1 | | 63 | 50 |
| TOTAL | 1.2 | 1 | 2 | 85 | 128 | 150 |

## PIPE AND END SECTION SCHEDULE

| LOCATION | 54201279 PIPE CULVERTS, TYPE 2, RCCP 24" | 54213669 PRC FLARED END SECTION 24" | X0323660 DROP BOX NO. 1 | 63500105 DELINEATORS |
|---|---|---|---|---|
| | FOOT | EACH | EACH | EACH |
| STA 600+69.49, 28.0' LT TO 41.0' RT | 69 | | | |
| STA 600+69.49, 41.0' RT TO 47.12' RT | | 1 | | 1 |
| STA 600+69.49, 28.0' LT | | | 1 | 1 |
| LT & RT STA 601+00.00 TO STA 613+00.00 | | | | 8 |
| RT STA 609+39.56 | | | | 1 |
| LT STA 610+25.56 | | | | 1 |
| TOTALS | 69 | 1 | 1 | 12 |


COOMBE-BLOXDORF P.C.
Engineers / Land Surveyors
Springfield, Illinois
Design Firm License No. 184-002703