

70400100 Temporary Concrete Barrier

Location			
Sta.	Sta.		Foot
282+74.50	to 286+36.50	Stage II	
			Total = $\frac{362.5}{362.5}$

70400200 Relocate Temporary Concrete Barrier

Location			
Sta.	Sta.		Foot
283+24.00	to 286+75.00	Stage III	
			Total = $\frac{350}{350}$

78001110 Paint Pavement Marking -- Line 4"

Location			
Sta.	Sta.		Foot
281+90.00	to 288+90.50	Lt & Rt	1400 2 Coats White Edgeline
281+90.00	to 288+90.50	CL	2800 2 Coats Solid Dbl Yellow
			Total = $\frac{4200}{4200}$

78300100 Pavement Marking Removal

Location			
Sta.	Sta.		Sq. Ft.
283+00.00	to 287+25.00	Lt	141.7 LT Edgeline
281+75.00	to 284+32.47	Cl	171.7 Solid Dbl Yellow
285+28.48	to 02+88.00	Cl	206.0 Solid Dbl Yellow
283+00.00	to 286+50.00	Rt	116.7 RT Edgeline
			Total = $\frac{636.0}{636.0}$

X0712400 Temporary Pavement

Location			
Sta.	Sta.		Sq. Yd.
281+90.00	to 287+25.00	Lt	282.4 Stage I
			Total = $\frac{282.4}{282.4}$

X0919000 Temporary Pavement Removal

Location			
Sta.	Sta.		Sq. Yd.
284+52.47	to 285+08.47	Lt	50.7 Stage III
			Total = $\frac{50.7}{50.7}$

Z0005400 Breaker-Run Crushed Stone

Location			
Sta.			Ton
284+80.47			224 15' wide x 98.34' long x 2' deep
			Total = $\frac{224}{224}$

Z0030250 Impact Attenuators, Temporary (Non-Redirective), Test Level 3

Location			
Sta.	Sta.		Each
282+72.50			1 Stage II (45 mph Array)
286+38.50			1 Stage II (45 mph Array)
			Total = $\frac{2}{2}$

Z0030350 Impact Attenuators, Relocate (Non-Redirective), Test Level 3

Location			
Sta.			Each
283+22.00			1 Stage II (45 mph Array) to Stage III
286+77.00			1 Stage II (45 mph Array) to Stage III
			Total = $\frac{2}{2}$

FILE NAME = C:\Projects\p211906\d11906cvr.dgn	USER NAME = jordanid	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES		F.A.P. RTE. 611	SECTION 102T	COUNTY HENRY	TOTAL SHEETS 41	SHEET NO. 10
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	REVISED -		SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	FED. ROAD DIST. NO. _____	ILLINOIS FED. AID PROJECT	CONTRACT NO. 64C70	
PLOT DATE = Fri Feb 08 08:53:46 2008	DATE -	REVISED -	REVISED -								