

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
592	121-1R, 121HVB	ST CLAIR	239	32

PAVING SCHEDULE

STATION TO STATION	PROCESSING MODIFIED SOIL 12"	LIME	SUB-BASE GRANULAR MATERIAL TYPE A 4"	SUB-BASE GRANULAR MATERIAL TYPE C	BIT. MAT'L'S (PRIME COAT)	AGGREGATE (PRIME COAT)	BRIDGE APPROACH PAVEMENT	POLY. HOT-MIX ASPHALT COURSE MIX "D", N90	HOT-MIX ASPHALT BINDER COURSE IL-19.0, N90	LEVELING BINDER (MACHINE METHOD) N90	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) 7"	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) 8 1/2"	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) 9 1/2"	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) 14 1/4"	HOT-MIX ASPHALT SHOULDERS
	SQ YD	TON	SQ YD	CU YD	TON	TON	SQ YD	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	TON
IL. 157															
4996+88 - 5010+30					4.1	26.4		945	1212						163
5010+30 - 5028+52	16362	327		86					826					12416	
5028+52 - 5028+82			279							271					
5030+47 - 5030+77			279							271					
5030+77 - 5050+00	17314	346		11					19					13144	
5050+00 - 5088+60					12.0	76.9		2704	27						502
ST. PAUL DR.															
200+13 - 203+29			1657								1517				
RANGE LN.															
99+98 - 102+64			1991										1872		
103+36 - 110+00			3818										3389		
FRONTAGE RD.															
498+16 - 509+05			100		1.4	9.1		350	25	165					
509+05 - 513+00			943								756				
DONALD ST.															
401+50 - 405+17			1748	21									1618		
CONNECTOR RD.															
300+13 - 308+47			3076								2376				
COOPER DR.															
603+00 - 603+88			903								792				
TOTALS	33676	673	14794	118	17.5	112.4	542	3999	2109	165	3168	2273	6879	25560	665

PROPOSED MEDIAN

SIDE/STATION	SIDE/STATION	CONC. MEDIAN SURFACE 4"	CONC. MEDIAN TY SB-6 (SPECIAL)	CONCRETE MEDIAN	CORRUGATED MEDIAN	PCC RAMPED MEDIAN TERMINAL	CONC MEDIAN TYPE SB6.06
		SQ FT	SQ FT	SQ FT	SQ FT	EACH	SQ FT
IL. 157							
LT. 4998+77	LT. 4998+84					1	
RT. 4999+48	RT. 4999+55					1	
RT. 5001+76	RT. 5001+86					1	
RT. 5023+17	RT. 5023+23					1	
RT. 5023+23	CL 5025+14		765				
CL 5025+14	CL 5028+52	3138					
CL 5028+52	CL 5028+82			360			
CL 5030+47	CL 5030+77			360			
CL 5030+77	CL 5032+69	1379					
CL 5032+69	LT. 5036+25		1425				
LT. 5036+25	LT. 5036+31					1	
RT. 5037+59	RT. 5037+65					1	
RT. 5037+65	RT. 5041+21		1417				
RT. 5039+62	RT. 5039+74					2	92
RT. 5041+21	RT. 5041+27					1	
RANGE LN.							
RT. 103+88	RT. 103+94					1	
CL 103+94	CL 105+77		1187			1	
CL 105+77	CL 106+27				320		
TOTALS		4517	4794	720	320	11	92

SHOULDER SCHEDULE

SIDE	STATION	HOT-MIX ASPHALT SHOULDER WIDTH	AGGREGATE SHOULDER WIDTH	STATION	HOT-MIX ASPHALT SHOULDER WIDTH	AGGREGATE SHOULDER WIDTH	LENGTH	AGGREGATE SHOULDER TYPE B 8"	HOT-MIX ASPHALT SHOULDER 6"	HOT-MIX ASPHALT SHOULDER 14 1/4"
		FOOT	FOOT		FOOT	FOOT		FOOT	SQ YD	SQ YD
IL. 157										
RT.	5010+30	8	2	5022+08	8	2	1178	263		1045
LT.	5010+81	8	2	5028+49	8	2	1768	391		1565
RT.	5023+23	8	2	5027+96	8	2	473	106		415
RT.	5027+96	2.5		5028+56	2.5		60			17
LT.	5030+74	8	2	5036+55	8	2	581	126		509
RT.	5030+81	2.5		5031+34	2.5		53			15
RT.	5031+34	8	2	5036+22	8	2	488	105		427
RT.	5037+62	8	2	5042+94	8	2	532	103		371
LT.	5037+68	8	2	5050+00	8	2	1232	271		1089
RT.	5043+90	8	2	5050+00	8	2	611	136		542
DONALD ST.										
RT.	403+61	4		405+17	4		188		84	
LT.	403+73	4		405+17	4		174		77	
FRONTAGE RD.										
RT.	507+43	2		508+64	8		121		76	
TOTALS								1501	237	5995

PROPOSED SIDEWALK

SIDE/STATION	SIDE/STATION	P.C.C. SIDEWALK 4"	P.C.C. SIDEWALK 6" (SPECIAL)
		SQ FT	SQ FT
IL. 157			
RT. 5027+96	RT. 5028+86		421
RT. 5030+51	RT. 5031+33		386
RANGE LN.			
LT. 99+95	LT. 102+33	1626	
RT. 101+53	RT. 102+64	942	
LT. 103+29	LT. 106+43	2080	
RT. 103+53	RT. 106+07	1624	
RT. 106+20	RT. 107+03	452	
LT. 106+90	LT. 107+47	346	
RT. 107+23	RT. 108+94	987	
LT. 107+89	LT. 108+79	523	
LT. 108+97	LT. 109+51	298	
RT. 109+34	RT. 110+00	377	
LT. 109+64	LT. 110+00	203	
TOTALS		9458	807

STRIP REFLECTIVE CRACK CONTROL TREATMENT

STATION TO STATION	LENGTH
	FOOT
IL. 157	
4996+88 - 5010+30	9394
5050+00 - 5088+60	23160
FRONTAGE RD.	
498+16 - 509+05	1484
TOTAL	34038

NOTE: APPLY TO ALL PAVEMENT AND SHOULDER JOINTS WITHIN THE RESURFACING AREA.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

FAP ROUTE 592
SECTION 121-1R, 121HVB
ST. CLAIR COUNTY

DRAWN BY: