SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: 1000

ITEM NO.	CODE NO.	ITEM	UNIT	QUANTITY
1	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	10
2	20200410*	EARTH EXCAVATION (SPECIAL)	CU YD	2,468
3	20201200*	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	247
4	20800150	TRENCH BACKFILL	CU YD	126
5	25000350*	SEEDING, CLASS 7	ACRE	0.03
6	25200200*	SUPPLEMENTAL WATERING	UNIT	14
7	25200700*	SODDING, SPECIAL	SQ YD	1,350
8	28000500	INLET AND PIPE PROTECTION	EACH	17
9	31101000*	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	2,042
10	35100100*	AGGREGATE BASE COURSE, TYPE A	TON	1,022
11	40200800*	AGGREGATE SURFACE COURSE, TYPE B	TON	65
12	40600100*	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,241
13	40600300*	AGGREGATE (PRIME COAT)	TON	7
14	40603000	HOT-MIX ASPHALT BINDER COURSE, IL-12.5, N50	TON	538
15	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C" N50	TON	403
16	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	82
17	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	7,944
18	42400800	DETECTABLE WARNINGS	SQ FT	40
19 Δ	56400800*	FIRE HYDRANT AND VALVE TO BE MOVED	EACH	1
20	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
21	60242400*	INLETS, SPECIAL	EACH	13
22	60255500	MANHOLES TO BE ADJUSTED	EACH	10
23	60260100	INLETS TO BE ADJUSTED	EACH	2
24	60266600	VALVE BOXES TO BE ADJUSTED	EACH	5
25	60500305	FILLING INLETS	EACH	8
26	60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	2,421
27	61140200*	STORM SEWERS, SPECIAL 12"	FOOT	522
28	61140400*	STORM SEWERS, SPECIAL 15"	FOOT	84
29	70101700*	TRAFFIC CONTROL AND PROTECTION	L SUM	1
30	72000100	SIGN PANEL - TYPE 1	SQ FT	21
31	72900100	METAL POST - TYPE A	FOOT	36
32 Δ	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	256
33 Δ	78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	48
34 Δ	78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	41
35 Δ	XX001653*	ORNAMENTAL FENCE COMPLETE	FOOT	108
36	Z0005400*	BREAKER-RUN CRUSHED STONE	TON	506
37	Z0012450*	CONCRETE STEPS	CU YD	0.96
38	67100100	MOBILIZATION	L SUM	1

Δ SPECIALTY ITEMS

* INDICATES SPECIAL PROVISION

PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / RT. OF WAY CHECKED / CADD FILE NAME — NOTE BOOK NO. — BY — DATE

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / B.M. NOTED / STRUCTURE NOTATIONS CHKD — NOTE BOOK NO. — BY — DATE

S:/TRANS/1050D07/COVERETC.DGN

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - ___	REVISED - ___
		DRAWN - ___	REVISED - ___
	PLOT SCALE = $SCALE$	CHECKED - ___	REVISED - ___
	PLOT DATE = $DATE$	DATE - _____	REVISED - ___

WILLETT, HOFMANN & ASSOCIATES, INC
CONSULTING ENGINEERS
DIXON, IL

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. __ OF ___ SHEETS STA. _____ TO STA. _____

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5482	07-00171-00-FP	LEE	25	2

CONTRACT NO. 85429

FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT