

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982	*	SANGAMON	114	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
05-00447-01-PV		CITY OF SPRINGFIELD		

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY	LANDSCAPING	TRAFFIC SIGNALS
				CAPITOL AVENUE 05-00447-01-PV J000-2A	CAPITOL AVENUE 05-00447-01-PV Y003 (S)	CAPITOL AVENUE 05-00447-01-PV Y031-1F (S)
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	48	48		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	52	52		
20101100	TREE TRUNK PROTECTION	EACH	13	13		
* 20700400	POROUS GRANULAR EMBANKMENT (SPECIAL)	CU YD	42	42		
20800150	TRENCH BACKFILL	CU YD	687	687		
(S) * 25200700	SODDING, SPECIAL	SQ YD	675		675	
(S) 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	27	27		
28000510	INLET FILTERS	EACH	26	26		
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	8816	8816		
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	1311	1311		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	1055	1055		
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	106	106		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	347	347		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	118	118		
42000201	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SQ YD	5542	5542		
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	2198	2198		
42001300	PROTECTIVE COAT	SQ YD	14087	14087		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1633	1633		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	34014	34014		
* 42400610	TEMPORARY SIDEWALK	SQ FT	6255	6255		
* 42400800	DETECTABLE WARNINGS	SQ FT	376	376.0		
* 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	710	710		
50200100	STRUCTURE EXCAVATION	CU YD	631	631		
50300225	CONCRETE STRUCTURES	CU YD	170.3	170.3		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1		
50800105	REINFORCEMENT BARS	POUND	18510	18510		

* PAY ITEM REQUIRES A SPECIAL PROVISION

(S) DENOTES SPECIALTY ITEMS

LAYOUT	TCJ	03/27/07
DRAWN	TCJ	03/27/07
REVIEWED	MH	11/30/07

PLOT DATE = 01/10/2008 11:23 AM
 FILE NAME = \\s02\jobs\05-00447-01\road\road\vector\station\shmet\section.L7th-11th.c-004.S00.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = P000936

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAU RTE 7982 CAPITOL AVE
 SEC NO. 05-00447-01-PV
 SANGAMON COUNTY, ILLINOIS

VERT.
 SCALE: HORIZ.
 DATE 09/19/07

DRAWN BY TCJ
 CHECKED BY MH