

SUMMARY OF QUANTITIES

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982	*	SANGAMON	114	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 05-00447-01-PV		CITY OF SPRINGFIELD		

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY	LANDSCAPING	TRAFFIC SIGNALS
				CAPITOL AVENUE 05-00447-01-PV J000-2A 288	CAPITOL AVENUE 05-00447-01-PV Y003 (S)	CAPITOL AVENUE 05-00447-01-PV Y031-1F (S)
* X0323444	DECORATIVE STEEL RAILING	FOOT	288	288		
* X0324634	REMOVE, STOCKPILE AND REPLACE SIGN PANEL AND SIGN PANEL ASSEMBLY (SPECIAL)	EACH	28	28		
* X0325220	REMOVE AND REINSTALL SIGN PANEL	SQ FT	2	2		
* X0300266	WOODEN FENCE REMOVAL	FOOT	153	153		
* X8950305	REMOVE EXISTING SIGNAL HEAD	EACH	14			14
* X8950307	REMOVE EXISTING PEDESTRIAN SIGNAL HEAD	EACH	16			16
* XX000303	ORNAMENTAL LIGHTING UNIT COMPLETE	EACH	10			10
* XX000959	TRASH RECEPTACLES	EACH	7	7		
* XX001186	PLANTER REMOVAL	EACH	8	8		
* XX001286	SPECIAL EXCAVATION	CU YD	6672	6672		
* XX002189	RELOCATE EXISTING TRAFFIC SIGNAL CONTROLLER AND CABINET, COMPLETE	EACH	3			3
* XX003246	LIRIOPE SPICATA (1 QUART)	EACH	579		579	
* XX003273	SEDUM 'AUTUMN JOY' (1 GAL)	EACH	490		490	
* XX003308	TRENCH DRAIN	FOOT	12	12		
* XX003799	COPPER SERVICE, TYPE K 1"	FOOT	44		44	
* XX005799	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY GPS SYSTEM	EACH	3			3
* XX005908	PAVE-EDGE PAVER RETAINING SYSTEM	FOOT	258	258		
* XX005967	TOPSOIL (PLANTING MIXTURE)	CU YD	1135		1135	
* XX006599	TREE - ACER X FREEMANI 'ARMSTRONG' (ARMSTRONG FREEMAN MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	8		8	
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
* Z0022800	FENCE REMOVAL	FOOT	480	480		
* Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	5	5		
* Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	5	5		
* Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
* XX007320	REMOVE AND RELOCATE DROP BOXES	L SUM	1	1		

* PAY ITEM REQUIRES A SPECIAL PROVISION

(S) DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAU RTE 7982 CAPITOL AVE
SEC NO. 05-00447-01-PV
SANGAMON COUNTY, ILLINOIS

SCALE: VERT.
HORIZ.
DATE 09/19/07

DRAWN BY TCJ
CHECKED BY MH



LAYOUT TCJ 03/21/07
 DRAWN TCJ 03/21/07
 REVIEWED MH 11/20/07
 PLOT DATE = 01/18/2008 11:23 AM
 FILE NAME = I:\02_05A\02-0241\cadd\road\station\sheet\section_L74-11th\C-004_500.dgn
 PLOT SCALE = 50.000 / IN
 USER NAME = Pop06056

© Copyright Hanson Professional Services Inc. 2008