

SUMMARY OF QUANTITIES

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982	*	SANGAMON	114	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 05-00447-01-PV		CITY OF SPRINGFIELD		

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY	LANDSCAPING	TRAFFIC SIGNALS
				CAPITOL AVENUE 05-00447-01-PV	CAPITOL AVENUE 05-00447-01-PV	CAPITOL AVENUE 05-00447-01-PV
(S) * XX007321	PRECAST PLANTER EDGE TYPE 1	EACH	27	J000-2A 27	Y003 (S)	Y031-IF (S)
(S) * XX007322	PRECAST PLANTER EDGE TYPE 2	EACH	17	17		
* XX007323	LIMESTONE EDGER	FOOT	68	68		
* XX007324	RECYCLING RECEPTACLE	EACH	7	7		
* XX005962	BENCH	EACH	39	39		
* XX007325	REMOVE EXISTING TRAFFIC SIGNAL POST	EACH	16			16
* XX007326	VEGETATIVE SCREEN PANEL	SQ FT	3120	3120		
* XX007327	IRRIGATION BED 0.5 GPH	SQ FT	7631		7631	
* XX007328	IRRIGATION BED 1.0 GPH	SQ FT	3017		3017	
* XX007329	RAISED URN SUPPLY	EACH	20		20	
* XX007330	1 1/2" PVC, SCHEDULE 40 PIPE	FOOT	448		448	
* XX007331	1" PVC, SCHEDULE 40 PIPE	FOOT	2422		2422	
* XX007332	1 1/2" SCHEDULE 40 PIPE IN CASING	FOOT	165		165	
* XX007333	1" SCHEDULE 40 PIPE IN CASING	FOOT	203		203	
* XX007334	4" PVC CASING PIPE	FOOT	118		118	
* XX007335	8" PVC CASING PIPE	FOOT	125		125	
* XX007336	COPPER SERVICE, TYPE K 1 1/2"	FOOT	90		90	
* XX007337	1.5" RPZ ASSEMBLY	EACH	2		2	
* XX007338	1" RPZ ASSEMBLY	EACH	1		1	
* XX007339	2-STATION VALVE BOX ASSEMBLY	EACH	1		1	
* XX007340	4-STATION VALVE BOX ASSEMBLY	EACH	2		2	
* XX007341	IRRIGATION CONTROL WIRE IN 1" CONDUIT	FOOT	1344		1344	
* XX007342	TWO WIRE DECODER CONTROLLER	EACH	1		1	
* XX007343	MULCH, SHREDDED HARDWOOD, 4"	SQ YD	1260		1260	
* XX007344	TREE, QUERCUS WAREI 'REGAL PRINCE' (REGAL PRINCE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6		6	
* XX007345	ILLEX GLABRA 'SHAMROCK' (SHAMROCK INKBERRY HOLLY), 5 GAL. WELL DEVELOPED	EACH	32		32	

* PAY ITEM REQUIRES A SPECIAL PROVISION

(S) DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAU RTE 7982 CAPITOL AVE
 SEC NO. 05-00447-01-PV
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT. DATE 09/19/07
 HORIZ. DRAWN BY TCJ
 CHECKED BY MH



LAYOUT DATE: 03/27/07
 DRAWN BY: TCJ
 REVIEWED BY: MH
 PLOT DATE: 03/27/07
 FILE NAME: I:\Projects\05-00447-01-PV\Drawings\Summary of Quantities.dwg
 PLOT SCALE: 1/8" = 1'-0"
 USER NAME: Popper93