

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982	*	SANGAMON	114	12
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 05-00447-01-PV CITY OF SPRINGFIELD				

PAVEMENT SCHEDULE

LOCATION			SUB-BASE GRANULAR MATERIAL, TYPE A 4"	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)
BEGIN STATION	END STATION	OFFSET	SQ YD	GALLON	TON	SQ YD	SQ YD
CAPITOL AVENUE/7TH STREET INTERSECTION							
48+85.00	49+60.70	LT/RT		44	49		
49+55.96	50+36.70	LT/RT	813				
49+60.70	49+62.71	LT/RT					7
49+62.71	50+44.41	LT/RT					733
49+78.82	50+28.10	RT		5	6		
49+79.03	50+29.11	LT		6	6		
SUBTOTAL			813	55	62		740
CAPITOL AVENUE 7TH STREET - 9TH STREET							
50+36.70	50+93.91	RT	112				
50+93.91	51+79.91	RT	244				
51+79.91	57+48.21	RT	1113				
50+36.70	50+93.91	LT	112				
50+93.91	51+57.91	LT	181				
51+57.91	52+07.50	LT	97				
52+07.50	53+15.50	LT	306				
53+15.50	55+32.20	LT	422				
55+32.20	55+74.20	LT	119				
55+74.20	57+48.21	LT	339				
50+44.41	57+59.20	LT/RT				2648	
SUBTOTAL			3044			2648	
CAPITOL AVENUE/9TH STREET INTERSECTION							
57+48.21	58+65.33	LT/RT	888				
57+76.71	58+36.78	LT		7	7		
57+79.68	58+33.19	RT		6	7		
57+59.20	58+53.61	LT/RT					756
SUBTOTAL			888	13	14		756
CAPITOL AVENUE 9TH STREET - 11TH STREET							
58+65.33	59+02.60	RT	73				
59+02.60	59+88.60	RT	244				
59+88.60	60+59.60	RT	139				
60+59.60	61+97.46	RT	390				
62+06.28	62+94.42	RT	250				
62+94.42	64+09.42	RT	244				
64+09.42	64+95.42	RT	244				
64+95.42	65+36.64	RT	81				
58+65.33	59+02.63	LT	73				
59+02.63	59+66.63	LT	181				
59+66.63	61+72.21	LT	402				
61+72.21	61+97.46	LT	72				
62+06.28	62+94.43	LT	250				
62+94.43	64+75.43	LT	354				
64+75.43	64+95.43	LT	57				
64+95.43	65+36.64	LT	81				
58+53.61	61+97.46	LT/RT				1384	
62+06.28	65+44.43	LT/RT				1378	
SUBTOTAL			3132			2761	
CAPITOL AVENUE/11TH STREET INTERSECTION							
65+36.64	66+43.85	LT/RT	808				
65+44.43	66+35.91	LT/RT					702
65+65.03	66+14.91	RT		6	6		
65+65.47	66+15.36	LT		6	6		
66+35.91	66+75.50	LT/RT				133	
66+43.85	66+79.85	LT/RT	130				
66+75.50	67+40.00	LT/RT		27	30		
SUBTOTAL			939	38	43	133	702
TOTAL			8816	106	118	5542	2198

CURB AND GUTTER SCHEDULE

LOCATION			CONCRETE GUTTER	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18
BEGIN STATION	END STATION	OFFSET	FOOT	FOOT
CAPITOL AVENUE/7TH STREET INTERSECTION				
49+32.00	49+55.96	RT		27.0
49+32.00	49+55.96	LT		27.0
49+55.96	49+81.92	RT		78.0
49+55.96	49+82.15	LT		72.0
50+24.88	50+36.70	RT		61.0
50+25.98	50+36.70	LT		61.0
SUBTOTAL				326.0
CAPITOL AVENUE 7TH STREET - 9TH STREET				
50+36.70	50+98.91	LT		62.2
50+36.70	50+98.91	RT		62.2
50+98.91	51+52.91	LT	54.0	
50+98.91	51+74.91	RT	76.0	
51+52.91	52+12.50	LT		59.6
51+74.91	54+00.00	RT		225.1
52+12.50	53+10.50	LT	98.0	
53+10.50	54+00.00	LT		89.5
54+00.00	55+37.20	LT		137.2
54+00.00	57+48.21	RT		348.2
55+37.20	55+89.20	LT	32.0	
55+69.20	57+48.21	LT		183.0
SUBTOTAL			260.0	1167.0
CAPITOL AVENUE/9TH STREET INTERSECTION				
57+48.21	57+78.21	LT		47.0
57+48.21	57+81.19	RT		50.0
58+31.66	58+65.33	RT		51.0
58+35.28	58+65.33	LT		45.0
SUBTOTAL				193.0
CAPITOL AVENUE 9TH STREET - 11TH STREET				
58+65.33	59+07.60	RT		42.3
58+65.33	59+07.63	LT		42.3
59+07.60	59+83.60	RT	76.0	
59+07.63	59+61.63	LT	54.0	
59+61.63	61+77.21	LT		215.6
59+83.60	60+64.60	RT		81.0
60+64.60	61+97.46	RT	132.9	
61+77.21	61+97.46	LT	20.3	
62+06.28	62+89.42	RT	83.2	
62+06.32	62+89.43	LT	83.1	
62+89.42	63+92.42	RT		103.0
62+89.43	64+80.43	LT		191.0
63+92.42	64+90.42	RT	98.0	
64+80.43	64+90.43	LT	10.0	
64+90.42	65+36.50	RT		46.1
64+90.43	65+36.50	LT		46.1
SUBTOTAL			557.4	767.3
CAPITOL AVENUE/11TH STREET INTERSECTION				
65+36.50	65+66.50	RT		47.0
65+36.50	65+66.97	LT		45.0
66+13.67	66+43.85	RT		45.0
66+13.85	66+43.85	LT		45.0
66+43.85	66+79.40	RT		37.0
66+43.85	66+79.40	LT		37.0
SUBTOTAL				256.0
TOTAL			817.5	2709.5

DRIVEWAY AND SIDEWALK SCHEDULE

LOCATION			PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH
BEGIN STATION	END STATION	OFFSET	SQ YD	SQ FT
CAPITOL AVENUE/7TH STREET INTERSECTION				
49+54.84	49+83.00	LT		426.0
49+54.79	49+83.59	RT		545.0
50+23.76	50+36.69	RT		260.0
50+24.02	50+36.69	LT		259.0
SUBTOTAL				1490.0
CAPITOL AVENUE 7TH STREET - 9TH STREET				
50+36.69	53+27.39	LT		5098.9
50+36.69	51+93.24	RT		2197.9
52+14.76	53+97.34	RT		1167.0
53+66.96	54+41.16	LT		1113.2
54+12.41	55+99.27	RT		1122.0
54+65.89	54+85.68	LT		296.6
55+20.30	56+29.20	LT		1631.0
56+12.09	57+48.20	RT		1198.6
57+05.19	57+48.21	LT		863.7
	52+03.90	RT	64	
	53+37.50	LT	146	
	54+06.21	RT	45	
	54+54.07	LT	101	
	55+04.16	LT	130	
	56+05.68	RT	40	
	56+67.74	LT	209	
SUBTOTAL			735	14688.8
CAPITOL AVENUE/9TH STREET INTERSECTION				
57+48.20	57+75.24	LT		391.0
57+48.20	57+78.22	RT		457.0
58+34.61	58+65.36	RT		469.5
58+38.26	58+65.36	LT		393.7
SUBTOTAL				1711.2
CAPITOL AVENUE 9TH STREET - 11TH STREET				
58+65.36	59+78.64	LT		1738.0
58+65.36	60+30.60	RT		2518.7
60+15.63	60+52.65	LT		555.0
60+47.60	61+94.11	RT		1673.0
61+77.61	61+94.07	LT		247.0
62+10.04	63+01.43	RT		1411.0
62+10.07	63+11.43	LT		1559.0
63+33.43	63+87.42	RT		817.0
63+45.43	64+31.42	LT		1289.0
64+07.42	64+53.42	RT		660.0
64+63.43	65+36.50	LT		1136.0
64+73.42	65+36.50	RT		947.0
	59+95.92	LT	106	
	60+40.15	RT	52	
	61+12.37	LT	317	
	61+45.63	RT	83	
	63+18.69	RT	88	
	63+27.01	LT	92	
	63+97.42	RT	37	
	64+47.21	LT	89	
	64+63.42	RT	33	
SUBTOTAL			898	14550.7
CAPITOL AVENUE/11TH STREET INTERSECTION				
65+36.50	65+64.44	LT		425.0
65+36.50	65+63.52	RT		416.0
66+16.38	66+43.91	LT		364.0
66+16.64	66+43.91	RT		367.8
SUBTOTAL				1572.8
TOTAL			1633	34013.5

EARTHWORK SCHEDULE

LOCATION		SUB-BASE GRANULAR MATERIAL, TYPE C	SPECIAL EXCAVATION
BEGIN STATION	END STATION	TON	CU YD
CAPITOL AVENUE/7TH STREET INTERSECTION			
49+31.89	50+36.71	58	678
SUBTOTAL		58	678
CAPITOL AVENUE 7TH STREET - 9TH STREET			
50+36.71	57+48.23	826	2462
SUBTOTAL		826	2462
CAPITOL AVENUE/9TH STREET INTERSECTION			
57+48.23	58+65.28	125	526
SUBTOTAL		125	526
CAPITOL AVENUE 9TH STREET - 11TH STREET			
58+65.28	65+36.50	1264	2357
SUBTOTAL		1264	2357
CAPITOL AVENUE/11TH STREET INTERSECTION			
65+36.50	66+79.40	93	649
SUBTOTAL		93	649
REDUCTION FROM AGGREGATE FOR TEMPORARY ACCESS			
JOB TOTAL		-1055	
SUBTOTAL		-1055	
TOTAL		1311	6672

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAU RTE 79