

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982	*	SANGAMON	114	15
STA.	TO STA.			
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 05-00447-01-PV		CITY OF SPRINGFIELD		

UTILITY ADJUSTMENT SCHEDULE

LOCATION	EXISTING ELEVATION	PROPOSED ELEVATION	ELEVATION DIFFERENCE	MANHOLES TO BE ADJUSTED EACH	FRAMES AND LIDS TO BE ADJUSTED EACH	NOTES
7TH ST. INTERSECTION						
48+93.81	7.36' RT	593.61	593.57	-0.04	1	WATER VALVE
49+60.92	29.76' LT	595.21	595.16	-0.05	1	TRAFFIC SIGNAL
49+84.23	19.97' LT	595.32	595.02	-0.30	1	ELECTRIC
49+99.41	3.02' LT	595.69	595.45	-0.24	1	N/A
50+03.52	41.12' RT	595.25	595.27	0.02	1	SEWER
50+04.21	4.05' LT	595.72	595.51	-0.21	1	SEWER
50+09.10	2.57' RT	595.71	595.48	-0.23	1	N/A
50+09.30	7.14' RT	595.65	595.42	-0.23	1	WATER VALVE
50+10.82	27.00' RT	595.40	595.25	-0.15	1	ELECTRIC
50+15.74	34.30' RT	595.30	595.12	-0.18	1	WATER VALVE
50+19.29	39.69' RT	595.22	595.04	-0.18	1	WATER VALVE
50+29.55	26.75' LT	595.01	595.51	0.50	1	SEWER
SUBTOTAL				9	3	
MIDBLOCK OF 7TH ST. AND 9TH ST.						
50+42.69	24.19' RT	595.61	595.87	0.26	1	WATER VALVE
50+70.04	37.59' RT	596.31	596.32	0.01	1	GAS VALVE
51+06.72	24.35' RT	596.06	596.14	0.08	1	WATER VALVE
51+34.44	26.06' LT	595.81	596.23	0.42	1	SEWER
51+97.44	19.33' LT	596.13	596.31	0.18	1	ELECTRIC
52+17.03	26.25' RT	596.42	596.58	0.16	1	ELECTRIC
52+45.32	25.84' LT	595.76	596.39	0.63	1	SEWER
52+83.12	7.90' LT	596.10	596.01	-0.09	1	N/A
53+16.29	31.05' RT	596.11	596.34	0.23	1	GAS VALVE
53+77.80	36.52' LT	595.67	595.71	0.04	1	ELECTRIC
53+78.55	18.27' LT	595.13	595.25	0.12	1	ELECTRIC
53+88.09	26.81' RT	595.59	595.19	-0.40	1	ELECTRIC
53+97.71	35.96' LT	595.65	595.73	0.08	1	ELECTRIC
54+03.58	21.74' LT	595.30	595.37	0.07	1	SEWER
54+15.31	31.54' RT	595.34	595.25	-0.09	1	WATER VALVE
54+15.33	17.32' RT	595.42	594.97	-0.45	1	WATER VALVE
54+17.51	12.66' LT	595.64	594.82	-0.82	1	SEWER
54+22.57	7.76' LT	595.67	594.94	-0.73	1	N/A
54+29.13	20.54' RT	595.28	595.21	-0.07	1	WATER VALVE
54+52.76	22.10' LT	595.49	595.26	-0.23	1	ELECTRIC
54+62.24	18.20' RT	595.25	595.46	0.21	1	WATER VALVE
55+20.77	29.64' RT	596.28	596.29	0.01	1	WATER VALVE
56+02.67	21.27' LT	596.01	596.34	0.33	1	ELECTRIC
56+17.49	28.43' RT	596.36	596.52	0.16	1	ELECTRIC
56+72.63	32.19' RT	596.76	596.73	-0.03	1	WATER VALVE
SUBTOTAL				13	12	
9TH ST. INTERSECTION						
57+48.98	13.41' LT	595.48	595.21	-0.27	1	TELEPHONE
57+60.96	18.32' RT	595.08	595.17	0.09	1	WATER VALVE
57+82.60	32.32' RT	594.79	594.94	0.15	1	GAS VALVE
57+90.63	21.26' LT	595.54	595.67	0.13	1	ELECTRIC
57+93.32	27.27' RT	595.08	595.26	0.18	1	ELECTRIC
58+05.01	9.50' RT	595.50	595.64	0.14	1	SEWER
58+24.21	21.67' LT	595.41	595.68	0.27	1	ELECTRIC
58+29.77	19.90' RT	595.24	595.51	0.27	1	WATER VALVE
58+33.63	24.90' RT	595.17	595.34	0.17	1	ELECTRIC
58+35.80	5.98' RT	595.63	595.72	0.09	1	ELECTRIC
58+53.19	26.56' RT	595.93	595.74	-0.19	1	ELECTRIC
SUBTOTAL				7	4	
MIDBLOCK OF 9TH ST. AND 11TH ST.						
59+79.06	21.47' LT	596.71	597.58	0.87	1	N/A
60+66.57	0.77' RT	598.72	598.72		1	SEWER
60+71.66	25.14' LT	598.47	598.90	0.43	1	N/A
60+75.67	27.03' RT	598.31	598.47	0.16	1	N/A
60+79.04	19.57' LT	598.57	598.65	0.08	1	N/A
60+80.49	22.32' RT	598.26	598.55	0.29	1	WATER VALVE
61+53.52	0.08' RT	600.08	600.54	0.46	1	SEWER
62+08.65	25.12' LT	601.24	601.14	-0.10	1	ELECTRIC
63+60.89	18.55' LT	598.66	598.91	0.25	1	ELECTRIC
63+65.70	25.35' LT	598.86	599.00	0.14	1	ELECTRIC
63+95.72	3.44' RT	598.67	598.56	-0.11	1	ELECTRIC
64+01.69	0.39' RT	598.81	598.62	-0.19	1	ELECTRIC
SUBTOTAL				11	1	
11TH ST. INTERSECTION						
65+60.65	25.85' LT	598.17	598.00	-0.17	1	ELECTRIC
65+84.32	10.10' RT	598.66	598.59	-0.07	1	WATER VALVE
65+90.67	26.96' RT	598.69	598.67	-0.02	1	SEWER
66+01.87	10.18' RT	598.53	598.45	-0.08	1	WATER VALVE
66+24.38	26.39' LT	598.01	598.41	0.40	1	TRAFFIC SIGNAL
SUBTOTAL				2	3	
TOTAL				42	23	

**LIGHTING SCHEDULE - FOR INFORMATION ONLY
TO BE COMPLETED BY CWLP**

LOCATION	REMOVE EXISTING UTILITY POLE	REMOVE EXISTING LIGHT POLE	ORNAMENTAL PEDESTRIAN LIGHT	ORNAMENTAL STREET LIGHT	ORNAMENTAL STREET LIGHT FOUNDATION	NOTES
CAPITOL AVENUE/7TH STREET INTERSECTION						
49+61.69	26.00' LT				1	COMBINATION LIGHT/TRAFFIC SIGNAL
49+61.71	26.00' RT				1	COMBINATION LIGHT/TRAFFIC SIGNAL
50+45.90	26.00' LT				1	COMBINATION LIGHT/TRAFFIC SIGNAL
50+45.93	26.00' LT				1	COMBINATION LIGHT/TRAFFIC SIGNAL
SUBTOTAL				4		
CAPITOL AVENUE 7TH STREET - 8TH STREET						
50+60.27	31.53' LT					
51+44.47	31.47' LT					
52+28.39	31.37' LT					
53+12.61	31.31' LT					
SUBTOTAL				4		
CAPITOL AVENUE 8TH STREET - 9TH STREET						
54+04.40	37.56' LT					
54+73.21	29.29' LT					
54+76.68	29.57' LT					
55+27.54	29.47' LT					
56+13.65	29.64' LT					
56+20.71	28.68' LT					
57+21.46	29.60' LT					
SUBTOTAL				7		
CAPITOL AVENUE 9TH STREET INTERSECTION						
57+56.55	28.05' LT					
57+58.19	26.00' LT				1	COMBINATION LIGHT/TRAFFIC SIGNAL
57+58.21	26.00' RT				1	COMBINATION LIGHT/TRAFFIC SIGNAL
58+54.60	26.00' RT				1	COMBINATION LIGHT/TRAFFIC SIGNAL
58+54.62	26.00' LT				1	COMBINATION LIGHT/TRAFFIC SIGNAL
58+60.66	24.63' RT				1	
SUBTOTAL				2	4	
CAPITOL AVENUE 9TH STREET - 10TH STREET						
60+69.77	24.30' RT				1	
59+66.86	25.96' LT				1	
61+21.58	31.47' RT				1	
61+80.26	30.65' RT				1	
SUBTOTAL				2	2	
CAPITOL AVENUE 10TH STREET - 11TH STREET						
63+49.54	28.35' LT				1	
64+43.92	18.44' RT				1	
SUBTOTAL				1	1	
CAPITOL AVENUE/11TH STREET INTERSECTION						
65+36.90	26.00' LT				1	COMBINATION LIGHT/TRAFFIC SIGNAL
65+43.42	26.00' RT				1	COMBINATION LIGHT/TRAFFIC SIGNAL
65+43.43	26.00' LT				1	COMBINATION LIGHT/TRAFFIC SIGNAL
65+47.04	17.95' LT					
65+52.88	44.43' RT					
65+53.76	30.60' LT					
65+61.27	41.37' LT					
66+16.93	32.57' RT					
66+18.31	31.08' LT					
66+36.90	26.00' RT				1	COMBINATION LIGHT/TRAFFIC SIGNAL
SUBTOTAL				2	4	
TOTAL				5	20	

**HYDRANT SCHEDULE - FOR INFORMATION ONLY
TO BE COMPLETED BY CWLP**

LOCATION	FIRE HYDRANTS TO BE REMOVED	FIRE HYDRANTS
CAPITOL AVENUE/7TH STREET INTERSECTION		
50+31.57	57.36' RT	1
50+31.57	57.36' RT	1
SUBTOTAL		
1		
CAPITOL AVENUE 8TH STREET - 9TH STREET		
54+35.83	30.28' RT	1
54+35.83	30.28' RT	1
SUBTOTAL		
1		
CAPITOL AVENUE/9TH STREET INTERSECTION		
58+40.26	41.41' LT	1
58+38.26	41.41' LT	1
SUBTOTAL		
1		
CAPITOL AVENUE 9TH STREET - 10TH STREET		
60+84.58	26.00' RT	1
60+80.39	26.05' RT	1
SUBTOTAL		
1		
CAPITOL AVENUE 10TH STREET - 11TH STREET		
65+25.30	26.00' RT	1
65+25.26	21.61' RT	1
SUBTOTAL		
1		
CAPITOL AVENUE/11TH STREET INTERSECTION		
66+19.38	41.92' RT	1
66+19.38	41.92' RT	1
SUBTOTAL		
1		
TOTAL		
		6

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES
NAME	DATE	
		FAU RTE 7982 CAPITOL AVE SEC NO. 05-00447-01-PV SANGAMON COUNTY, ILLINOIS SCALE: VERT. / HORIZ. DATE 09/19/07



LAYOUT: TCJ 03/21/07
 DRAWN: TCJ 03/21/07
 REVIEWED: MH 11/30/07
 PLOT DATE = 01/18/2006 10:29 AM
 FILE NAME = H:\22jobs\02\20\01\aeddd\road\minterstation\sheet\section_11\7th-11th\C-005-SCHED.dgn
 PLOT SCALE = 50:000 / IN.
 USER NAME = Pj000536

DRAWN BY: TCJ
 CHECKED BY: MH