CONTRACT NO. 93450

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982	*	SANGAMON	114	19
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 05-00447-01-PV CITY OF SPRINGFIELD

IRRIGATION SCHEDULE

LOCATION			IRRIGATION BED 0.5 GPH	IRRIGATION BED 1.0 GPH	RAISED URN SUPPLY	1 1/2" PVC SCHEDULE 40 PIPE	1" PVC SCHEDULE 40 PIPE	1 1/2" PVC SCHEDULE 40 PIPE IN CASING	1" PVC SCHEDULE 40 PIPE IN CASING	4" PVC CASING PIPE	8" PVC CASING PIPE	COPPER SERVICE . TYPE K 1 1/2"	COPPER SERVICE . TYPE K 1"	1.5" RPZ ASSEMBLY	1" RPZ ASSEMBLY	2-STATION VALVE BOX ASSEMBLY	4-STATION VALVE BOX ASSEMBLY	IRRIGATION CONTROL WIRE IN 1" CONDUIT	TWO WIRE DECODER CONTROLLER
BEGIN STATION	END STATION	OFFSET	SQ FT	SQ FT	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	FOOT	EACH
CAPITOL AVENUE/7TH STREET INTERSECTION																			
49+78.50	49+83.92	LT	134																
50+24.10	50+29.93	LT	140																
49+78.15	49+16.41	RT	136																
50+23.75	50+28.26	RT	115																
49+55.96	49+81.42	LT					56												
50+27.19	50+36.70	LT					32												
49+55.96	50+36.70	LT																81	
49+55.96	49+80.68	RT					55												
50+25.96	50+36.70	RT					36												
		SUBTOTAL	525				179											81	
CAPITOL AVENUE 7TH STREET - 9TH STREET																			
50+44.92	50+66.92	LT	174																
50+71.90	50+91.92	LT	160																
51+59.91	52+05.50	LT	361																
53+17.5	53+20.31	LT	23																
53+71.52	54+34.35	LT	500																
54+73.81	54+80.91	LT	57																
55+27.45	55+30.22	LT	22																
55+74.20	56+17.87	LT	345																
57+13.33	57+32.20	LT	150																
57+37.20	57+57.21	LT	160																
50+50.01	50+66.90	RT	160																
50+71.91	50+91.90	RT	160																
51+81.91	51+87.69	RT	46																
52+19.10	52+21.04	RT	12																
53+64.99	53+97.34	RT	512																
54+12.41	54+44.32	RT	503																
55+74.71	55+99.27	RT	316																
56+12.09	56+23.71	RT	159																
57+12.21	57+32.21	RT	160																
57+37.21	57+57.21	RT	160																
50+36.70	54+00.00	LT					369												
50+36.70	54+00.00	LT																364	
50+36.70	52+23.41	RT					187												
52+23.41	54+00.00	RT				177													
54+00.00	54+33.18	LT					37												
54+24.58	54+29.43	LT										50							
54+30.21		LT												1					
54+30.21		LT																	1
54+32.42		LT															1		
54+34.81		LT						38	38		38								
54+33.18	57+48.21	LT					318												
54+33.18	54+34.81	LT				8	8												
54+00.00	54+34.81	RT				40													
54+12.96	57+48.21	RT					343												
51+14.91		LT			1														
51+14.91		RT			1														
51+58.90		RT			1														
52+50.50		LT			1														
52+94.50		LT			1														
54+18.32		LT			1														
55+53.20		LT			1														
		SUBTOTAL	4140		7	225	1262	38	38		38	50		1			1	364	1
CAPITOL AVENUE/9TH STREET INTERSECTION																			
57+48.21	57+56.51						9												
58+58.63	58+65.33						7												
57+48.21	57+56.30						9												
58+57.45	58+65.33						8												
57+48.21	58+63.33																	118	
		SUBTOTAL					33											118	
CAPITOL AVENUE 9TH STREET - 11TH STREET																			
58+55.63	58+75.63	LT	160																
58+80.61	59+00.63	LT	160																
59+68.63	59+71.34	LT	22																
60+20.50	60+49.26	LT	229																
62+96.42	63+06.12	LT	77																
63+47.90	64+26.47	LT	622																
64+67.95	64+73.42	LT	44																
64+97.42	65+17.42	LT	160																
65+22.42	65+42.42	LT	160																
58+55.63	58+75.63	RT	160																
58+80.63	59+00.63	RT	160																
59+90.59	60+26.31	RT	283																
60+53.98	60+57.60	RT	29																
62+96.42	62+98.14	RT	14																
63+39.24	63+85.42	RT	366																
64+97.42	65+17.42	RT	160																

NOTE:

ADDITIONAL/INCIDENTAL MATERIALS NECESSARY FOR INSTALLATION OF THE IRRIGATION SYSTEM, FOR WHICH NO INDIVIDUAL PAY ITEMS HAVE BEEN PROVIDED, WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE VARIOUS RELATED ITEMS OF WORK, AS SCHEDULED.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAU RTE 7982 CAPITOL AVE
SEC NO. 05-00447-01-PV
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ.
DATE 09/19/07
DRAWN BY TCJ
CHECKED BY MH

© Copyright Hanson Professional Services Inc. 2008

HANSON

LAYOUT	TCJ	03/21/07
DRAWN	TCJ	03/21/07
REVIEWED	MH	11/30/07

PLOT DATE = 6\18\2008,10:21 AM
FILE NAME = H:\Projects\82x2841a\sadl\cad\maintenance\sheet\section_1_7th-11th\C-0005_SCHED.dgn
PLOT SCALE = 50.0000 ' / in.
USER NAME = Pop08036