

SUMMARY OF QUANTITIES

0021

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	S.I.	SP PR
20101200	TREE ROOT PRUNING	EACH	3.0		
<del>20200100</del>	<del>EARTH EXCAVATION</del>	<del>CU YD</del>	<del>2.00</del>		
20800150	TRENCH BACKFILL	CU YD	46.		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	540.		
25000110	SEEDING, CLASS 1A	ACRE	0.1		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10.0		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10.0		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10.0		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	9.0		
28000400	PERIMETER EROSION BARRIER	FOOT	1,290.0		
28000510	INLET FILTERS	EACH	15.0		
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	540		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	8,793.0		
42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	1,390.0		
42400800	DETECTABLE WARNINGS	SQ FT	48.0		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	386.		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	183.0		
44000600	SIDEWALK REMOVAL	SQ FT	660.0		
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	10.	X	
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	47	X	
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	22	X	
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	27.	X	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	22.0		

SUMMARY OF QUANTITIES

0021

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	S.I.	SP PR
56103000	DUCTILE IRON WATER MAIN 6"	FOOT	29.0	X	*
56200300	WATER SERVICE LINE 1"	FOOT	30.0	X	
56201400	CORPORATION STOPS 1"	EACH	2.0	X	*
56400510	FIRE HYDRANTS TO BE REMOVED AND REPLACED	EACH	1.0	X	*
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	5.0	X	*
56500800	DOMESTIC WATER SERVICE BOXES	EACH	2.0	X	*
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1.0		
60207905	CATCH BASINS, TYPE C, TYPE 11 FRAME AND GRATE	EACH	1.0		
60255700	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	3.0		
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4.0		
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4.0		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	183.0		
67100100	MOBILIZATION	L SUM	1.0		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.0		
72000100	SIGN PANEL - TYPE 1	SQ FT	17.0		
72900100	METAL POST - TYPE A	FOOT	28.0		
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	237.0	X	
78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	48.0	X	
Z0004514	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 4"	SQ YD	386	X	*
Z0015000	CURB STOPS 1"	EACH	2.0		*

FILE NAME \*  
P:\2012\120146\oad\phase 2\deg-East Side

USER NAME \* #USER\*  
E:\mshatad\120146-sht-notes.dgn  
PLOT SCALE \* #SCALE#  
PLOT DATE \* 2/20/2014

DESIGNED - RCL  
DRAWN - RCL  
CHECKED -  
DATE -

REVISED  $\Delta$  - 4-15-2014  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

WOODSTOCK SAFE ROUTES  
SUMMARY OF QUANTITIES

SCALE: NTS SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0037	12-00112-00-SW	MCHENRY	20	3
CONTRACT NO. 61A15				
ILLINOIS FED. AID PROJECT				