

LOCATION OF WORK:

FAP 711 (IL 119) S. N. 092-0207
 RURAL TWO LANE RURAL TWO LANE
 MINOR ARTERIAL MINOR ARTERIAL
 STA. 721+50 TO STA. 744+00 STA. 729+38.75 TO STA. 732+31.25
 VERMILION COUNTY VERMILION COUNTY

FUNDING BREAKOUT:
 CONSTRUCTION TYPE CODE:

80% FEDERAL, 20% STATE 80% FEDERAL, 20% STATE
 0004 0011

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	843.0	843.0 0.0
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	577.0	577.0 0.0
20200100	EARTH EXCAVATION	CU YD	210.0	210.0 0.0
20300100	CHANNEL EXCAVATION	CU YD	4,131.0	4,131.0 0.0
20400800	FURNISHED EXCAVATION	CU YD	670.0	670.0 0.0
• 25000210	SEEDING, CLASS 2A	ACRE	1.0	1.0 0.0
• 25000350	SEEDING, CLASS 7	ACRE	3.0	3.0 0.0
• 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90.0	90.0 0.0
• 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90.0	90.0 0.0
• 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90.0	90.0 0.0
• 25100125	MULCH, METHOD 3	ACRE	3.0	3.0 0.0
• 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	4,840.0	4,840.0 0.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,800.0	2,800.0 0.0
28000305	TEMPORARY DITCH CHECKS	FOOT	170.0	170.0 0.0
• DENOTES SPECIALTY ITEM				

EFK Moen, LLC
 Civil Engineering Design

FILE NAME :	USER NAME : detersbj	DESIGNED - JRD	REVISED - BJH 01/08/2014	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
01\pvc\work\pvidot\detersbj\0373988\03-	05-D978614-ahtr-500.dgn	DRAWN - MSK	REVISED -		711	116BR-1	VERMILION	84	3				
	PLOT SCALE = 48.0000' / in.	CHECKED - SLD	REVISED -		CONTRACT NO. 70614								
	PLOT DATE = 1/13/2014	DATE - 10/18/13	REVISED -		SCALE: N.A.	SHEET NO. 1 OF 8 SHEETS			ILLINOIS FED. AID PROJECT				