

PAVEMENT SCHEDULE

STATION TO STATION	31100700	35501312	35501318	35650200	BASE COURSE WIDENING, 8 1/2"	40600200	40600300	406000837	40603085	40603540	
	SUBBASE GRANULAR MATERIAL, TYPE A 8"	HOT-MIX ASPHALT BASE COURSE, 7"	HOT-MIX ASPHALT BASE COURSE, 8 1/2"	BASE COURSE WIDENING, 7"		BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	
SQ YD					TON						
MAINLINE WABASH AVENUE											
WABASH AVE (FAU 8012)											
340+00.00	357+40.94	5,941		5,573		5.7	30	998		977	
357+40.94	361+37.69	2,246		80	1,713	5.1	27	539		733	
361+37.69	366+19.35	1,938		1,745		3.6	19	532		536	
366+19.35	367+61.39	554			435	1.7	9	242		255	
367+61.39	382+60.23	5,539		4,183		7.8	41	1,114		1,139	
382+60.23	383+91.15	644			513	1.8	9	243		254	
383+91.15	389+15.49	2,689		2,420		3.9	21	575	14	561	
389+15.49	393+05.74	3,568		2,430		4.8	25	640	384	695	
393+05.74	408+01.83	6,175		5,592		9.2	48	1,097		1,319	
408+01.83	409+71.52	803		444	275	1.3	7	216		195	
409+71.52	414+99.27	1,646		1,445		2.7	15	396		395	
414+99.27	417+20.62	665		292	246	1.7	9	175	51	252	
417+20.62	424+95.08	2,827		2,449		4.5	23	492	650	655	
424+95.08	427+48.98	1,848		1,681		2.1	11	249	296	313	
427+48.98	431+88.53	2,519		2,199		3.2	17	487	268	482	
431+88.53	433+43.53	497		237	168	1.1	6	132	268	185	
433+43.53	436+70.35	1,114		883		2.0	11	266	71	294	
436+70.35	440+46.20	1,834			1,221	4.1	22	1,134	800	625	
440+46.20	451+32.10	4,095		3,555		6.5	34	1,061	198	950	
451+32.10	455+21.44	3,173		1,911	715	4.5	24	371	251	659	
455+21.44	463+23.01	2,737		2,173		4.5	24	498	533	682	
463+23.01	466+38.15	1,188		440	460	2.6	14	376	20	383	
466+38.15	482+20.69	4,365		3,449		9.0	47	1,349	243	1,322	
482+20.69	485+54.30	540			311	4.2	22	61		610	
485+54.30	492+79.37					4.2	22			620	
RAMP C											
11+11.46	15+31.46	544		463		1.1	6	66		190	
RAMP A											
13+36.88	18+38.48	938		726		1.4	7	76		207	
BUNKER HILL RD											
1+37.00	8+02.44	3,082	2,661			2.0	11			297	
ASH GROVE RD											
11+93.41	12+42.18	5		5		0.2	1	16		22	
ARCHER ELEVATOR RD											
11+42.19	14+66.85	1,719	1,485			1.2	6			166	
14+66.85	18+03.15	340	280			0.8	4	37	132	119	
MERCANTILE DR											
4+20.48	5+23.29					0.4	2			54	
5+23.29	6+61.08	641	413		111	1.2	6			182	
6+61.08	8+56.86	67				1.0	5			146	
STADIUM DR											
10+80.09	12+73.99	368			228	0.6	3			78	
HOLLIS DR											
9+75.00	19+16.01	4,139	3,495			2.7	14			391	
KOKE MILL RD											
24+15.14	27+68.24	382	257			2.1	11			308	
SUBTOTAL											
		71,370	8,591	44,375	339	6,810	116.5	613	13,437	4,831	17,251
HOLLIS EAST LIMITS TO 9+75 & COCKRELL											
HOLLIS DR											
25+23.22	28+08.34					0.9	5			127	
STA 28+08.34 BK =STA 0+00.00 AH											
0+00.00	3+66.85	1,674	1,425			1.1	6			160	
3+66.85	6+52.06	2,952	2,437			1.9	10			273	
6+52.06	9+75.00	1,504	1,297			1.0	5			145	
COCKRELL LN											
11+02.35	12+23.26					0.2	1			33	
12+23.26	13+14.10	511	480			0.4	2			54	
13+14.10	14+23.02	858	804			0.6	3			90	
14+23.02	18+60.40	2,396	2,093			1.6	9			234	
SUBTOTAL											
		9,895	8,536	0	0	0	7.7	41	0	0	1,116
TURN LANE AND BICYCLE LANE ON ARCHER											
ARCHER ELEVATOR RD											
11+42.19	14+66.85	721	721			0.5	3			81	
SUBTOTAL											
		721	721	0	0	0	0.5	3	0	0	81
ADDITIONAL BIKE LANES ON MERCANTILE (4' WIDTH WABASH TO STADIUM)											
MERCANTILE DR											
6+61.08	8+56.86	87	87			0.1	1			10	
SUBTOTAL											
		87	87	0	0	0	0.1	1	0	0	10
TOTALS											
		82,073	17,935	44,375	339	6,810	124.8	658	13,437	4,831	18,458

SURFACE REMOVAL - BUTT JOINT

STATION TO STATION	40600982	40600985
	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT
SQ YD		
MAINLINE WABASH AVENUE		
WABASH AVE (FAU 8012)		
340+00.0	340+30.0	73.3
INTERNATIONAL PKWY		
12+25.98	12+40.98	60.1
BUNKER HILL RD & ASH GROVE RD		
12+27.18	12+42.18	59.4
ARCHER ELEVATOR RD		
17+33.15	18+0.15	169.5
PLEASANT RUN		
9+07.05	9+22.05	80.0
NORTH MEADOWBROOK RD		
11+70.95	11+85.95	57.3
SOUTH MEADOWBROOK RD		
63+35.15	63+50.15	59.9
SUBTOTAL		486.2
USE		74
HOLLIS EAST LIMITS TO 9+75 & COCKRELL LANE		
COCKRELL LN		
11+03.26	12+23.26	236.0
SUBTOTAL		236.0
USE		0
TOTAL		723
		74

PROTECTIVE COAT

CONCRETE ITEM	42001300
	PROTECTIVE COAT SQ YD
MAINLINE WABASH AVENUE	
TY M-6.06 CURB AND GUTTER	82
TY M-6.12 CURB AND GUTTER	46
TY M-6.18 CURB AND GUTTER	11
TY M-6.24 CURB AND GUTTER	332
TY B-6.12 CURB AND GUTTER	85
TY B-6.18 CURB AND GUTTER	1197
TY B-6.24 CURB AND GUTTER	2565
CONCRETE GUTTER, TY B	65
TYPE B GUTTER OUTLET	18
CONCRETE MEDIAN SURFACE 4"	734
CONCRETE MEDIAN TY SM-6.06	451
CONCRETE MEDIAN TY SM-6.12	109
CONCRETE MEDIAN TY SM (DOWELLED)	1855
SUBTOTAL	
USE	7550
HOLLIS EAST LIMITS TO 9+75 & COCKRELL LANE	
COCKRELL LANE	
TY M-6.06 CURB AND GUTTER	16
TY M-6.24 CURB AND GUTTER	55
TY B-6.18 CURB AND GUTTER	875
CONCRETE MEDIAN SURFACE 4"	190
CONCRETE CURB, TY B (SPECIAL)	3
SUBTOTAL	
USE	1139
TOTAL	
	8,689