STORM SEWER SCHEDULE (CONTINUED FROM PREVIOUS SHEET)

STATION	OFFSET	SIDE	TYPE	STANDARD AND DESIGN NUMBER	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	15"	24"	60"	PRC FLARED DROP BOX END SECTIONS ERS, ELLIPTICAL WITH GRATE 42"	48"	METAL END SECTIONS 12"	PIPE DRAINS 12"	MANHOLES, TYPE A 4' A-1-C	4' A-3	4' A-3V	4' A-8	4' A-10	5' A-1-C	5' A-3V	5' A-8	5' MEDIAN INLET (604106)	6' A-1-C	6' A-1-C SPL	6' A-3V	6' A-8	7' A-1-C	7' A-3V	7' A-8	8' A-3V	8' A-1-C	9' A-3V	9' MEDIAN INLET (604106)	SPECIAL	INLETS TYPE A A-3	A-3V	A-8	A-10	TYPE B B-1-C	B-3V	B-8	B-10	MEDIAN INLET (604106)	TYPE E SPECIAL 4'x4'	INLET BOX TYPE E STD 610001	STORM SEWERS, CLASS A, TYPE 2 60"	STORM SEWER (WATER MAIN REQUIREMENTS) 12"	15"	18"	24"	30"	36"	42"	48"	60"	ERS ELLIPTICAL 24"	ERS ELLIPTICAL 48"	TRENCH BACKFILL
					EACH							FOOT	EACH																																FOOT												CU YD
0+85.00	43.70'	LT	INLET	602301, 604036																																1																					
			SS																																											22											3
1+71.00	44.00'	LT	INLET	602301, 604036																																1																					
			SS																																											22											2
1+71.00	19.44'	LT	MH	602401, 602601, 602701, 604011															1																																						
			SS																																														80								9
2+51.00	19.50'	LT	MH	602401, 602601, 602701, 604011															1																																						
			SS																																														80								9
3+31.00	19.50'	LT	MH	602401, 602601, 602701, 604011															1																																						
			SS																																														117								15
6+20.00	18.00'	RT	INLET	602301, 604011																															1																						
			SS																																											78											11
7+00.00	18.00'	RT	INLET	602306, 602601,																																			1																		
			SS																																											84											11
7+85.00	18.00'	RT	MH	602401, 602601, 602701, 604011											1																																										
			SS																																											94											13
7+85.00	26.58'	RT	INLET	602301, 604036																																1																					
			SS																																											8											2
8+82.00	18.00'	RT	INLET																																								1														
			SS																																											96											17
7+00.00	29.50'	LT	INLET	602301, 604011																															1																						
			SS																																											72											10
7+75.21	29.50'	LT	MH	602401, 602601, 602701, 604011											1																																										
			SS																																												57										7
8+35.00	27.98	LT	INLET																																								1														
			SS																																													143									26
COCKRELL LN																																																									
12+62.08	23.50'	LT	INLET	602301, 604046																																	1																				
			SS																																											12											1
12+62.08	35.93'	LT	END SECTION	542301	1																																																				
13+23.78	38.01	RT	END SECTION	542301	1																																																				
			SS																																											60											7
13+87.56	39.55	LT	END SECTION	542301	1																																																				
			SS																																												15										3
13+87.56	23.50'	LT	INLET	602306, 602601,																																			1																		
			SS																																												59										9
13+87.56	38.91	RT	MH	602401, 602601, 602701, 604011											1																							1																		
			SS																																												12										3
13+87.56	53.47	RT	INLET	602301, 604036																																1																					
17+50.00	59.72	LT	INLET	602301, 604036																																1																					
			SS																																												34										3
17+50.00	23.50'	LT	INLET	602306, 604046																																					1																
			SS																																												41										6
17+50.00	20.61	RT	MH	602401, 602601, 602701, 604011											1																																										
			SS																																												153										9
19+05.00	22.49	RT	MH	602401, 602601, 602701, 604011											1																																										
			SS																																												16										2
19+23.00	29.23	RT	INLET																																								1														
18+98.00	37.5	RT	INLET	602301, 604036																																1																					
			SS																																											14											5
19+28.58	60.24	LT	INLET																																								1														
			SS																																												89										5
			SS																																														52								13
19+63.73	68.43'	RT	MH	602401, 602601, 602701, 604011															1																																						
SUBTOTAL					3	0	1	0	0	0	0	0	2	0	5	0	1	0	5	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	3	7	1	0	6	0	1	0	4	0	0	832	476	267	495	0	0	0	0	0	0	0	277
TOTAL					4	2	5*	1	1	1	1	16	10	3	15	9	1	5	17	8	2	1	1	3	1	8	4	1	1	4	1	2	1	4	8	32	1	2	9	2	1	1	19	1	990	3,390	2,317	2,661	3,123	1,364	504	54	3,324	462	62	32	8,254

*NOTE: SEE PIPE CUVLERT SCHEDULE FOR MORE 24" END SECTIONS.

FILE NAME = c:\pw_work\pwidot\edwardsjd\d0373645\D672890-sht-schedule.dgn Default	USER NAME = edwardsjd	DESIGNED - JMO	REVISED - JDE 2/21/2014
	PLOT SCALE = 100.0000 ' / in.	DRAWN - JMO	REVISED -
	PLOT DATE = Feb-21-2014 02:21:51PM	CHECKED - AWM	REVISED -
		DATE - 12/4/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAU ROUTE 8012 (WABASH AVE)
SCHEDULE OF QUANTITIES

SCALE: SHEET 18 OF 27 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8012	21(W-3, TS-1, RS-7)	SANGAMON	679	81

CONTRACT NO. 72890
ILLINOIS FED. AID PROJECT