WABASH AVENUE

EXISTING STATION	PROPOSED STATION	FACING	EXIST OFFSET	PROP OFFSET	SIGN	SIGN DESIGNATION	SIGN SIZE (in x in)	SIGN PANEL TY 1 SPL (Sq. Ft.)	SIGN PANEL TY 2 SPL (Sq. Ft.)	SIGN PANEL T3 (Sq. Ft.)	REM SIGN PANEL ASMBLY TY A SPL (Each)	REM SIGN PANEL ASMBLY TY B SPL (Each)	No. of Posts	Telescoping Stl Sign Support (Foot)	Concrete Foundation (CU YD)	STRUCTURAL STEEL SIGN SUPPORT (POUND)	STRUCTURAL STEEL SIGN SUPPORT MEMBER•	REM GR MT SIN SUPPORT (EACH)	REM CONC FDN-GR MT (EACH)
								X7200105	X7200205	72000300	X7240110	X7240200		72800100	73400100	72700100		73700100	73700200
343+45.00	343+45.00	East	28 LT	23 LT	Truck Entrance (Symbol)	W11-10	36 x 36	9			1		1	14					
347+77.00	347+77.00	West	28 RT	45 RT	Speed Limit 50 Ahead (Yellow Diamond)	W3-5	36 x 36	9			1		1	14					
350+34.00	350+34.00	West	28 RT	45 RT	Divided Highway (Symbol)	W6-1	36 x 36	9			1		1	14					
353+77.00	346+25.00	East	43 LT	33 LT	Two Way Traffic (symbol)	W6-3	36 x 36	9			1		1	14					
353+84.00	353+84.00	West	24 RT	49 RT	Speed Limit 50	R2-1 (50 MPH)	36 x 48		12			1	1	14					
355+54.00	355+54.00	West	31 RT	57 RT	JCT (Blue)	M2-1(BL)	21 x 15	2.2											
355+54.00	355+54.00	West	31 RT	57 RT	Interstate 72	M1-1(72)	36 x 36	9				1							
355+54.00	355+54.00	West	31 RT	57 RT	JCT (White)	M2-1	21 x 15	2.2											
355+54.00	355+54.00	West	31 RT	57 RT	36	M1-4(36)	36 x 36	9											
357+45.00	357+45.00	East	51 LT	56 LT	Speed Limit 55	R2-1 (55 MPH)	36 x 48		12			1	1	14					
360+37.00	360+37.00	North	56 LT	78 LT	Wabash	City	40 x 8	2.2											
360+37.00	360+37.00	West	56 LT	78 LT	International	City	40 x 8	2.2											
360+37.00	360+37.00	South	56 LT	78 LT	Wabash	City	40 x 8	2.2			1		1	14					
360+37.00	360+37.00	East	56 LT	78 LT	International	City	40 x 8	2.2											
360+53.00	360+53.00	West	35 RT	52 RT	Signal Ahead (Symbol)	W3-3	36 x 36	9			1		1	14					
361+74.00	361+74.00	West	35 RT	51 RT	Right Turn Lane	R3-I100 (Right)	24 x 24	4											
361+74.00	361+74.00	West	35 RT	51 RT	Slant Arrow Right at 45 (Symbol)	M6-2 (Right)	21 x 15	2.2			1		1	14					
363+38.00	363+38.00	West	37 RT	59 RT	Abraham Lincoln	District 6	30 x 30	6											
363+38.00	363+38.00	West	37 RT	59 RT	Horizontal Arrow Right (Symbol), (Brown)	M6-1 (Right) (BR)	21 x 15	2.2											
365+00.00	365+00.00	East	49 LT	57 LT	Speed Limit 50	R2-1 (50 MPH)	36 x 48		12			1	1	14					
366+09.00	366+09.00	East	15 LT	9 LT	Left Turn Lane	R3-I100 (Left)	24 x 24	4											
366+09.00	366+09.00	East	15 LT	9 LT	Slant Arrow Left at 45 (Symbol)	M6-2 (Left)	21 x 15	2.2			1		1	14					
	367+05.00	East		53 LT	One Way Left Arrow	R6-1 (Left)	54 x 18	6.75											
	367+05.00	East		53 LT	One way Right Arrow	R6-1 (Right)	54 x 18	6.75											
	367+05.00	East		54 LT	Do Not Enter	R5-1	36 x 36	9.0											
367+07.00		East	13 LT		Left Turn YIELD On Green (Ball)	R10-12	24 x 30				1								
	367+26.00			0 LT	No Left Turn	R3-2 (Left)	36 x 36	9					1	14					
	366+38.00	East		17 LT	FYA (Flashing Yellow)	R10-12	24 x 30	5											
	367+60.00			54 LT	One Way	R6-1 (Right)	54 x 18	6.75					1	14					
	367+60.00			54 LT	One Way	R6-1 (Left)	54 x 18	6.75											
	367+65.00			54 LT	Do Not Enter	R5-1	36 x 36	9					1	14					
367+98.00	367+91.00	North	31 RT	48 RT	One Way Left Arrow	R6-2(Right)	18 x 24	3			1								
	368+11.00	East		54 RT	No Right Turn	R3-1 (Right)	36 x 36	9					1	14					
	368+11.00	East		54 RT	No Left Turn	R3-2 (Right)	36 x 36	9											
368+31.00	368+73.00	West	6 LT	0 LT	Keep Right (Symbol)	R4-7	24 x 30	5			1		1	14					
368+31.00	368+73.00	West	6 LT	0 LT	Object Marker (Yellow)	TYPE 1	18 x 18	2.3											
369+02.00	369+02.00	West	29 RT	45 RT	Speed Limit 50	R2-1 (50 MPH)	36 x 48		12			1	1	14					
374+33.00	374+33.00	East	16 LT	10 LT	Left Turn Lane	R3-I100 (Left)	24 x 24	4			1		1	14					
374+33.00	374+33.00	East	16 LT	10 LT	Slant Arrow Left at 45 (Symbol)	M6-2 (Left)	21 x 15	2.2											
376+04.00	376+04.00	West	7 LT	1 LT	Left Turn Lane	R3-I100 (Left)	24 x 24	4			1		1	14					
376+04.00	376+04.00	West	7 LT	1 LT	Slant Arrow Left at 45 (Symbol)	M6-2 (Left)	21 x 15	2.2											
381+84.00	381+59.00	East	17 LT	11 LT	Keep Right (Symbol)	R4-7	24 x 30	5			1		1	14					
381+84.00	381+59.00	East	17 LT	11 LT	Object Marker (Yellow Diamond)	TYPE 1	18 x 18	2.3											
382+20.00	382+17.00	South	53 LT	56 LT	One Way Left Arrow	R6-2(Left)	18 x 24	3			1								
	382+98.00			43 RT	One Way Left Arrow	R6-1 (Left)	54 x 18	6.75											
	382+98.00			43 RT	One Way Left Arrow	R6-1 (Right)	54 x 18	6.75											
	382+98.00			43 RT	Do Not Enter	R5-1	36 x 36	9											
383+05.00		West	5 LT		Left Turn YIELD On Green (Ball)	R10-12	24 x 30				1								
	383+11.00				No Left Turn	R3-2 (Left)	36 x 36	9											
	383+75.00	West		8 RT	Left Yield on Flashing Yellow Arrow	See Detail	24 x 36	6											
387+49.00	388+30.00	East	5 LT	8 LT	Keep Right (Symbol)	R4-7	24 x 30	5			1		1	14					
387+49.00	388+30.00	East	5 LT	8 LT	Object Marker (Yellow)	TYPE 1	18 x 18	2.3											
387+62.00	387+62.00	West	33 RT	58 RT	Combination Hor Alignment/Intersection)	W1-10	36 x 36	9			1		1	14					
388+63.00	388+63.00	West	35 RT	59 RT	B.S.S. St Agnes •	City	48 x 24	8											
388+63.00	388+63.00	West	35 RT	59 RT	Home of Emma Hopkins •	City	60 x 24		10			1	2	28					
390+02.00	390+02.00	East	37 LT	49 LT	Speed Limit 50	R2-1 (50 MPH)	36 x 48		12			1	1	14					
391+23.00		East	33 LT		Ash Grove	D3-1	73 x 20					1							
	390+50.00	East		30 LT	Ash Grove	D3-1	73 x 20		10.1										
391+23.00		East	9 LT		Left Turn YIELD On Green (Ball)	R10-12	24 x 30				1								
	390+50.00	East		9 LT	Left Yield on Flashing Yellow Arrow	See Detail	24 x 36	6											
391+81.00		West	22 RT		Ash Grove	D3-1	73 x 20					1							
	392+33.00	West		28 RT	Move RT (or LT) Arrow / Bunker Hill RT (or LT)	D3-1	73 x 20		10.1										
	392+09.00			92LT	Wabash	City	40 x 8												
	392+33.00	West		10 LT	Left Yield on Flashing Yellow Arrow	See Detail	24 x 36	6											
392+16.00	392+26.00	West	44 RT	60 RT	Ash Grove	City	40 x 8	2.2											
392+16.00	392+26.00	North	44 RT	60 RT	Wabash	City	40 x 8	2.2			1		1	14					
392+16.00	392+26.00	East	44 RT	60 RT	Ash Grove	City	40 x 8	2.2											
392+16.00	392+26.00	South	44 RT	60 RT	Wabash	City	40 x 8	2.2											
393+49.00	393+49.00	West	29 RT	45 RT	Speed Limit 50	R2-1 (50 MPH)	36 x 48		12			1	1	14					
399+87.00	399+87.00	East	38 LT	45 LT	Signal Ahead (Symbol)	W3-3	36 x 36	9			1		1	14					
406+52.00	406+52.00	East	39 LT	44 LT5	Speed Limit 50	R2-1 (50)	36 x 48		12			1	1	14					
407+51.00	407+51.00	East	35 LT	45 LT	Combination Hor Alignment/Intersection)	W1-10	36 x 36	9			1		1	14					
407+91.00	407+91.00	West	38 RT	45 RT	Speed Limit 45	R2-1 (45 MPH)	36 x 48		12			1	1	14					
409+00.00	409+13.00	South	41 RT	54 RT	Stop Sign	R1-1	30 x 30	6.3			1		1	14					
425+94.00	425+70.00	East	31 LT	37 LT	Archer Elevator	D3-1	72 x 22		11			1							
	426+57.00	North		48 RT	Wabash	D3-1	36 x 25	6.3											

CONTINUED ON NEXT SHEET

FILE NAME = c:\pw_work\pwidot\sparksgw\d0373645\D672890-sht-schedule.dgn	USER NAME = sparksgw	DESIGNED - JMO	REVISED -
		DRAWN - JMO	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED - AWM	REVISED -
Default	PLOT DATE = Feb-04-2014 01:29:45PM	DATE - 12/4/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAU ROUTE 8012 (WABASH AVE)
SCHEDULE OF QUANTITIES

SCALE: | SHEET 23 OF 27 SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8012	21(W-3, TS-1, RS-7)	SANGAMON	679	86
		CONTRACT NO. 72890		
		ILLINOIS FED. AID PROJECT		