

STA 432+05.00 RT
 "LANDSCAPING ROCKS WITHIN PROPOSED RIGHT-OF-WAY AT THIS LOCATION SHALL BE SALVAGED AND LEFT NEAR THE SIGN FOR USE BY THE PROPERTY OWNER. THE ADJACENT LANDSCAPING ROCKS, LANDSCAPING PLANTS, AND THE EXISTING SIGN BEYOND STATE RIGHT-OF-WAY SHALL NOT BE DISTURBED."

STA 433+20.00 RT
 "LANDSCAPING ROCKS WITHIN PROPOSED RIGHT-OF-WAY AT THIS LOCATION SHALL BE SALVAGED AND LEFT NEAR THE SIGN FOR USE BY THE PROPERTY OWNER. THE ADJACENT LANDSCAPING ROCKS, LANDSCAPING PLANTS, AND THE EXISTING SIGN BEYOND STATE RIGHT-OF-WAY SHALL NOT BE DISTURBED."

PROPOSED COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24

45' R

STA 431+80.00 68.00' RT
 STA 432+00.00 60.00' RT

PROPOSED COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24

PROPOSED ROW LINE

STA 9+27.00 40.02' LT
 STA 8+98.00 40.08' LT
 STA 9+07.05 29.12' LT

PLEASANT RUN BEGINS STATION 9+07.05

PROPOSED COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12

PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

STA 9+17.14 29.00' RT

STA 9+20.08 39.96' RT

STA 9+25.08 39.97' RT

2 CENTERED CURVE
 45' - 450'
 OFFSET = 8.0'

PROPOSED ROW LINE
 STA 433+25.00 60.00' RT

PROPOSED COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24


PROPOSED TEMPORARY EASEMENT

PROPOSED PORTLAND CEMENT CONCRETE SIDEWALK, 4"

SPRINGFIELD CUSTARD, L.L.C
 PARCEL NO. 6134121

SOLON, L.L.C
 PARCEL NO. 6134117

PIIAI SERVICES INC.
 PARCEL NO. 6134122



FILE NAME =	USER NAME = spksgw	DESIGNED - SEW	REVISED -
c:\pwork\pwork\spksgw\10373645\0672890-sht-plan-Pleasant.dgn		DRAWN - AS	REVISED -
PLOT SCALE = 40.0000' / in.		CHECKED - SEW	REVISED -
PLOT DATE = Feb-04-2014 01:38:17PM		DATE - 12/04/2013	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

PLEASANT RUN
 PLAN SHEET

SCALE: 1"=20' SHEET NO. 1 OF 1 SHEETS STA. 9+07.05 TO STA. 10+00.00

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8012	21(W-3,TS-1,RS-7)	SANGAMON	679	209
CONTRACT NO. 72890				
ILLINOIS FED. AID PROJECT				