

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE												
				MAINLINE WABASH AVENUE	RETAINING WALL	SIGNALS & LIGHTING AT I-72 RAMPS	SIGNALS AT CITY STR OTHER THAN ARCHER ELEVATOR	SIGNALS AT ARCHER ELEVATOR	LIGHTING AT PLEASANT RUN	SIDEWALK	HOLLIS EAST LIMITS TO 9+75 & COCKRELL	SIDEWALK ON SIDEROADS	TURN LANE AND BICYCLE LANE ON ARCHER	ADD' L BIKE LANES ON MERCANTILE (4' WIDTH WABASH TO STADIUM)		
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 13.3% STATE 6.7% CITY	100% CITY	80% STATE 20% CITY	80% FED 20% CITY	100% CITY	100% CITY	100% CITY		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	10864.0	10302.0								562.0				
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	178994.0	167894.0								11100.0				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	57082.0	55824.0								1258.0				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	9188.0	8356.0								832.0				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	7678.0	6298.0								1380.0				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	3248.0	3148.0								100.0				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	21349.0	21056.0								293.0				
* 72000300	SIGN PANEL - TYPE 3	SO FT	481.0	481.0												
* 72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	3362.0	3362.0												
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1242.0	1102.0								140.0				
* 73400100	CONCRETE FOUNDATIONS	CU YD	4.0	4.0												
* 73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	4.0	4.0												
* 73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	4.0	4.0												
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	79848.0	76754.0								3094.0				

FILE NAME :	USER NAME :	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAU ROUTE 8012 (WABASH AVE) SUMMARY OF QUANTITIES			FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...	...	DRAWN -	REVISED -					8012	21HW-3, TS-1, RS-7)	SANGAMON	679	16
...	...	CHECKED -	REVISED -					CONTRACT NO. 72890			ILLINOIS FED. AID PROJECT	
...	...	DATE -	REVISED -					SCALE: N/A	SHEET 13 OF 24 SHEETS	STA.	TO STA.	

* SPECIALTY ITEM