

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE											
				MAINLINE WABASH AVENUE	RETAINING WALL	SIGNALS & LIGHTING AT I-72 RAMP	SIGNALS AT CITY STR OTHER THAN ARCHER ELEVATOR	SIGNALS AT ARCHER ELEVATOR	LIGHTING AT PLEASANT RUN	SIDEWALK	HOLLIS EAST LIMITS TO 9+75 & COCKRELL	SIDEWALK ON SIDEROADS	TURN LANE AND BICYCLE LANE ON ARCHER	ADD'L BIKE LANES ON MERCANTILE (4' WIDTH WABASH TO STADIUM)	
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 13.3% STATE 6.7% CITY	100% CITY	80% STATE 20% CITY	80% FED 20% CITY	100% CITY	100% CITY	100% CITY	
				0004	0040	0021	0021	0021	0021	0021	0004	0021	0004	0004	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4729.0	4178.0								551.0			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3305.0	3149.0								156.0			
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	875.0	875.0											
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	1727.0									1727.0			
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	4589.0	4292.0								297.0			
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	40.0									40.0			
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	7193.0	7193.0											
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	301.0									301.0			
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	28682.0	27912.0								770.0			
* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	1638.0	1574.0								64.0			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1505.0	1471.0								34.0			
* 78200300	PRISMATIC CURB REFLECTOR	EACH	760.0	728.0								32.0			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	18.0	18.0											
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	16.0	16.0											
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4.0	4.0											
78300100	PAVEMENT MARKING REMOVAL	SD FT	17816.0	16933.0								883.0			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	489.0	489.0											

FILE NAME =	USER NAME = sparkgn	DESIGNED - AWM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAU ROUTE 8012 (WABASH AVE) SUMMARY OF QUANTITIES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
01\pav\work\pav\sparkgn\08373645\0672890-ehf-500.dgn	DRAWN - TJD	REVISED -	8012					21W-3, TS-1, RS-71	SANGAMON	679	17	
Default	CHECKED - AWM	REVISED -	CONTRACT NO. 72890					ILLINOIS FED. AID PROJECT				
	DATE - 12/04/2013	REVISED -	SCALE: N/A					SHEET 14 OF 24 SHEETS	STA. TO STA.			

* SPECIALTY ITEM