

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	MAINLINE WABASH AVENUE	RETAINING WALL	SIGNALS & LIGHTING AT I-72 RAMPS	SIGNALS AT CITY STR OTHER THAN ARCHER ELEVATOR	SIGNALS AT ARCHER ELEVATOR	LIGHTING AT PLEASANT RUN	SIDEWALK	HOLLIS EAST LIMITS TO 9+75 & COCKRELL	SIDEWALK ON SIDEROADS	TURN LANE AND BICYCLE LANE ON ARCHER	ADD'L BIKE LANES ON MERCANTILE (4' WIDTH WABASH TO STADIUM)
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 13.3% STATE 6.7% CITY	100% CITY	80% STATE 20% CITY	80% FED 20% CITY	100% CITY	100% CITY	100% CITY
				0004	0040	0021	0021	0021	0021		0004	0021	0004	0004
X6020084	MANHOLE, SPECIAL	EACH	1.0	1.0										
X6024200	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 1 FRAME, CLOSED LID, SPECIAL	EACH	1.0								1.0			
X6060048	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6, 18 (SPECIAL)	FOOT	460.0	337.0							123.0			
X6060052	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6, 24 (SPECIAL)	FOOT	142.0	142.0										
X6060500	CORRUGATED MEDIAN REMOVAL	SO FT	633.0	633.0										
X6061005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	28.0								28.0			
X6061460	PAVED DITCH (SPECIAL)	FOOT	20.0	20.0										
X6061902	CONCRETE MEDIAN, TYPE SM (SPECIAL)	SO FT	16692.0	16692.0										
* X7200105	SIGN PANEL - TYPE 1 (SPECIAL)	SO FT	968.0	915.0							53.0			
* X7200205	SIGN PANEL - TYPE 2 (SPECIAL)	SO FT	243.0	243.0										
* X7240110	REMOVE SIGN PANEL ASSEMBLY - TYPE A (SPECIAL)	EACH	67.0	59.0							8.0			
* X7240200	REMOVE SIGN PANEL ASSEMBLY - TYPE B (SPECIAL)	EACH	33.0	32.0							1.0			
* X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1.0			0.3	0.6	0.1						
* X8950100	RELOCATE EXISTING MASTER CONTROLLER	EACH	1.0			1.0								

FILE NAME : c:\pwork\pwork\sparkg\08373645\0672090-shi-500.dgn	USER NAME : sparkg 2090-shi-500.dgn	DESIGNED - AHM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAU ROUTE 8012 (WABASH AVE) SUMMARY OF QUANTITIES				F.A.U. R/E: 8012	SECTION 211W-3, TS-1, RS-71	COUNTY SANGAMON	TOTAL SHEETS 679	SHEET NO. 25
Default	PLOT SCALE : 100.0000' / 1"	DRAWN - TJO	REVISED -		SCALE: N/A	SHEET 22 OF 24 SHEETS	STA.	TO STA.	CONTRACT NO. 72890				
	PLOT DATE : Feb-04-2014 04:00:48PM	CHECKED - AHM	REVISED -		ILLINOIS FED. AID PROJECT								
		DATE - 12/04/2013	REVISED -										

* SPECIALTY ITEM