

SCHEDULE OF QUANTITIES

A-3 SURFACE TREATMENT SCHEDULE

LOCATION	SEAL COAT	COVER COAT	P BIT MATLS	BIT MATLS
	AGGR. ( TON)	AGGR. ( TON)	C&S CT ( TON)	PR CT ( TON)
[ S. B. I. 4D ( HARVEST RD. ) ]				
STA. 2111+90.05 TO STA. 2113+50.00	3.73	7.46	1.59	0.53
STA. 2113+50.00 TO STA. 2114+60.10	2.26	4.52	0.96	0.32
STA. 2114+60.10 TO STA. 2124+35.00	17.33	34.66	7.41	2.47
( O&C Side Rd ) - Sta 2120+00.93 LT	0.63	1.26	0.09	0.09
( PAVEMENT OMISSION):				
STA. 2124+75.00 TO STA. 2127+60.00				
STA. 2128+00.00 TO STA. 2136+51.01	15.13	30.26	6.48	2.16
STA. 2128+90.00 TO STA. 2136+51.01	13.53	27.06	5.79	1.93
( STA EQN):				
STA 2136+51.01 ( BK ) = STA 2137+36.86 ( AH)				
STA. 2137+36.86 TO STA. 2151+18.50	24.56	49.12	10.50	3.50
( BRIDGE OMISSION):				
STA. 2151+58.50 TO STA. 2151+91.52				
STA. 2152+31.52 TO STA. 2170+52.67	32.38	64.76	13.83	4.61
STA. 2170+52.67 TO STA. 2171+39.03	1.68	3.36	0.72	0.24
STA. 2171+39.03 TO STA. 2172+29.03	1.90	3.80	0.81	0.27
PROJECT TOTAL	113	226	49	16

AGGREGATE BASE COURSE, TYPE A 4''

LOCATION	QUANTITY ( SQ YD)
[ S. B. I. 4D ( HARVEST RD. ) ]	
STA. 2112+00.05 TO STA. 2113+50.00	349.88
STA. 2113+50.00 TO STA. 2114+60.10	226.32
STA. 2114+60.10 TO STA. 2124+25.00	1,715.38
( PAVEMENT OMISSION):	
STA. 2124+75.00 TO STA. 2127+60.00	
STA. 2128+10.00 TO STA. 2136+51.01	1,495.13
STA. 2128+90.00 TO STA. 2136+51.01	1,352.91
( STA EQN):	
STA 2136+51.01 ( BK ) = STA 2137+36.86 ( AH)	
STA. 2137+36.86 TO STA. 2151+08.50	2,438.47
( BRIDGE OMISSION):	
STA. 2151+58.50 TO STA. 2151+91.52	
STA. 2152+41.52 TO STA. 2170+52.67	3,219.82
STA. 2170+52.67 TO STA. 2171+39.03	167.92
STA. 2171+39.03 TO STA. 2172+19.03	168.89
PROJECT TOTAL	11,135

PAINT PAVEMENT MARKING - LINE 5''

LOCATION STATION TO STATION	LENGTH FOOT	YELLOW SKIP-DASH ( FOOT)
[ S. B. I. 4D ( HARVEST RD. ) ]		
STA. 2111+60.06 TO STA. 2136+51.01	2,490.95	622.74
( STA EQN):		
STA 2136+51.01 ( BK ) = STA 2137+36.86 ( AH)		
STA. 2137+36.86 TO STA. 2172+58.60	3,521.74	880.44
PROJECT TOTAL		1,504