

SCHEDULE OF QUANTITIES

AGGREGATE SURFACE COURSE, TYPE B

TYPE	LOCATION	Thickness (5" to 1.5") (in)	W ₁ (FT)	W ₂ (FT)	L (FT)	QUANTITY (TON)
	[S. B. I. 4D (HARVEST RD.)]					
Aggr PE	STA. 2113+39.37 LT	3.25	14	25	15	6.01
Aggr FE	STA. 2116+36.35 LT	3.25	12	15	15	4.16
O&C Side Rd	STA. 2120+00.93 LT	3.25	25	50	15	11.57
Aggr PE	STA. 2120+05.71 RT	3.25	21	43	15	9.87
	(PAVEMENT OMISSION):					
	STA. 2124+75.00 TO					
	STA. 2127+60.00					
Aggr FE	STA. 2128+75.76 LT	3.25	28	49	15	11.88
Aggr PE mbt	STA. 2130+50.64 LT		665.99			
	(Landing):	6	489.59			18.59
	(Apron):	3.25	176.40			3.63
Aggr FE	STA. 2130+72.60 RT	3.25	12	20	15	4.94
Aggr FE	STA. 2136+30.85 LT	3.25	27	45	15	11.10
	(STA EQN):					
	STA 2136+51.01 (BK) =					
	STA 2137+38.86 (AH)					
Aggr Side Rd	STA. 2147+02.85 LT	3.25	55	90	15	22.36
Aggr FE	STA. 2148+54.10 RT	3.25	13	18	15	4.78
	(BRIDGE OMISSION):					
	STA. 2151+58.50 TO					
	STA. 2151+91.52					
Aggr PE	STA. 2158+67.39 RT	3.25	26	53	15	12.18
Aggr FE	STA. 2159+77.76 LT	3.25	259.87		15	5.34
Aggr FE	STA. 2166+09.57 LT	3.25	26	34	15	9.25
PROJECT TOTAL						136

HOT- MIX ASPHALT SURFACE
REMOVAL - BUTT JOINT

LOCATION	QUANTITY (SQ YD)
[S. B. I. 4D (HARVEST RD.)]	
STA. 2111+60.05 TO STA. 2112+00.05	184.73
STA. 2112+00.05 TO STA. 2112+80.05	186.67
STA. 2124+45.00 TO STA. 2124+75.00	66.67
(O&C Side Rd) - Sta 2120+00.93 LT	58.33
(PAVEMENT OMISSION):	
STA. 2124+75.00 TO STA. 2127+60.00	
STA. 2127+60.00 TO STA. 2127+90.00	66.67
(STA EQN):	
STA 2136+51.01 (BK) = STA 2137+36.86 (AH)	
STA. 2137+36.86 TO STA. 2151+08.50	53.33
(BRIDGE OMISSION):	
STA. 2151+58.50 TO STA. 2151+91.52	
STA. 2152+91.52 TO STA. 2152+21.52	53.33
STA. 2171+39.03 TO STA. 2172+19.03	168.89
STA. 2172+19.03 TO STA. 2172+59.03	173.78
PROJECT TOTAL	
	1,013