

SCHEDULE OF QUANTITIES

INCIDENTAL HOT-MIX  
ASPHALT SURFACING

LOCATION	QUANTITY ( TON )
[ S. B. I. 4D ( HARVEST RD. ) ]	
STA. 2111+60.05 TO STA. 2112+00.05	41.38
STA. 2124+25.00 TO STA. 2124+45.00	6.97
STA. 2124+45.00 TO STA. 2124+75.00	8.40
( PAVEMENT OMISSION ):	
STA. 2124+75.00 TO STA. 2127+60.00	
STA. 2127+60.00 TO STA. 2127+90.00	8.40
STA. 2127+90.00 TO STA. 2128+10.00	6.97
( STA EQN ):	
STA 2136+51.01 ( BK ) = STA 2137+36.86 ( AH )	
STA. 2151+08.50 TO STA. 2151+58.50	13.69
( BRIDGE OMISSION ):	
STA. 2151+58.50 TO STA. 2151+91.52	
STA. 2151+91.52 TO STA. 2152+41.52	13.69
STA. 2172+19.03 TO STA. 2172+59.03	38.93
PROJECT TOTAL	139

AGGREGATE WEDGE  
SHOULDERS, TYPE B

LOCATION	QUANTITY ( TON )
[ S. B. I. 4D ( HARVEST RD. ) ]	
STA. 2111+60.06 TO STA. 2124+45.00	146.34
( PAVEMENT OMISSION ):	
STA. 2124+75.00 TO STA. 2127+60.00	32.46
STA. 2127+90.00 TO STA. 2136+51.01	98.06
( STA EQN ):	
STA 2136+51.01 ( BK ) = STA 2137+36.86 ( AH )	
STA. 2137+36.86 TO STA. 2151+58.50	161.91
( BRIDGE OMISSION ):	
STA. 2151+58.50 TO STA. 2151+91.52	
STA. 2151+91.52 TO STA. 2172+59.03	235.47
PROJECT TOTAL	675

( ESTIMATED QUANTITIES )  
AGGREGATE BASE REPAIR

LOCATION ( APPROX. 15% OF RDWY AREA )	QUANTITY ( TON )
[ S. B. I. 4D ( HARVEST RD. ) ]	
STA. 2112+00.05 TO STA. 2112+80.05	9.57
STA. 2171+39.03 TO STA. 2172+19.03	8.66
PROJECT TOTAL	19

( ESTIMATED QUANTITIES )  
PREPARATION OF BASE

LOCATION ( APPROX. 15% OF RDWY AREA )	QUANTITY ( SQ YD )
[ S. B. I. 4D ( HARVEST RD. ) ]	
STA. 2111+60.05 TO STA. 2112+00.05	27.71
STA. 2124+45.00 TO STA. 2124+75.00	10.00
( PAVEMENT OMISSION ):	
STA. 2124+75.00 TO STA. 2127+60.00	
STA. 2127+60.00 TO STA. 2127+90.00	10.00
( STA EQN ):	
STA 2136+51.01 ( BK ) = STA 2137+36.86 ( AH )	
STA. 2151+28.50 TO STA. 2151+58.50	8.00
( BRIDGE OMISSION ):	
STA. 2151+58.50 TO STA. 2151+91.52	
STA. 2152+91.52 TO STA. 2152+21.52	8.00
STA. 2172+19.03 TO STA. 2172+59.03	26.07
PROJECT TOTAL	90

SHORT-TERM PAVEMENT MARKING

LOCATION	QUANTITY ( FOOT )
[ S. B. I. 4D ( HARVEST RD. ) ]	
STA. 2111+60.06 TO STA. 2124+75.00	119.54
( PAVEMENT OMISSION ):	
STA. 2124+75.00 TO STA. 2127+60.00	
STA. 2127+60.00 TO STA. 2136+51.01	81.00
( STA EQN ):	
STA 2136+51.01 ( BK ) = STA 2137+36.86 ( AH )	
STA. 2137+36.86 TO STA. 2151+58.50	129.24
( BRIDGE OMISSION ):	
STA. 2151+58.50 TO STA. 2151+91.52	
STA. 2151+91.52 TO STA. 2172+59.03	187.96
PROJECT TOTAL	518