

PAVING SCHEDULE

LOCATION		LENGTH	PAVEMENT WIDTH	SHOULDER WIDTH	PAVEMENT AREA	SHOULDER AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	PORTLAND CEMENT CONCRETE PAVEMENT, 9" (JOINTED)	HOT-MIX ASPHALT SHOULDERS, 8"
STATION TO	STATION	FEET	FEET	FEET	SQ YD	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD
EB RA												
0+90.09	TO 301+61.98	90.1	16.3	8.0	162.8	80.1	24.3	0.5	13.6	20.4	0.0	0.0
301+61.98	TO 305+08.02	346.0	16.3	4.0	1,353.2	153.8	150.7	3.0	86.8	130.2	0.0	0.0
305+08.02	TO 306+82.17	174.1	16.3	8.0	314.4	154.8	46.9	0.9	27.2	40.8	0.0	0.0
306+82.17	TO 310+75.05	392.9	16.5	12.0	718.1	523.8	124.2	2.5	78.5	117.7	0.0	0.0
310+75.05	TO 311+05.92	30.9	16.3	8.0	55.8	27.4	8.3	0.2	4.4	6.7	0.0	0.0
311+05.92	TO 315+53.04	447.1	16.3	4.0	807.8	198.7	100.7	2.0	57.0	85.5	0.0	0.0
315+53.04	TO 324+01.76	848.7	16.0	NA	1,508.8	NA	0.0	0.0	0.0	0.0	1,508.8	0.0
324+01.76	TO 324+54.97	53.2	Variable	NA	202.7	NA	0.0	0.0	0.0	0.0	202.7	0.0
400+00.00	TO 406+51.68	651.7	Variable	NA	6,511.2	NA	0.0	0.0	0.0	0.0	6,511.2	0.0
WB RA												
200+19.69	TO 206+86.47	666.8	16.1	8.0	1,192.8	592.7	178.5	3.6	109.5	164.3	0.0	0.0
206+86.47	TO 209+47.77	261.3	16.1	12.0	467.4	348.4	81.6	1.6	52.8	79.3	0.0	0.0
209+47.77	TO 212+31.29	283.5	16.1	8.0	507.2	252.0	75.9	1.5	42.3	63.5	0.0	0.0
212+31.29	TO 214+26.66	195.4	20.0	4.0	836.3	86.8	92.3	1.8	53.7	80.6	0.0	53.0
214+26.66	TO 214+86.98	60.3	21.0	4.0	542.9	26.8	57.0	1.1	9.1	13.7	0.0	0.0
214+86.98	TO 216+46.07	159.1	22.0	4.0	719.0	70.7	79.0	1.6	45.6	68.5	0.0	0.0
216+46.07	TO 217+01.81	55.7	22.0	10.0	467.2	61.9	52.9	1.1	11.7	17.5	0.0	0.0
217+01.81	TO 218+09.68	107.9	25.0	NA	299.6	NA	0.0	0.0	0.0	0.0	299.6	0.0
218+09.68	= 119+74.73	STA. EQ.										
119+74.73	TO 121+08.28	133.6	Variable	NA	389.1	NA	0.0	0.0	0.0	0.0	389.1	0.0
115+37.11	TO 119+74.73	437.6	Variable	NA	5,203.3	NA	0.0	0.0	0.0	0.0	5,203.3	0.0
TRUCK PARKING												
SHEET TOTALS												
		5,396			22,260	2,578	1,072	21	592	889	14,115	53

PAVEMENT MARKING SCHEDULE

LOCATION		LENGTH	MODIFIED URETHANE PAVEMENT MARKING-LETTERS AND SYMBOLS (YELLOW)	MODIFIED URETHANE PAVEMENT MARKING-LINE 4" (YELLOW)	MODIFIED URETHANE PAVEMENT MARKING-LINE 4" (WHITE)	MODIFIED URETHANE PAVEMENT MARKING-LINE 6"
STATION TO	STATION	FOOT	SQ FT	FOOT	FOOT	FOOT
EB RA						
300+71.89	TO 301+61.98	90.1		90.1	90.1	0.0
301+61.98	TO 305+08.02	346.0	9.2	346.0	0.0	0.0
305+08.02	TO 306+82.17	174.1		174.1	174.1	0.0
306+82.17	TO 310+75.05	392.9		392.9	392.9	0.0
310+75.05	TO 311+05.92	30.9		30.9	30.9	0.0
311+05.92	TO 315+53.04	447.1		447.1	447.1	0.0
315+53.04	TO 324+01.76	848.7		848.7	848.7	0.0
324+01.76	TO 324+54.97	53.2		53.2	53.2	0.0
CAR PARKING						
				299.6	534.8	0.0
TRUCK PARKING						
			4.6		1,638.5	0.0
WB RA						
200+19.69	TO 206+86.47	666.8		666.8	666.8	0.0
206+86.47	TO 209+47.77	261.3		261.3	261.3	0.0
209+47.77	TO 212+31.29	283.5		283.5	283.5	0.0
212+31.29	TO 214+26.66	195.4	4.6	195.4	0.0	0.0
214+26.66	TO 214+86.98	60.3		60.3	60.3	44.0
214+86.98	TO 216+46.07	159.1	4.6	159.1	0.0	0.0
216+46.07	TO 217+01.81	55.7		55.7	55.7	0.0
217+01.81	TO 218+09.68	107.9		107.9	107.9	0.0
218+09.68	= 119+74.73	STA. EQ.				
119+74.73	TO 121+08.28	133.6		133.6	133.6	0.0
CAR PARKING						
				354.1	506.4	
TRUCK PARKING						
			4.6		1,754.5	
PROJECT TOTAL						
		4,307	28	4,960	8,040	44