

**THOUVENOT,
WADE &
MOERCHEN, INC.**
ENGINEERS ♦ SURVEYORS ♦ PLANNERS



CORPORATE OFFICE
4940 OLD COLLINSVILLE RD.
SWANSEA, ILLINOIS 62226
TEL (618) 624-4488
FAX (618) 624-6688
corp@twm-inc.com

WATERLOO OFFICE
113 SOUTH MAIN STREET
WATERLOO, ILLINOIS 62296
TEL (618) 939-5050
FAX (618) 939-3938
waterloo@twm-inc.com

EDWARDSVILLE OFFICE
1015B CENTURY DRIVE
EDWARDSVILLE, ILLINOIS 62025
TEL (618) 656-4040
FAX (618) 656-4343
edwardsville@twm-inc.com

ST. LOUIS OFFICE
1001 CRAIG ROAD, SUITE 260
ST. LOUIS, MISSOURI 63146
TEL (314) 236-5052
FAX (314) 872-2194
stlouis@twm-inc.com

PROFESSIONAL REGISTRATIONS	LICENSE NO.
ALPHOS PROFESSIONAL DESIGN FIRM	184-001250
PROFESSIONAL ENGINEERING CORP.	82-055710
PROFESSIONAL STRUCTURAL ENGR. CORP.	81-052002
ALPHOS PROF. LAND SURVEYING CORP.	048-000018
MISSOURI PROFESSIONAL ENGR. CORP.	MC 001528
MISSOURI LAND SURVEYING CORP.	MC 000346

SEAL

Signature: _____
Signature Date: _____
Expiration Date: _____

STATEMENT OF RESPONSIBILITY
I hereby confirm that the documents herein to be authenticated by my seal is restricted to this sheet, and I hereby disclaim any responsibility for all other drawings, specifications, estimates, reports or other documents or instruments relating to or intended to be utilized for any other part of the architectural, engineering or survey project.

TITLE: SHILOH STATION ROAD PHASE 3
SUMMARY OF QUANTITIES
12-0001-03-PV

PROJECT: SHILOH STATION ROAD
RECONSTRUCTION - PHASE 3
VILLAGE OF SHILOH
ST. CLAIR COUNTY, ILLINOIS

REV.	DATE	DESCRIPTION
△		
△		
△		

DRAWN BY:	NTS	SHEET
DESIGNED BY:	NTS	3
CHECKED BY:		OF 23 SHEETS
APPROVED BY:		PROJECT DESCRIPTION
PROJECT NUMBER:	T01100602	

ISSUED FOR REVIEW ISSUED FOR BIDDING
 ISSUED FOR CONSTR. RECORD DRAWING

SUMMARY OF QUANTITIES			
Code Number	Item	Unit	Quantity
20100500	TREE REMOVAL, ACRES	ACRE	0.25
20200100	EARTH EXCAVATION	CU YD	990
20400800	FURNISHED EXCAVATION	CU YD	371
20800150	TRENCH BACKFILL	CU YD	148
25000100	SEEDING, CLASS 1	ACRE	0.75
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	63
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	63
25000800	POTASSIUM FERTILIZER NUTRIENT	POUND	63
25100115	MULCH, METHOD 2	ACRE	0.75
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	140
28000400	PERIMETER EROSION BARRIER	FOOT	316
28000500	INLET AND PIPE PROTECTION	EACH	13
28100107	STONE RIPRAP, CLASS A4	SQ YD	11
28200200	FILTER FABRIC	SQ YD	11
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	3,179
30201500	LIME	TON	61.2
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	966
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	333
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	144
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.7
40600300	AGGREGATE (PRIME COAT)	TON	1
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,116
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	263
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	55
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	72
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	8,697
42400800	DETECTABLE WARNINGS	SQ FT	24
44000100	PAVEMENT REMOVAL	SQ YD	1,982
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	102
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	43
50105220	PIPE CULVERT REMOVAL	FOOT	103
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	1.0
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	439
550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	473
550A2350	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 21"	FOOT	47
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	70
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1
60219570	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	5
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	6.0
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1,598
67100100	MOBILIZATION	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	115
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1,943
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	81
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	15
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,155
72000100	SIGN PANEL - TYPE 1	SQ FT	20.0
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	12.0
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	6.3
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	73
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,943
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	81
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	15
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	11
X0323265	REMOVE EXISTING RIPRAP	SQ YD	114
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	5
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
XX006119	TRAFFIC CONTROL AND PROTECTION (DETOUR)	L SUM	1

* SPECIALTY ITEMS