

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				URBAN 100% STATE	0005
				ROADWAY	
				1000	RURAL
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2048	2048	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	955	955	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2546	2546	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	80502	80502	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	10410	10410	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	213	213	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2048	2048	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	955	955	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1558	1558	
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1558	1558	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2794	2794	
X2020110	GRADING AND SHAPING SHOULDERS	UNITS	190	190	
X5537800	STORM SEWERS TO BE CLEANED, 12"	FOOT	300	300	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	14	14	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	30	30	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				URBAN 100% STATE	0005
				ROADWAY	
				1000	RURAL
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	970	970	
Z0076600	TRAINEES	HOOR			
Ⓢ Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOOR	500	500	

FILE NAME *	USER NAME * nramper	DESIGNED - RG	REVISED -
FILE.L		DRAWN - RG	REVISED -
	PLOT SCALE * 100.0000' / in	CHECKED - MCR	REVISED -
	PLOT DATE * 9/28/2012	DATE - 9/28/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Rev. 4-8-13 Ⓢ 0042 ⚠

US ROUTE 45 (OLD HALF DAY ROAD)		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SUMMARY OF QUANTITIES		3502	49-RS-6	LAKE	33	4
SCALE: SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 60N31				
ILLINOIS FED. AID PROJECT						

* - SPECIALTY ITEM