

SUMMARY OF QUANTITIES			URBAN 100% STATE		CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	WILL COUNTY ROADWAY 0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	170	170				
25200110	SODDING, SALT TOLERANT	SO YD	170	170				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	83	83				
40600300	AGGREGATE (PRIME COAT)	TON	389	389				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	152	152				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	417	417				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	340	340				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	9773	9773				
42001300	PROTECTIVE COAT	SO YD	340	340				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	17113	17113				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	78544	78544				
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	231	231				

SUMMARY OF QUANTITIES			URBAN 100% STATE		CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	WILL COUNTY ROADWAY 0005				
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SO YD	384	384				
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SO YD	154	154				
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	845	845				
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	1408	1408				
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	563	563				
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SO YD	430	430				
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SO YD	716	716				
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SO YD	289	289				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	314	314				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	12	12				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	7	7				
60255500	MANHOLES TO BE ADJUSTED	EACH	8	8				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				

\* SPECIALTY ITEMS

\* SPECIALTY ITEMS  
# NON-PARTICIPATING ITEMS

Rev. 4-8-13

FILE NAME :	USER NAME :	DESIGNED :	REVISED :
DATE :	DATE :	DRAWN :	REVISED :
PLOT SCALE :	CHECKED :	DATE :	REVISED :
PLOT DATE :	DATE :	DATE :	REVISED :

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL 53 (INDEPENDENCE BLVD.)  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	MY-RS-2	WILL	35	3
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT			CONTRACT NO. 60N44	