

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	38	38		
25200110	SODDING, SALT TOLERANT	SO YD	38	38		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	34	34		
X4060120	NON-TRACKING BITUMINOUS MATERIALS (PRIME COAT)	POUND	26,210	26,210		
40600300	AGGREGATE (PRIME COAT)	TON	158	158		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	63	63		
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	1727	1727		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	442	442		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	148	148		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3515	3515		
42001300	PROTECTIVE COAT	SO YD	55	55		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	38	38		

2

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	38825	38825		
44000600	SIDEWALK REMOVAL	SO FT	38	38		
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	875	875		
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	27178	27178		
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	580	580		
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	85	85		
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	55	55		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	9813	9813		

Rev. 4-12-13

FILE NAME :	USER NAME : atdredma	DESIGNED -	REVISED -
PLT SEALE : 100.0000 1/1 in.	CHECKED -	DRAWN -	REVISED -
PLT DATE : 4/3/2012	DATE -		REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

STATE RD. (IL 50 (CICERO AVE.) TO 79TH STREET) SUMMARY OF QUANTITIES

F.A. RTE. 3577	SECTION 2010-158-RS	COUNTY COOK	TOTAL SHEETS 21	SHEET NO. 3
CONTRACT NO. 60N72				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

SCALE: SHEET NO. OF SHEETS STA. TO STA.