

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				ROADWAY 0003		SAFETY 0021	NON PARTICIPATING
				STU	STE	STU	
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	262	-	262	-	-
* 20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	267	-	267	-	-
* 20101100	TREE TRUNK PROTECTION	EACH	70	70	-	-	-
* 20101200	TREE ROOT PRUNING	EACH	70	38	32	-	-
* 20101400	NITROGEN FERTILIZER NUTRIENT	POUND	396	396	-	-	-
* 20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	396	396	-	-	-
* 20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	396	396	-	-	-
20200100	EARTH EXCAVATION	CU YD	16,223	15,239	984	-	-
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	8,923	8,274	649	-	-
20300100	CHANNEL EXCAVATION	CU YD	780	780	-	-	-
20800150	TRENCH BACKFILL	CU YD	4,423	4,423	-	-	-
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	30,085	30,085	-	-	-
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	22,689	22,689	-	-	-
* 25000110	SEEDING, CLASS 1A	ACRE	4.4	4.4	-	-	-
* 25000312	SEEDING, CLASS 4A	ACRE	0.4	0.4	-	-	-
* 25000314	SEEDING, CLASS 4B	ACRE	0.4	0.4	-	-	-
* 25000324	SEEDING, CLASS 5B	ACRE	0.4	0.4	-	-	-
* 25100115	MULCH, METHOD 2	ACRE	4.8	4.8	-	-	-
* 25100630	EROSION CONTROL BLANKET	SQ YD	22,689	22,689	-	-	-
* 25200200	SUPPLEMENTAL WATERING	UNIT	70	70	-	-	-
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	480	480	-	-	-
28000305	TEMPORARY DITCH CHECKS	FOOT	510	510	-	-	-
28000400	PERIMETER EROSION BARRIER	FOOT	7,126	7,126	-	-	-
28000510	INLET FILTERS	EACH	122	122	-	-	-
28100107	STONE RIPRAP, CLASS A4	SQ YD	448	448	-	-	-
28200200	FILTER FABRIC	SQ YD	448	448	-	-	-
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	6,604	6,604	-	-	-
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	30,085	30,085	-	-	-
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	3,882	3,882	-	-	-
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	5,571	-	5,571	-	-
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	83	62	21	-	-
40600300	AGGREGATE (PRIME COAT)	TON	160	137	23	-	-
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	-	-	-

* INDICATES SPECIALTY ITEM

CONTRACT NO. 63745
SECTION 95-00049-00-PV
KANE COUNTY
TOTAL SHEETS 138
SHEET NO. 3
DATE 06/20/12
FILE 110994-SQTY.shp



DESIGNED - DJS	REVISED - PER IDOT 10/19/12
DRAWN - UKS	REVISED - PER ACOE 3/14/13
CHECKED - RWL	REVISED
DATE - 06/20/12	FILE - 110994-SQTY.shp

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: STA. TO STA.

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
4006	95-00049-00-PV	KANE	138	3
CONTRACT NO. 63745				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT N-8003 (095)				