

DATE	BY	FINAL SURVEY	DATE	BY
		NOTED		
		NO. 1		

DATE	BY	ORIGINAL SURVEY	DATE	BY
		NOTED		
		NO. 1		

6	SCHEDULE OF EARTHWORK QUANTITIES (BREAKDOWN)												
STATION	DISTANCE	EARTH EXCAVATION (CUT)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	AGGREGATE SUBGRADE IMPROVEMENT (PGE)	FURNISHED EXCAVATION (FILL)	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	AGGREGATE SUBGRADE IMPROVEMENT (PGE)	FURNISHED EXCAVATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	AGGREGATE SUBGRADE IMPROVEMENT (PGE)	FURNISHED EXCAVATION
(XX+XX)	(FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	AVG. (SQ FT)	AVG. (SQ FT)	AVG. (SQ FT)	AVG. (SQ FT)	(CU FT)	(CU FT)	(CU FT)	(CU FT)
10+72		42	51	0	31								
	28					58	46	0	42	1,610	1,274	0	1,176
11+00		73	40	0	53								
	45					111	34	0	44	4,995	1,530	0	1,958
11+45		149	28	0	34								
	5					137	54	0	32	685	270	0	160
11+50		125	80	0	30								
	1					136	79	0	30	136	79	0	30
11+51		147	77	0	30								
	49					111	53	0	33	5,439	2,597	0	1,593
12+00		75	29	0	35								
	50					74	31	0	39	3,700	1,525	0	1,925
12+50		73	32	0	42								
	36					70	30	0	42	2,502	1,080	0	1,494
12+86		66	28	0	41								
	14					61	42	0	52	847	581	0	721
13+00		55	55	0	62								
	50					63	47	0	61	3,150	2,325	0	3,025
13+50		71	38	0	59								
	50					69	45	0	58	3,450	2,250	0	2,900
14+00		67	52	0	57								
	22					85	41	0	44	1,870	891	0	957
14+22		103	29	0	30								
	28					87	29	0	28	2,436	798	0	784
14+50		71	28	0	26								
	50					74	62	33	38	3,700	3,075	1,650	1,875
15+00		77	95	66	49								
	50					76	96	66	52	3,800	4,800	3,300	2,600
15+50		75	97	66	55								
	12					76	87	66	42	906	1,038	792	498
15+62		76	76	66	28								
	38					74	87	66	44	2,812	3,287	2,508	1,653
16+00		72	97	66	59								
	50					67	97	66	70	3,325	4,850	3,300	3,475
16+50		61	97	66	80								
	50					58	98	67	90	2,875	4,900	3,325	4,475
17+00		54	99	67	99								
	38					66	87	67	63	2,489	3,287	2,527	2,375
17+38		77	74	66	26								
	12					73	75	66	27	876	894	792	318
17+50		69	75	66	27								
	50					50	94	66	57	2,500	4,700	3,300	2,850
18+00		31	113	66	87								
	50					31	66	33	60	1,525	3,275	1,650	2,975
18+50		30	18	0	32								
	4					31	18	0	33	124	72	0	130
18+54		32	18	0	33								
	46					33	18	0	31	1,518	805	0	1,403
19+00		34	17	0	28								
	45					48	18	0	28	2,138	788	0	1,260
19+45		61	18	0	28								
	5					62	18	0	27	310	90	0	133
19+50		63	18	0	25								
	50					80	29	0	23	3,975	1,425	0	1,125
20+00		96	39	0	20								
	40					122	24	0	11	4,880	940	0	420
20+40		148	8	0	1								
	10					149	8	0	1	1,485	80	0	10
20+50		149	8	0	1								
	50					130	17	0	3	6,475	850	0	125
21+00		110	26	0	4								
	33					118	18	0	4	3,894	578	0	116
21+33		126	9	0	3								
	17					118	18	0	3	1,998	298	0	51
21+50		109	26	0	3								
	21					115	18	0	3	2,405	378	0	63