

DATE	
BY	
CHECKED	
SURVEY	
NOTED	
NOTE BOOK	
NO.	

DATE	
BY	
CHECKED	
SURVEY	
NOTED	
NOTE BOOK	
NO.	

6	SCHEDULE OF EARTHWORK QUANTITIES (BREAKDOWN)												
STATION	DISTANCE	EARTH EXCAVATION (CUT)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	AGGREGATE SUBGRADE IMPROVEMENT (PGE)	FURNISHED EXCAVATION (FILL)	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	AGGREGATE SUBGRADE IMPROVEMENT (PGE)	FURNISHED EXCAVATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	AGGREGATE SUBGRADE IMPROVEMENT (PGE)	FURNISHED EXCAVATION
(XX+XX)	(FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	AVG. (SQ FT)	AVG. (SQ FT)	AVG. (SQ FT)	AVG. (SQ FT)	(CU FT)	(CU FT)	(CU FT)	(CU FT)
21+71		120	10	0	3								
	29					142	5	0	3	4,104	145	0	73
22+00		163	0	0	2								
	50					148	7	0	3	7,375	325	0	125
22+50		132	13	0	3								
	50					125	24	0	7	6,250	1,175	0	325
23+00		118	34	0	10								
	35					170	17	0	5	5,933	595	0	175
23+35		221	0	0	0								
	15					204	15	0	7	3,053	218	0	105
23+50		186	29	0	14								
	50					148	38	0	13	7,400	1,875	0	625
24+00		110	46	0	11								
	50					105	43	0	11	5,225	2,150	0	525
24+50		99	40	0	10								
	50					91	42	0	13	4,550	2,100	0	650
25+00		83	44	0	16								
	33					85	33	0	18	2,789	1,089	0	578
25+33		86	22	0	19								
	17					69	32	0	22	1,165	544	0	374
25+50		51	42	0	25								
	50					81	58	0	42	4,050	2,875	0	2,075
26+00		111	73	0	58								
	11					130	37	0	29	1,425	402	0	319
26+11		148	0	0	0								
	39					94	20	0	21	3,666	780	0	800
26+50		40	40	0	41								
	26					40	38	0	37	1,040	975	0	949
26+76		40	35	0	32								
	18					44	29	0	26	792	522	0	468
26+94		48	23	0	20								
	6					49	22	0	18	294	132	0	108
27+00		50	21	0	16								
	35					54	19	0	11	1,890	648	0	368
27+35		58	16	0	5								
	11					58	23	0	6	633	248	0	66
27+46		57	29	0	7								
	4					58	29	0	7	230	116	0	26
27+50		58	29	0	6								
	27					70	24	0	13	1,890	648	0	351
27+77		82	19	0	20								
	23					86	29	0	23	1,978	656	0	518
28+00		90	38	0	25								
	50					117	46	0	31	5,850	2,275	0	1,525
28+50		144	53	0	36								
	33					168	38	0	43	5,544	1,254	0	1,403
28+83		192	23	0	49								
	17					205	43	0	55	3,477	731	0	935
29+00		217	63	0	61								
	50					165	54	0	36	8,250	2,700	0	1,775
29+50		113	45	0	10								
	50					112	45	0	21	5,575	2,225	0	1,025
30+00		110	44	0	31								
	6					96	32	0	30	573	189	0	177
30+06		81	19	0	28								
	44					80	30	0	41	3,498	1,320	0	1,804
30+50		78	41	0	54								
	24					86	28	0	31	2,052	660	0	744
30+74		93	14	0	8								
	26					99	27	0	16	2,561	702	0	416
31+00		104	40	0	24								
	50					121	29	0	17	6,025	1,425	0	825
31+50		137	17	0	9								
	2					137	17	0	9	274	34	0	18
31+52		137	17	0	9								
	48					190	12	0	7	9,120	552	0	312