

FINAL SURVEY	BY	DATE	SURVEYED	NOTED	REMARKS
NO. 1	NO. 2	NO. 3	NO. 4	NO. 5	NO. 6

7	SCHEDULE OF GEOTECHNICAL FABRIC FOR GROUND STABILIZATION (21001000)		
	STATION		AREA (SQ YD)
	FROM	TO	
Washington Street	200+00	4+50	3,832
	4+50	9+50	3,078
	9+50	15+00	3,811
	15+00	20+00	3,005
	20+00	25+00	3,364
	25+00	29+50	3,119
	29+50	34+50	3,368
	34+50	39+50	4,142
	39+50	45+00	3,677
	45+00	50+50	3,700
	50+50	55+00	1,218
	55+00	60+00	
	60+00	63+34	
	16+70	18+50	120
Cedar Lake Road	18+50	22+40	1,036
	PROJECT TOTAL		37,470

8	SCHEDULE OF AGGREGATE SUBGRADE IMPROVEMENT 12" (30300112)		
	STATION		AREA (SQ YD)
	FROM	TO	
Washington Street	200+00	4+50	3,559
	4+50	9+50	2,906
	9+50	15+00	3,598
	15+00	20+00	2,835
	20+00	25+00	3,187
	25+00	29+50	2,952
	29+50	34+50	3,190
	34+50	39+50	3,889
	39+50	45+00	3,478
	45+00	50+50	3,504
	50+50	55+00	1,131
	55+00	60+00	
	60+00	63+34	
	16+70	18+50	91
Cedar Lake Road	18+50	22+40	874
	PROJECT TOTAL		35,194

9	SCHEDULE OF BITUMINOUS MATERIALS (PRIME COAT) (40600100)		
	STATION		VOLUME (GALLON)
	FROM	TO	
Washington Street	200+00	4+50	2,266
	4+50	9+50	1,530
	9+50	15+00	1,902
	15+00	20+00	1,513
	20+00	25+00	1,726
	25+00	29+50	1,600
	29+50	34+50	1,782
	34+50	39+50	2,257
	39+50	45+00	1,958
	45+00	50+50	1,951
	50+50	55+00	674
	55+00	60+00	
	60+00	63+34	
	16+70	18+50	115
Cedar Lake Road	18+50	22+40	774
	PROJECT TOTAL		20,048

10	SCHEDULE OF HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (40600982)		
	STATION		AREA (SQ YD)
	FROM	TO	
Washington Street	200+00	4+50	25
	4+50	9+50	
	9+50	15+00	
	15+00	20+00	
	20+00	25+00	
	25+00	29+50	
	29+50	34+50	
	34+50	39+50	
	39+50	45+00	
	45+00	50+50	
	50+50	55+00	13
	55+00	60+00	
	60+00	63+34	
	16+70	18+50	25
Cedar Lake Road	18+50	22+40	
	PROJECT TOTAL		63

11	SCHEDULE OF TEMPORARY RAMP (40600990)		
	STATION		AREA (SQ YD)
	FROM	TO	
Washington Street	200+00	4+50	23
	4+50	9+50	20
	9+50	15+00	54
	15+00	20+00	20
	20+00	25+00	57
	25+00	29+50	48
	29+50	34+50	43
	34+50	39+50	56
	39+50	45+00	54
	45+00	50+50	69
	50+50	55+00	18
	55+00	60+00	
	60+00	63+34	
	16+70	18+50	
Cedar Lake Road	18+50	22+40	
	PROJECT TOTAL		462

12	SCHEDULE OF PROTECTIVE COAT (42001300)		
	STATION		AREA (SQ YD)
	FROM	TO	
Washington Street	200+00	4+50	977
	4+50	9+50	861
	9+50	15+00	871
	15+00	20+00	891
	20+00	25+00	789
	25+00	29+50	713
	29+50	34+50	818
	34+50	39+50	868
	39+50	45+00	934
	45+00	50+50	757
	50+50	55+00	46
	55+00	60+00	
	60+00	63+34	
	16+70	18+50	182
Cedar Lake Road	18+50	22+40	424
	PROJECT TOTAL		9,131

13	SCHEDULE OF HOT-MIX ASPHALT BINDER COURSE, IL- 19.0, N70 (40603085)					
STREET	STATION		AREA @ 6- 1/4" (SQ YD)	AREA @ 8- 1/4" (SQ YD)	TOTAL VOLUME (SQ YD-IN)	WEIGHT (115 LB/SQ YD-IN) (TON)
	FROM	TO				
Washington Street	200+00	4+50	469	2,493	23,499	1,352
	4+50	9+50		2,492	20,562	1,183
	9+50	15+00		3,137	25,883	1,489
	15+00	20+00		2,428	20,028	1,152
	20+00	25+00		2,758	22,757	1,309
	25+00	29+50		2,546	21,002	1,208
	29+50	34+50		2,759	22,760	1,309
	34+50	39+50	661	2,669	26,155	1,504
	39+50	45+00		3,003	24,778	1,425
	45+00	50+50		3,027	24,976	1,437
	50+50	55+00	860	129	6,442	371
	55+00	60+00				
	60+00	63+34				
	Cedar Lake Road	16+70	18+50			
18+50		22+40	277	336	4,502	259
PROJECT TOTAL					13,998	

14	SCHEDULE OF HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (40603335)				
STREET	STATION		AREA @ 2-1/2"	TOTAL VOLUME	WEIGHT
	FROM	TO	(SQ YD)	(SQ YD-IN)	(112 LB/SQ YD-IN) (TON)
Washington Street	200+00	4+50	665	1,662	94
	4+50	9+50	68	169	10
	9+50	15+00	39	98	6
	15+00	20+00	112	281	16
	20+00	25+00	140	350	20
	25+00	29+50	143	358	21
	29+50	34+50	252	630	36
	34+50	39+50	517	1,292	73
	39+50	45+00	311	778	44
	45+00	50+50	268	670	38
	50+50	55+00	52	130	8
		55+00	60+00		
Cedar Lake Road	60+00	63+34			
	16+70	18+50	29	73	5
	18+50	22+40	428	1,069	60
PROJECT TOTAL					431

15	SCHEDULE OF HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 (40603340)				
STREET	STATION		AREA @ 2-1/4"	TOTAL VOLUME	WEIGHT (112 LB/SQ YD-IN)
	FROM	TO	(SQ YD)	(SQ YD-IN)	(TON)
Washington Street	200+00	4+50	4,521	10,172	570
	4+50	9+50	2,492	5,608	315
	9+50	15+00	3,137	7,059	396
	15+00	20+00	2,428	5,462	306
	20+00	25+00	2,758	6,206	348
	25+00	29+50	2,546	5,728	321
	29+50	34+50	2,759	6,207	348
	34+50	39+50	3,331	7,494	420
	39+50	45+00	3,003	6,758	379
	45+00	50+50	3,027	6,812	382
	50+50	55+00	989	2,226	125
	55+00	60+00			
60+00	63+34				
Cedar Lake Road	16+70	18+50	1,003	2,257	127
	18+50	22+40	2,783	6,262	351
PROJECT TOTAL					4,388

ORIGINAL SURVEY	BY	DATE	SURVEYED	NOTED	REMARKS
NO. 1	NO. 2	NO. 3	NO. 4	NO. 5	NO. 6



460 E Devon Ave, Suite 300
Itasca, Illinois 60143
Tel: 630.773.3900 Fax: 630.773.3975
www.civiltechinc.com

DESIGNED - PK
DRAWN - JRR
CHECKED - RTM
DATE - 12/17/2012
REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SHEET NO. 9 OF 16 SHEETS

F.A.U. RFE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0187	05-00121-07-WR	LAKE	223	19
CONTRACT NO. 63765				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				